DocuSign Envelope ID: 46728D73-D621-4703-A608-BB8F5C076F09

4/04/06

COMPUTED BY: MDH DATE: 03/06/15
CHECKED BY: JEB DATE: 03/06/15

PROJECT REFERENCE NO.	SHEET NO.
17BP.14.R.85	3B-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SUMMARY OF EARTHWORK

STATION	STATION	UNCL. EXCAV.	EMBANK. +15%	BORROW	WASTE
-L- 13+00.00	-L- 15+25.00	4	150	146	0
SUBTOTALS:		4	150	146	0
SUBTOTALS:					
SUBTOTALS:					
PROJECT TOTALS:		4	150	146	0
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT				7	
GRAND TOTALS:		4	150	153	0
SAY:		5	155	155	0

EST. GRANULAR MATERIAL = 50 CY (CONTINGENCY)
EST. GEOTEXTILE FOR SOIL STABILIZATION = 50 SY (CONTINGENCY)
EST. UNDERCUT EXCAVATION = 50 CY (CONTINGENCY)
EST. INCIDENTAL STONE BASE = 50 TONS (CONTINGENCY)

NOTE:

Earthwork quantities are calculated by the Roadway Design Unit. These earthwork quantities are based in part on subsurface data provided by the Geotechnical Engineering Unit.

Approximate quantities only. Unclassified Excavation, Borrow Excavation, Clearing & Grubbing, and Removal & Breakup of existing pavement will be paid at the lump sum price for "Grading".

Excavation for proposed culvert will be paid at the lump sum price for "Culvert Excavation".

RIGHT OF WAY AREA DATA

PARCEL NO.	PROPERTY OWNERS NAMES	TOTAL ACREAGE	AREA TAKEN	AREA REMAINING RT.	AREA REMAINING LT.	CONST. EASE.	DRAINAGE UTILITY EASE.	TEMP. DRAINAGE EASE.
1	WINSTON WESTMORELAND	0.000	0.000	0.000	0.000	0.000	0.000	0.000
2	ISIAH NEWMAN & SHARON DAVENPORT	0.000	0.000	0.000	0.000	0.000	0.000	0.000
3	LYNDSAY DAVENPORT & SHARON DAVENPORT	0.000	0.000	0.000	0.000	0.000	0.000	0.000
4	SHARON DAVENPORT	0.000	0.000	0.000	0.000	0.000	0.000	0.000
5	DONALD HELTON	0.054	0.000	0.054	0.000	0.000	0.054	0.000
6	WINSTON WESTMORELAND	0.000	0.000	0.000	0.000	0.000	0.000	0.000

Plans Prepared By:
DRMP
DRMP, INC.
4235 SOUTH STREAM BLVD., SUITE 150
CHARLOTTE, NC 28217
NC LICENSE NO.: C-2213 (704) 332-2289

1/3/2019
C:\Projects\Proj\190065_Rdy_psh_3B-1.dgn
Mthone