

PROJECT NO.	SHEET NO.	TOTAL NO.
2026CPT.14.08.10441, 50943.3.7	10	

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1297000000-E 1½" MILLING	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2591000000-E 4" CONCRETE SIDEWALK	2612500000-N REMOVE AND REPLACE CONCRETE CURB RAMPS	2759000000-N REMOVE EXISTING CURB RAMP	2815000000-N ADJ. OF DROP INLET	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	4600000000-N AUDIBLE WARNING DEVICE	TEMPORARY CURB RAMPS	TEMPORARY SILT FENCE	SAFETY FENCE	1/4" HARDWARE CLOTH	SEED & MULCHING	RESPONSE FOR EROSION CONTROL	CONCRETE WASHOUT STRUCTURE	7444000000-E INDUCTIVE LOOP SAWCUT	7456100000-E LEAD-IN CABLE (14-2)
								MI	FT			SY	TONS	TONS	TONS	LF	SY	EA	EA	EA	EA	EA	EA	EA	LF	LF	LF	AC	EA	EA	LF	LF
2026CPT.14.08.10441	Haywood	1	US-19	FROM SR 1307 TO MM 8.25	1	5		0.460	64	7.790	8.250	17,272	1,451	122	751					17	15	6									1,065.00	300.00
TOTAL FOR MAP NO. 1								0.460				17,272	1,451	122	751					17	15	6									1,065.00	300.00
2026CPT.14.08.10441	Haywood	2	US-19	ALONG US 19 FROM MM 8.55 TO S LAKESHORE DR		2	MD	3.260	60	8.550	11.810	114,752	9,639	710	2,952					68	3	6									904.00	21.00
TOTAL FOR MAP NO. 2								3.260				114,752	9,639	710	2,952					68	3	6									904.00	21.00
TOTAL FOR PROJ NO. 2026CPT.14.08.10441								3.720				132,024	11,090	832	3,703					85	18	12									1,969.00	321.00
50943.3.7	Haywood	1,2	US-19	FROM SR 1307 TO S LAKESHORE DR		2	2WD	4.020	20	7.790	11.810					169	63	4	7				4	2	150	150	60	0.50	5	5		
TOTAL FOR MAP NO. 5								4.020								169	63	4	7				4	2	150	150	60	0.50	5	5		
TOTAL FOR PROJ NO. 50943.3.7								4.020								169	63	4	7				4	2	150	150	60	0.50	5	5		
GRAND TOTAL								7.740				132,024	11,090	832	3,703	169	63	4	7	85	18	12	4	2	150	150	60	0.50	5	5	1,969.00	321.00