

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.14.R.103 (44-0192)	1	12

**STATE OF NORTH CAROLINA**  
**DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**

# STRUCTURE SUBSURFACE INVESTIGATION

PROJ. REFERENCE NO. 17BP.14.R.103 F.A. PROJ. 44-0192  
COUNTY HENDERSON  
PROJECT DESCRIPTION BRIDGE NO. 192 OVER MUD CREEK  
ON SR 1126  
  
SITE DESCRIPTION \_\_\_\_\_  
\_\_\_\_\_  
\_\_\_\_\_

## CONTENTS

<u>SHEET</u>	<u>DESCRIPTION</u>
1	TITLE SHEET
2-2A	LEGEND
3	SITE PLAN
4-6	BORE LOG & CORE REPORTS
7	CORE PHOTOGRAPHS
8-9	BORE LOG & CORE REPORTS
10	CORE PHOTOGRAPHS
11	BORE LOG REPORT
12	SITE PHOTOGRAPHS

## PERSONNEL

R. RIVENBARK  
M. BAHIRADHAN  
S. BUCHANAN  
RED DOG DRLLG.

INVESTIGATED BY RED DOG DRLLG.

CHECKED BY M. BAHIRADHAN

SUBMITTED BY SCHNABEL ENG.

DATE JUNE 2014

## CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WERE MADE FOR THE PURPOSE OF STUDY, PLANNING, AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N.C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL ENGINEERING UNIT AT (919) 707-6850. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA ARE PART OF THE CONTRACT.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION, AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE, OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N.C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

DRAWN BY: S. BUCHANAN

**NORTH CAROLINA DEPARTMENT OF TRANSPORTATION**  
**DIVISION OF HIGHWAYS**  
**GEOTECHNICAL ENGINEERING UNIT**  
**SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS**

SOIL DESCRIPTION										GRADATION																																																																																																																																		
<p>SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED, OR WEATHERED EARTH MATERIALS THAT CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND YIELD LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM. BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE:</p> <p style="text-align: center;"><i>VERY STIFF, GRAY, SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6</i></p>										<p>WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE. UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.</p>																																																																																																																																		
										<b>ANGULARITY OF GRAINS</b>																																																																																																																																		
<p>THE ANGULARITY OR ROUNDNESS OF SOIL GRAINS IS DESIGNATED BY THE TERMS <b>ANGULAR</b>, <b>SUBANGULAR</b>, <b>SUBROUNDED</b>, OR <b>ROUNDED</b>.</p>										<b>MINERALOGICAL COMPOSITION</b>																																																																																																																																		
										<p>MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.</p>																																																																																																																																		
SOIL LEGEND AND AASHTO CLASSIFICATION										COMPRESSION																																																																																																																																		
<p>GENERAL CLASS.</p> <table border="1" style="width: 100%; text-align: center;"><thead><tr><th colspan="4">GRANULAR MATERIALS (≤ 35% PASSING #200)</th><th colspan="4">SILT-CLAY MATERIALS (&gt; 35% PASSING #200)</th><th colspan="4">ORGANIC MATERIALS</th></tr><tr><th>A-1</th><th>A-3</th><th>A-2</th><th></th><th>A-4</th><th>A-5</th><th>A-6</th><th>A-7</th><th>A-1, A-2</th><th>A-4, A-5</th><th></th><th></th></tr><tr><th>GROUP CLASS.</th><th>A-1-a</th><th>A-1-b</th><th>A-2-4</th><th>A-2-5</th><th>A-2-6</th><th>A-2-7</th><th></th><th>A-7-5</th><th>A-7-6</th><th>A-3</th><th></th></tr></thead><tbody><tr><td>SYMBOL</td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>% PASSING</td><td>50 MX</td><td>30 MX</td><td>50 MX</td><td>51 MN</td><td>35 MX</td><td>35 MX</td><td>35 MX</td><td>35 MX</td><td>36 MN</td><td>36 MN</td><td>36 MN</td></tr><tr><td>LIQUID LIMIT</td><td>6 MX</td><td>NP</td><td>40 MX</td><td>41 MN</td><td>40 MX</td><td>41 MN</td><td>40 MX</td><td>41 MN</td><td>40 MX</td><td>41 MN</td><td>41 MN</td></tr><tr><td>PLASTIC INDEX</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr><tr><td>GROUP INDEX</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td><td>0</td></tr><tr><td>USUAL TYPES OF MAJOR MATERIALS</td><td>STONE FRAGS, GRAVEL, AND SAND</td><td>FINE SAND</td><td>SILTY OR CLAYEY GRAVEL AND SAND</td><td>SILTY SOILS</td><td>CLAYEY SOILS</td><td></td><td></td><td></td><td></td><td></td><td></td></tr><tr><td>GEN. RATING AS A SUBGRADE</td><td colspan="4">EXCELLENT TO GOOD</td><td colspan="4">FAIR TO POOR</td><td>FAIR TO POOR</td><td>POOR</td><td>UNSATURABLE</td><td></td></tr></tbody></table>										GRANULAR MATERIALS (≤ 35% PASSING #200)				SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS				A-1	A-3	A-2		A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5			GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7		A-7-5	A-7-6	A-3		SYMBOL												% PASSING	50 MX	30 MX	50 MX	51 MN	35 MX	35 MX	35 MX	35 MX	36 MN	36 MN	36 MN	LIQUID LIMIT	6 MX	NP	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	41 MN	PLASTIC INDEX	0	0	0	0	0	0	0	0	0	0	0	GROUP INDEX	0	0	0	0	0	0	0	0	0	0	0	USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS							GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD				FAIR TO POOR				FAIR TO POOR	POOR	UNSATURABLE		<p>SLIGHTLY COMPRESSIBLE MODERATELY COMPRESSIBLE HIGHLY COMPRESSIBLE</p> <p>LIQUID LIMIT LESS THAN 31 LIQUID LIMIT EQUAL TO 31-50 LIQUID LIMIT GREATER THAN 50</p>									
										GRANULAR MATERIALS (≤ 35% PASSING #200)				SILT-CLAY MATERIALS (> 35% PASSING #200)				ORGANIC MATERIALS																																																																																																																										
A-1	A-3	A-2		A-4	A-5	A-6	A-7	A-1, A-2	A-4, A-5																																																																																																																																			
GROUP CLASS.	A-1-a	A-1-b	A-2-4	A-2-5	A-2-6	A-2-7		A-7-5	A-7-6	A-3																																																																																																																																		
SYMBOL																																																																																																																																												
% PASSING	50 MX	30 MX	50 MX	51 MN	35 MX	35 MX	35 MX	35 MX	36 MN	36 MN	36 MN																																																																																																																																	
LIQUID LIMIT	6 MX	NP	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	40 MX	41 MN	41 MN																																																																																																																																	
PLASTIC INDEX	0	0	0	0	0	0	0	0	0	0	0																																																																																																																																	
GROUP INDEX	0	0	0	0	0	0	0	0	0	0	0																																																																																																																																	
USUAL TYPES OF MAJOR MATERIALS	STONE FRAGS, GRAVEL, AND SAND	FINE SAND	SILTY OR CLAYEY GRAVEL AND SAND	SILTY SOILS	CLAYEY SOILS																																																																																																																																							
GEN. RATING AS A SUBGRADE	EXCELLENT TO GOOD				FAIR TO POOR				FAIR TO POOR	POOR	UNSATURABLE																																																																																																																																	
<p>PI OF A-7-5 SUBGROUP IS ≤ LL - 30 ; PI OF A-7-6 SUBGROUP IS &gt; LL - 30</p>										<b>PERCENTAGE OF MATERIAL</b>																																																																																																																																		
										<table border="1" style="width: 100%; text-align: center;"><thead><tr><th>ORGANIC MATERIAL</th><th>GRANULAR SOILS</th><th>SILT - CLAY SOILS</th><th>OTHER MATERIAL</th></tr></thead><tbody><tr><td>TRACE OF ORGANIC MATTER</td><td>2 - 3%</td><td>3 - 5%</td><td>TRACE</td></tr><tr><td>LITTLE ORGANIC MATTER</td><td>3 - 5%</td><td>5 - 12%</td><td>LITTLE</td></tr><tr><td>MODERATELY ORGANIC</td><td>5 - 10%</td><td>12 - 20%</td><td>SOME</td></tr><tr><td>HIGHLY ORGANIC</td><td>&gt;10%</td><td>&gt;20%</td><td>HIGHLY</td></tr></tbody></table>										ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																																																																					
ORGANIC MATERIAL	GRANULAR SOILS	SILT - CLAY SOILS	OTHER MATERIAL																																																																																																																																									
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																																																																																																									
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																																																																																																									
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																																																																																																									
HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																																																																																																									
<p>GROUND WATER</p> <p> WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING</p> <p> STATIC WATER LEVEL AFTER 24 HOURS</p> <p> PERCHED WATER, SATURATED ZONE, OR WATER BEARING STRATA</p> <p> SPRING OR SEEP</p>										<b>MISCELLANEOUS SYMBOLS</b>																																																																																																																																		
										<table border="1" style="width: 100%; text-align: center;"><thead><tr><th>ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION</th><th>TEST BORING</th><th>TEST BORING W/ CORE</th></tr></thead><tbody><tr><td>SOIL SYMBOL</td><td></td><td></td></tr><tr><td>ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT</td><td></td><td></td></tr><tr><td>INFERRED SOIL BOUNDARY</td><td></td><td></td></tr><tr><td>INFERRED ROCK LINE</td><td></td><td></td></tr><tr><td>ALLUVIAL SOIL BOUNDARY</td><td></td><td></td></tr><tr><td>DIP &amp; DIP DIRECTION OF ROCK STRUCTURES</td><td></td><td></td></tr><tr><td></td><td></td><td></td></tr></tbody></table>										ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	TEST BORING	TEST BORING W/ CORE	SOIL SYMBOL			ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT			INFERRED SOIL BOUNDARY			INFERRED ROCK LINE			ALLUVIAL SOIL BOUNDARY			DIP & DIP DIRECTION OF ROCK STRUCTURES																																																																																																						
ROADWAY EMBANKMENT (RE) WITH SOIL DESCRIPTION	TEST BORING	TEST BORING W/ CORE																																																																																																																																										
SOIL SYMBOL																																																																																																																																												
ARTIFICIAL FILL (AF) OTHER THAN ROADWAY EMBANKMENT																																																																																																																																												
INFERRED SOIL BOUNDARY																																																																																																																																												
INFERRED ROCK LINE																																																																																																																																												
ALLUVIAL SOIL BOUNDARY																																																																																																																																												
DIP & DIP DIRECTION OF ROCK STRUCTURES																																																																																																																																												
CONSISTENCY OR DENSENESS										ABBREVIATIONS																																																																																																																																		
<p>PRIMARY SOIL TYPE</p> <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>COMPACTNESS OR CONSISTENCY</th><th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th><th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT<sup>2</sup>)</th></tr></thead><tbody><tr><td>GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td><td>VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE</td><td>&lt;4 4 TO 10 10 TO 30 30 TO 50 &gt;50</td><td>N/A</td></tr><tr><td>GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td><td>VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD</td><td>&lt;2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 &gt;30</td><td>&lt;0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 &gt;4</td></tr></tbody></table>										COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A	GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4	<p>AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F - FINE FOSS - FOSSILIFEROUS FRAC - FRACTURED, FRACTURES FRAGS - FRAGMENTS HI - HIGHLY</p> <p>MED. - MEDIUM MICA - MICACEOUS MOD. - MODERATELY NP - NON PLASTIC ORG. - ORGANIC PMT - PRESSUREMETER TEST SAP. - SAPROLITIC SD. - SAND, SANDY SL. - SILT, SILTY SLI. - SLIGHTLY TCR - TRICONE REFUSAL w - MOISTURE CONTENT V - VERY</p> <p>YST - VANE SHEAR TEST WEA. - WEATHERED γ - UNIT WEIGHT γ<sub>d</sub> - DRY UNIT WEIGHT</p> <p style="text-align: center;"><b>SAMPLE ABBREVIATIONS</b></p> <p>S - BULK SS - SPLIT SPOON ST - SHELBY TUBE RS - ROCK RT - RECOMPACTED TRIAXIAL CBR - CALIFORNIA BEARING RATIO</p>																																																																																																																							
										COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT <sup>2</sup> )																																																																																																																																
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE LOOSE MEDIUM DENSE DENSE VERY DENSE	<4 4 TO 10 10 TO 30 30 TO 50 >50	N/A																																																																																																																																									
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT SOFT MEDIUM STIFF STIFF VERY STIFF HARD	<2 2 TO 4 4 TO 8 8 TO 15 15 TO 30 >30	<0.25 0.25 TO 0.50 0.5 TO 1.0 1 TO 2 2 TO 4 >4																																																																																																																																									
<p>TEXTURE OR GRAIN SIZE</p> <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>U.S. STD. SIEVE SIZE OPENING (MM)</th><th>4</th><th>10</th><th>40</th><th>60</th><th>200</th><th>270</th></tr></thead><tbody><tr><td></td><td>4.76</td><td>2.00</td><td>0.42</td><td>0.25</td><td>0.075</td><td>0.053</td></tr></tbody></table>										U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270		4.76	2.00	0.42	0.25	0.075	0.053	<p>BOULDER (BLDR.) COBBLE (COB.) GRAVEL (GR.) COARSE SAND (CSE. SD.) FINE SAND (F SD.) SILT (SL.) CLAY (CL.)</p> <p>GRAIN SIZE: 305, 75, 2.0, 0.25, 0.05, 0.005</p>																																																																																																																				
										U.S. STD. SIEVE SIZE OPENING (MM)	4	10	40	60	200	270																																																																																																																												
	4.76	2.00	0.42	0.25	0.075	0.053																																																																																																																																						
<b>SOIL MOISTURE - CORRELATION OF TERMS</b>																																																																																																																																												
<p>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</p> <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>FIELD MOISTURE DESCRIPTION</th><th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th></tr></thead><tbody><tr><td>- SATURATED - (SAT.)</td><td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td></tr><tr><td>- WET - (W)</td><td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td></tr><tr><td>- MOIST - (M)</td><td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td></tr><tr><td>- DRY - (D)</td><td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td></tr></tbody></table>										FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE	<p><b>EQUIPMENT USED ON SUBJECT PROJECT</b></p> <table border="1" style="width: 100%; text-align: center;"><thead><tr><th>DRILL UNITS:</th><th>ADVANCING TOOLS:</th><th>HAMMER TYPE:</th></tr></thead><tbody><tr><td><input type="checkbox"/> MOBILE B-____</td><td><input type="checkbox"/> CLAY BITS</td><td><input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL</td></tr><tr><td><input type="checkbox"/> BK-51</td><td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td><td rowspan="2">CORE SIZE: <input type="checkbox"/> -B____ <input checked="" type="checkbox"/> -N 02____ <input type="checkbox"/> -H____</td></tr><tr><td><input type="checkbox"/> CME-45C</td><td><input type="checkbox"/> 8" HOLLOW AUGERS</td></tr><tr><td><input type="checkbox"/> CME-550</td><td><input type="checkbox"/> HARD FACED FINGER BITS</td><td rowspan="2">HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST</td></tr><tr><td><input type="checkbox"/> PORTABLE HOIST</td><td><input type="checkbox"/> TUNG-CARBIDE INSERTS</td></tr><tr><td><input checked="" type="checkbox"/> CME 45</td><td><input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td><td></td></tr><tr><td><input type="checkbox"/> _____</td><td><input type="checkbox"/> TRICONE _____ * STEEL TEETH</td><td></td></tr><tr><td><input type="checkbox"/> _____</td><td><input checked="" type="checkbox"/> TRICONE 3 _____ * TUNG-CARB.</td><td></td></tr><tr><td><input type="checkbox"/> _____</td><td><input checked="" type="checkbox"/> CORE BIT</td><td></td></tr><tr><td><input type="checkbox"/> _____</td><td><input checked="" type="checkbox"/> HOLLOW STEM AUGERS</td><td></td></tr></tbody></table>										DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:	<input type="checkbox"/> MOBILE B-____	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL	<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE: <input type="checkbox"/> -B____ <input checked="" type="checkbox"/> -N 02____ <input type="checkbox"/> -H____	<input type="checkbox"/> CME-45C	<input type="checkbox"/> 8" HOLLOW AUGERS	<input type="checkbox"/> CME-550	<input type="checkbox"/> HARD FACED FINGER BITS	HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST	<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS	<input checked="" type="checkbox"/> CME 45	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER		<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * STEEL TEETH		<input type="checkbox"/> _____	<input checked="" type="checkbox"/> TRICONE 3 _____ * TUNG-CARB.		<input type="checkbox"/> _____	<input checked="" type="checkbox"/> CORE BIT		<input type="checkbox"/> _____	<input checked="" type="checkbox"/> HOLLOW STEM AUGERS																																																																																	
										FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																																																	
- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																																																											
- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																																																											
- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																																																											
- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																																																											
DRILL UNITS:	ADVANCING TOOLS:	HAMMER TYPE:																																																																																																																																										
<input type="checkbox"/> MOBILE B-____	<input type="checkbox"/> CLAY BITS	<input checked="" type="checkbox"/> AUTOMATIC <input type="checkbox"/> MANUAL																																																																																																																																										
<input type="checkbox"/> BK-51	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	CORE SIZE: <input type="checkbox"/> -B____ <input checked="" type="checkbox"/> -N 02____ <input type="checkbox"/> -H____																																																																																																																																										
<input type="checkbox"/> CME-45C	<input type="checkbox"/> 8" HOLLOW AUGERS																																																																																																																																											
<input type="checkbox"/> CME-550	<input type="checkbox"/> HARD FACED FINGER BITS	HAND TOOLS: <input type="checkbox"/> POST HOLE DIGGER <input type="checkbox"/> HAND AUGER <input type="checkbox"/> SOUNDING ROD <input type="checkbox"/> VANE SHEAR TEST																																																																																																																																										
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> TUNG-CARBIDE INSERTS																																																																																																																																											
<input checked="" type="checkbox"/> CME 45	<input checked="" type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER																																																																																																																																											
<input type="checkbox"/> _____	<input type="checkbox"/> TRICONE _____ * STEEL TEETH																																																																																																																																											
<input type="checkbox"/> _____	<input checked="" type="checkbox"/> TRICONE 3 _____ * TUNG-CARB.																																																																																																																																											
<input type="checkbox"/> _____	<input checked="" type="checkbox"/> CORE BIT																																																																																																																																											
<input type="checkbox"/> _____	<input checked="" type="checkbox"/> HOLLOW STEM AUGERS																																																																																																																																											
PLASTICITY										COLOR																																																																																																																																		
<p>NONPLASTIC LOW PLASTICITY MED. PLASTICITY HIGH PLASTICITY</p>										<p>PLASTICITY INDEX (PI)</p> <p>0-5 6-15 16-25 26 OR MORE</p>																																																																																																																																		
										<p>DRY STRENGTH</p> <p>VERY LOW SLIGHT MEDIUM HIGH</p>																																																																																																																																		
<p>DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YELLOW-BROWN, BLUE-GRAY). MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.</p>																																																																																																																																												

		PROJECT REFERENCE NO. 17BP.14.R.103 (44-0192)	SHEET NO. 2A OF 12
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL ENGINEERING UNIT SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS			
ROCK DESCRIPTION		TERMS AND DEFINITIONS	
<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT IF TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p>ALLUVIUM (ALLUV.) - SOILS THAT HAVE BEEN TRANSPORTED BY WATER. AQUIFER - A WATER BEARING FORMATION OR STRATA. ARENACEOUS - APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS - APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN - GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) - SOILS THAT CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM - ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) - TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE - A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP - THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) - THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT - A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE - A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT - ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (FP) - LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) - A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT - FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE - A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS - A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) - IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER - WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL (RES.) SOIL - SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (RQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) - RESIDUAL SOIL THAT RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL - AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, THAT HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRUDED ROCKS. SLICKENSIDE - POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) - NUMBER OF BLOWS (N OR BPF) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS PENETRATION EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. STRATA CORE RECOVERY (SRC) - TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (SRQD) - A MEASURE OF ROCK QUALITY DESCRIBED BY TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (TS.) - SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>	
	NON-COASTAL PLAIN MATERIAL THAT WOULD YIELD SPT N VALUES > 100 BLOWS PER FOOT IF TESTED.		
	FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.		
	FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.		
	COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.		
WEATHERING			
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.		
VERY SLIGHT (V SL.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN. CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.		
SLIGHT (SL.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.		
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.		
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL</i>		
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &gt; 100 BPF</i>		
VERY SEVERE (V SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES &lt; 100 BPF</i>		
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.		
ROCK HARDNESS			
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.		
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.		
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.		
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PIECES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.		
SOFT	CAN BE GROOVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.		
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.		
FRACTURE SPACING		BEDDING	
TERM	SPACING	TERM	THICKNESS
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
INDURATION			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.		
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.		
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.		
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.		
		BENCH MARK: BL-2, -EL- STA. 12+95.29, OFFSET 13.61' LT, N 565544.0692, E 954793.5586 ELEVATION: 2137.76 FT.	
		NOTES: FIAD = FILLED IMMEDIATELY AFTER DRILLING	

APPROXIMATE SKEW OF  
BRIDGE AT STA. 13+00: 38.3° NW


PROJECT REFERENCE NO.	SHEET
17BP.14.R.103 (44-0192)	3 OF 12
<b>SITE PLAN</b>	
0 20 40 FEET	

BM #2, EL = 2139.46'  
-BL- STA. 8+43.13,  
OFFSET 12.74' RT  
NAIL IN BASE OF  
12" WALNUT

BM #1, EL = 2136.62'  
-BL- STA. 8+59.48,  
OFFSET 37.22' LT  
NAIL IN BASE OF  
UTILITY POLE

BL-2, EL = 2137.76'  
N 565544.0692,  
E 954793.5586  
-EL- STA. 12+95.29,  
OFFSET 13.61' RT

C:\Users\skittis\Desktop\NC\_DOT\_8.5x11\_TS.dgn



DRAWING SOURCE:  
440192\_NCDOT\_FS.DGN  
B440192\_RDY\_DSN.DGN



# NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

SHEET 4 OF 12

WBS 17BP.14.R.103		TIP 44-0192		COUNTY HENDERSON		GEOLOGIST S. Buchanan						
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126							GROUND WTR (ft)					
BORING NO. EB1-A		STATION 12+90		OFFSET 9 ft LT		ALIGNMENT -L-		0 HR. 9.8				
COLLAR ELEV. 2,138.6 ft		TOTAL DEPTH 23.6 ft		NORTHING 565,556		EASTING 954,755		24 HR. FIAD				
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45				DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER M. Seiler		START DATE 05/15/14		COMP. DATE 05/15/14		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		ELEV. (ft) DEPTH (ft)
2140												
	2,137.6	1.0	1	1	1							2,138.6 GROUND SURFACE 0.0
	2,136.1	2.5	1	2	1							2,137.6 ARTIFICIAL FILL 1.0
2135	2,134.6	4.0	2	1	1							ASPHALT AND STONE BASE
	2,133.1	5.5	WOH	WOH	WOH							ALLUVIAL
	2,131.6	7.0	WOH	WOH	WOH							BROWN, CLAYEY FINE TO MEDIUM GRAINED SAND, WITH TRACE ROOTS AND FINE GRAINED GRAVEL
2130	2,130.1	8.5	WOH	WOH	WOH							AT 5.5FT: GRAYISH BROWN
			WOH	WOH	WOH							
			WOH	WOH	WOH							
2125	2,125.1	13.5	5	11	16							2,126.1 RESIDUAL 12.5
												ORANGISH BROWN, SILTY FINE TO COARSE GRAINED SAND, WITH SOME QUARTZ GRAVEL
2120	2,120.1	18.5	50	50/0.3								2,119.3 AT 14.0FT TO 16.5FT: AUGERS GRINDING 19.3
												WEATHERED ROCK (GNEISS)
2115	2,115.1	23.5	60/0.1									2,115.1 23.5
												2,115.0 CRYSTALLINE ROCK 23.6
												(GNEISS)
												Boring Terminated with Standard Penetration Test Refusal at Elevation 2,115.0 ft in Crystalline Rock (Gneiss)



WBS 17BP.14.R.103				TIP 44-0192				COUNTY HENDERSON				GEOLOGIST S. Buchanan					
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126												GROUND WTR (ft)					
BORING NO. EB1-B				STATION 12+86				OFFSET 8 ft RT				ALIGNMENT -L-				0 HR. 16.1	
COLLAR ELEV. 2,138.7 ft				TOTAL DEPTH 39.8 ft				NORTHING 565,534				EASTING 954,796				24 HR. FIAD	
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45								DRILL METHOD SPT Core Boring				HAMMER TYPE Automatic					
DRILLER M. Seiler				START DATE 05/14/14				COMP. DATE 05/14/14				SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	MOI	LOG	SOIL AND ROCK DESCRIPTION		DEPTH (ft)	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100				ELEV. (ft)		DEPTH (ft)	
2140																	
	2,137.7	1.0												2,138.7	GROUND SURFACE	0.0	
	2,136.2	2.5	2	2	1									2,137.7	ARTIFICIAL FILL	1.0	
2135	2,134.7	4.0	1	2	1									2,137.3	ASPHALT AND STONE BASE	1.4	
	2,133.2	5.5	1	0	1										ROADWAY EMBANKMENT		
	2,131.7	7.0	WOH	WOH	WOH										BROWNISH BLACK AND WHITE, CLAYEY SILT, WITH LITTLE ROCK FRAGMENTS		
2130	2,130.2	8.5	WOH	WOH	WOH										ALLUVIAL		
			WOH	WOH	WOH										BROWN AND BLACK, CLAYEY FINE GRAINED SAND, WITH LITTLE SILT AND COARSE GRAINED SAND		
2125	2,125.2	13.5												2,126.9		11.8	
			5	7	10									2,124.4	ALLUVIAL		
2120	2,120.2	18.5												2,122.2	GRAY AND BLACK, SILTY FINE GRAINED SAND	14.3	
															RESIDUAL	16.5	
															ORANGISH BROWN AND WHITE, SILTY FINE TO COARSE GRAINED SAND, WITH SOME FINE TO COARSE GRAINED GRAVEL		
2115	2,115.2	23.5												2,115.2	WEATHERED ROCK (GNEISS)	23.5	
2110															CRYSTALLINE ROCK (GNEISS)		
															REC = 50%, RQD = 10%		
2105																	
2100																	
														2,098.9	Boring Terminated at Elevation 2,098.9 ft in Crystalline Rock (Gneiss)	39.8	




# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

SHEET 6 OF 12

WBS 17BP.14.R.103		TIP 44-0192		COUNTY HENDERSON		GEOLOGIST S. Buchanan						
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126							GROUND WTR (ft)					
BORING NO. EB1-B		STATION 12+86		OFFSET 8 ft RT		ALIGNMENT -L-						
COLLAR ELEV. 2,138.7 ft		TOTAL DEPTH 39.8 ft		NORTHING 565,534		EASTING 954,796						
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45				DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic						
DRILLER M. Seiler		START DATE 05/14/14		COMP. DATE 05/14/14		SURFACE WATER DEPTH N/A						
CORE SIZE NQ2		TOTAL RUN 15.7 ft										
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	REC. (ft) %	RQD (ft) %	SAMP. NO.	STRATA REC. (ft) %	RQD (ft) %	L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
2115.8	2,114.6	24.1	2.7	1:59/1.0 1:11/1.0 0:42/0.7	(2.4) 89%	(1.7) 63%		(8.2) 50%	(1.7) 10%		Begin Coring @ 23.5 ft	23.5
2110	2,111.9	26.8	5.0	1:00/1.0 0:58/1.0 1:05/1.0 1:06/1.0 0:50/1.0	(0.5) 10%	(0.0) 0%					CRYSTALLINE ROCK BROWNISH GRAY AND WHITE, SLIGHT TO MODERATELY SEVERE WEATHERED, MODERATELY HARD TO MEDIUM HARD, VERY CLOSE FRACTURED, GNEISS	
2105	2,106.9	31.8	5.0	0:58/1.0 0:47/1.0 1:01/1.0 1:10/1.0 1:41/1.0	(3.7) 74%	(0.8) 16%						
2100	2,101.9	36.8	3.0	1:18/1.0 1:15/1.0 1:17/1.0	(1.6) 53%	(1.0) 33%						
	2,098.9	39.8									Boring Terminated at Elevation 2,098.9 ft in Crystalline Rock (Gneiss)	39.8

**CORE PHOTOGRAPHS**  
**BRIDGE NO. 192 OVER MUD CREEK ON SR 1126**

**EB1-B**  
**BOX 1: 24.1 - 39.8 FEET**



APPROXIMATE SCALE IN FEET





WBS 17BP.14.R.103			TIP 44-0192			COUNTY HENDERSON			GEOLOGIST S. Buchanan					
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126									GROUND WTR (ft)					
BORING NO. EB2-A			STATION 13+28			OFFSET 10 ft LT			ALIGNMENT -L-					
COLLAR ELEV. 2,138.6 ft			TOTAL DEPTH 40.7 ft			NORTHING 565,556			EASTING 954,755					
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45						DRILL METHOD H.S. Augers			HAMMER TYPE Automatic					
DRILLER M. Seiler			START DATE 05/16/14			COMP. DATE 05/16/14			SURFACE WATER DEPTH N/A					
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100			ELEV. (ft)	DEPTH (ft)
2140														
	2,138.6	0.0											2,138.6	0.0
	2,137.1	1.5	4	3	3	6						M		
2135	2,135.6	3.0	2	1	2	3						M		
	2,134.1	4.5	2	2	2	4						M		
	2,132.6	6.0	1	2	2	4						W		
2130	2,131.1	7.5	3	3	2	5						W		
	2,129.6	9.0	1	3	2	5						W		
			1	2	1	3						W		
2125	2,125.1	13.5												
			7	6	4	10						W		
2120	2,120.1	18.5											2,121.4	17.2
			100/0.4							100/0.4				
2115	2,115.1	23.5												
	2,113.1	25.5	100/0.3							100/0.3				
2110			60/0.0							60/0.0			2,113.1	25.5
2105													2,106.6	32.0
													2,103.6	35.0
2100														
													2,097.9	40.7
													Boring Terminated at Elevation 2,097.9 ft in Crystalline Rock (Gneiss)	



# NCDOT GEOTECHNICAL ENGINEERING UNIT CORE BORING REPORT

SHEET 9 OF 12

WBS 17BP.14.R.103		TIP 44-0192		COUNTY HENDERSON		GEOLOGIST S. Buchanan					
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126							GROUND WTR (ft)				
BORING NO. EB2-A		STATION 13+28		OFFSET 10 ft LT		ALIGNMENT -L-					
COLLAR ELEV. 2,138.6 ft		TOTAL DEPTH 40.7 ft		NORTHING 565,556		EASTING 954,755					
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45				DRILL METHOD H.S. Augers		HAMMER TYPE Automatic					
DRILLER M. Seiler		START DATE 05/16/14		COMP. DATE 05/16/14		SURFACE WATER DEPTH N/A					
CORE SIZE NQ2		TOTAL RUN 15.2 ft									
ELEV (ft)	RUN ELEV (ft)	DEPTH (ft)	RUN (ft)	DRILL RATE (Min/ft)	REC. (ft) %	RQD (ft) %	STRATA REC. (ft) %	RQD (ft) %	L O G	DESCRIPTION AND REMARKS	DEPTH (ft)
2113.14	2,113.1	25.5	1.2	1:43/1.2	(1.1)	(0.8)	(5.6)	(3.0)		Begin Coring @ 25.5 ft	25.5
2110	2,111.0	26.7	5.0	1:28/1.0	92%	67%	86%	46%		CRYSTALLINE ROCK	
				1:05/1.0	(4.5)	(2.2)				BROWNISH GRAY AND WHITE, SLIGHT WEATHERED, HARD TO MODERATE HARD, CLOSE TO VERY CLOSE FRACTURED, GNEISS FRACTURES AT 30 DEGREES WITH IRON-STAIN INFILLING	
	2,106.9	31.7		1:03/1.0	90%	44%					
				1:20/1.0						AT 30.3FT TO 31.7FT: 90 DEGREE FRACTURE WITH SAND INFILLING	32.0
2105			5.0	1:07/1.0			(0.3)	(0.0)		CRYSTALLINE ROCK	
				1:13/1.0	48%	36%	10%	0%		BROWNISH GRAY AND WHITE, MODERATELY SEVERE WEATHERED, SOFT TO VERY SOFT, VERY CLOSE FRACTURED, GNEISS	35.0
	2,101.9	36.7		1:24/1.0			(5.3)	(4.7)		CRYSTALLINE ROCK	
2100			4.0	1:14/1.0	(3.2)	(2.9)	93%	82%		BROWNISH GRAY AND WHITE, SLIGHT WEATHERED, HARD TO MODERATE HARD, CLOSE TO VERY CLOSE FRACTURED, GNEISS	
	2,097.9	40.7		1:17/1.0	80%	73%					
				1:07/1.0						Boring Terminated at Elevation 2,097.9 ft in Crystalline Rock (Gneiss)	40.7
				1:23/1.0							

**CORE PHOTOGRAPHS**  
**BRIDGE NO. 192 OVER MUD CREEK ON SR 1126**

**EB2-A**

**BOX 1: 25.5 - 38.0 FEET**



APPROXIMATE SCALE IN FEET

**EB2-A**

**BOX 2: 38.0 - 40.7 FEET**



APPROXIMATE SCALE IN FEET



# NCDOT GEOTECHNICAL ENGINEERING UNIT BORELOG REPORT

SHEET 11 OF 12


WBS 17BP.14.R.103		TIP 44-0192		COUNTY HENDERSON		GEOLOGIST S. Buchanan						
SITE DESCRIPTION Bridge No. 192 over Mud Creek on SR 1126							GROUND WTR (ft)					
BORING NO. EB2-B		STATION 13+29		OFFSET 8 ft RT		ALIGNMENT -L-						
COLLAR ELEV. 2,138.6 ft		TOTAL DEPTH 23.5 ft		NORTHING 565,567		EASTING 954,770						
DRILL RIG/HAMMER EFF./DATE Red Dog Drilling CME-45				DRILL METHOD SPT Core Boring		HAMMER TYPE Automatic						
DRILLER M. Seiler		START DATE 05/15/14		COMP. DATE 05/15/14		SURFACE WATER DEPTH N/A						
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT			SAMP. NO.	LOG	SOIL AND ROCK DESCRIPTION	
			0.5ft	0.5ft	0.5ft	0	25	50	75	100		ELEV. (ft) DEPTH (ft)
2140												
	2,137.6	1.0	2	2	1							GROUND SURFACE 2,138.6 0.0
2135	2,136.1	2.5	WOH	WOH	WOH						M	TOPSOIL 2,136.1 2.5
	2,134.6	4.0	WOH	WOH	WOH						W	ALLUVIAL BROWN, CLAYEY FINE TO MEDIUM GRAINED SAND, WITH TRACE ROOTS 2,134.6 4.0
	2,133.1	5.5	WOH	WOH	WOH						W	ALLUVIAL BROWN TO GRAYISH BROWN, SILTY FINE TO COARSE GRAINED SAND, WITH TRACE ROOTS AND FINE GRAINED GRAVEL 2,133.1 5.5
2130	2,131.6	7.0	1	1	WOH						W	ALLUVIAL BROWN TO GRAYISH BROWN, SILTY FINE TO COARSE GRAINED SAND, WITH TRACE ROOTS AND FINE GRAINED GRAVEL 2,131.6 7.0
	2,130.1	8.5	1	2	3							ALLUVIAL GRAY, CLAYEY FINE GRAINED SAND, WITH TRACE ROOTS 2,130.1 8.5
2125	2,125.1	13.5	4	5	8						M	ALLUVIAL ORANGISH BROWN, SILTY FINE TO COARSE GRAINED SAND, WITH LITTLE FINE TO COARSE GRAINED QUARTZ GRAVEL 2,125.1 13.5
2120	2,120.1	18.5	100/0.4									WEATHERED ROCK (GNEISS) 2,120.1 18.5
	2,115.1	23.5	60/0.0									AT 22.5FT TO 23.5FT: AUGERS GRINDING 2,115.1 23.5
												Boring Terminated with Standard Penetration Test Refusal at Elevation 2,115.1 ft on Crystalline Rock (Gneiss)



**SITE PHOTOGRAPHS**  
**BRIDGE NO. 192 OVER MUD CREEK ON SR 1126**



**View of SR 1126 looking Southeast**



**View of Bridge No. 192 looking Northwest**