DocuSign Envelope ID: D0203EFE-D75A-4153-8031-E200FBC7E370

PROJ. REFERENCE NO.	SHEET NO.
17BP.14.R.162	PMP-1

STV 100 Years
STV Engineers, Inc.
900 West Trade St., Suite 715
Charlotte, NC 28202
NC License Number F-0991

BRIDGE #550088

PAVEMENT MARKING PLAN

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANAUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL & BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL & BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A. INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE.

ROAD NAME:	MARKING
SR 1340 (SNOW HILL RD)	PAINT

B. TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.
C. REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.
C. TEMPRORAY PAVEMENT MARKINGS ARE PLACED IN ONE(1) COAT OF PAINT, AND FINAL PAVEMENT MARKINGS ARE PLACED IN TWO(2) COATS OF PAINT.



PAVEMENT MARKING SCHEDULE

P2 - PAINT (24" WHITE)	WHITE STOPBAR	13 LF
P8 - PAINT (4" WHITE)	2FT. - 6 FT./SP	15 LF
PA - PAINT (4" WHITE)	WHITE EDGELINE	987 LF
PI - PAINT (4" YELLOW)	DOUBLE YELLOW CENTER LINE	930 LF

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

APPROVED: [signature] DATE: 1/28/2019

NORTH CAROLINA PROFESSIONAL SEAL 039234 ENGINEER NIKKI T. HONEYCUTT

PAVEMENT MARKING DETAIL

SCALE:	20
DATE:	11/29/17
DWG. BY:	ERW
DESIGN BY:	ERW
REVIEWED BY:	- - -

DIVISION OF HIGHWAYS STATE OF NORTH CAROLINA TRAFFIC ENGINEERING

REVISIONS

CADD FILE

R:\Traffic\Traffic Control\PMP\17BP14R162_rdy_pmp01.dgn

1/25/2019