

						LITTLE MOUNTAIN BUILDERS OF CATAWBA COUNTY LLC MAIDEN, NC	COLWELL CONSTRUCTION CO INC BLAIRSVILLE, GA		
ROADWAY ITEMS									
0001	0000100000-N	800	MOBILIZATION	Lump Sum		69,650.00	120,000.00		
0002	0043000000-N	226	GRADING (226)	Lump Sum		69,030.00	60,000.00		
0003	1220000000-E	545	INCIDENTAL STONE BASE	30 TON		71.00	97.60		
0004	1693000000-E	654	ASPH PLT MIX PVMT REPAIR	90 TON		178.00	350.00		
0005	2549000000-E	846	2'-6" CONC CURB & GUTTER	380 LF		70.00	125.00		
0006	2591000000-E	848	4" CONCRETE SIDEWALK	220 SY		55.50	106.20		
0007	2605000000-N	848	CONCRETE CURB RAMPS	3 EA		3,009.00	8,850.00		
0008	2612000000-E	848	6" CONCRETE DRIVEWAY	770 SY		115.00	159.30		
0009	2612300000-N	848	RETRO EXT CONC CURB RAMP	3 EA		850.00	8,850.00		
0010	2612500000-N	848	REM & REP CONC CURB RAMP	51 EA		3,009.00	4,130.00		
0011	4025000000-E	901	CONTR FURN, TYPE ***SIGN (E)	11 SF		25.00	30.00		
0012	4072000000-E	903	SUPPORT, 3-LB STL U-CHAN	20 LF		6.50	9.56		
0013	4102000000-N	904	SIGN ERECTION, TYPE E	2 EA		180.00	343.75		
0014	4447000000-E	SP	PED CHANNEL DEVICES	100 LF		110.00	77.50		
0015	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum		87,250.00	40,000.00		
0016	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) AUDIBLE WARNING DEVICES	4 EA		324.00	206.25		
0017	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) PEDESTRIAN TRANSPORT SERVICE	20 EA		50.00	77.50		
0018	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) TEMPORARY CURB RAMP	4 EA		1,500.00	1,462.50		
0019	4685000000-E	1205	THERMO PVT MKG LINES 4"90	50 LF		9.00	23.60		
0020	4695000000-E	1205	THERMO PVT MKG LINES 8"90 MILS	1,800 LF		10.00	29.50		
0021	4709000000-E	1205	24"WIDE THERMO 90 MILS	450 LF		23.60	41.30		
0022	4860000000-E	1205	LINE REMOVAL 8" WIDE	110 LF		6.00	2.36		
0023	4870000000-E	1205	LINE REMOVAL 24" WIDE	550 LF		12.50	5.90		
0024	6000000000-E	1605	TEMPORARY SILT FENCE	500 LF		2.40	4.72		
0025	6012000000-E	1610	SEDIMENT CONTROL STONE	30 TON		156.00	98.65		
0026	6029000000-E	SP	SAFETY FENCE	300 LF		2.40	3.54		
0027	6042000000-E	1632	1/4" HARDWARE CLOTH	500 LF		7.00	8.26		
0028	6084000000-E	1660	SEEDING AND MULCHING	0.5 ACR		5,500.00	4,720.00		
0029	6117000000-N	1675	RESPONSE FOR EROS CONTROL	10 EA		800.00	826.00		
0030	6117500000-N	SP	CONC WASHOUT STRUCTURE	10 EA		325.00	5,585.95		
CONTRACT TOTAL						TOTAL	617,242.00	TOTAL	882,227.30
ROADWAY ITEMS						SUB-TOTAL	617,242.00	SUB-TOTAL	882,227.30

BIDDERS IN ORDER

LITTLE MOUNTAIN BUILDERS OF CATAWBA COUNTY LLC	2
COLWELL CONSTRUCTION CO INC	3

CONTRACT TOTAL

617,242.00	
882,227.30	