DocuSign Envelope ID: 2EC5C0B1-871E-4C02-97E2-DE619F95547A

EROSION CONTROL PLAN

PROJECT REFERENCE NO.	SHEET NO.
I7BP.RJ4.J76	EC-4/CONST.4
R/W SHEET NO.	
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER



ENVIRONMENTALLY SENSITIVE AREA
SEE PROJECT SPECIAL PROVISIONS

INSTALL DRIVEWAY PIPE DURING CLEARING & GRUBBING PHASE

CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 4

NOTE:

PLACE TEMPORARY ROCK SILT CHECKS TYPE – A AT DRAINAGE OUTLETS.

BRIDGE REMOVAL AND BRIDGE CONSTRUCTION SHALL BE PER REQUIREMENTS IN THE NCDOT BEST MANAGEMENT PRACTICES FOR CONSTRUCTION AND MAINTENANCE ACTIVITIES MANUAL

DEWATER AREA BEHIND IMPERVIOUS DIKES INTO SPECIAL STILLING BASIN(S).

CONTRACTOR SHALL INSTALL AN ONSITE CONCRETE WASHOUT STRUCTURE PER THE NCDOT DETAIL AND SPECIAL PROVISIONS. ACTUAL LOCATION OF THE STRUCTURE SHALL BE DETERMINED IN THE FIELD. CONCRETE WASHOUT STRUCTURE SHALL BE MAINTAINED BY THE CONTRACTOR. ALL CONCRETE TRUCKS SHALL USE THE CONCRETE WASHOUT STRUCTURE. NO WASHOUT OF CONCRETE TRUCKS SHALL BE ALLOWED EXCEPT IN THE CONCRETE WASHOUT STRUCTURE.