



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN

GOVERNOR

March 20, 2025

J.R. "JOEY" HOPKINS

SECRETARY

ADDENDUM # 1

Contract No. DN01096
TIP No.: N/A
Federal Aid No.: Helene
WBS Element: DF18314.2045109; DF18314.2045116; DF18314.2045467;
DF18314.2045468; DF18314.2045469
County: Henderson
Description: Emergency Repair: Drainage, Erosion Control, Grade, Guardrail,
Traffic Control, and Wall at various locations along SR 1602 (Grant
Mountain Rd)

Letting Date: March 25, 2025

Plan Holders

**Content Summary: Pre-Bid Meeting Minutes and Roster, Provision
Changes, Pay Item Changes, Revised plans to reflect pay item
changes**

The above contract has experienced the following revisions:

1. Pre-Bid Meeting Minutes (see attached)
2. Pre-Bid Roster (see attached)
3. Revise **Provision SP1 G37 Specialty Items** on page **G-6** to include "0034-0038 Retaining Wall Items" (see attached)
4. Addition of **Minimize Removal of Vegetation Provision** on page **EC-12** (see attached)
5. Pay Item changes: (see attached)
 - a. The quantity for line item 0005: 0222000000-E GEOTEXTILE FOR ROCK EMBANKMENTS has increased from 360 SY to **860 SY**

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS - DIVISION 14
253 WEBSTER ROAD
SYLVA, NC 28779

Telephone: (828) 331-5200
Fax: (828) 331-5201
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
253 WEBSTER ROAD
SYLVA, NC 28779


- b. The quantity for line item 0006: 0314000000-E SELECT MATERIAL, CLASS ***** (VII) has increased from 600 TON to **4400** TON
 - c. 0063000000-N SP GRADING was removed and 0043000000-N 226 GRADING has been added in its place.
- 6. Revise Grading Summary of Quantities page 14 (of DN01096 STANDARD PLANS SHEETS – ROADWAY pdf) reflect the pay item changes. (see attached)
 - 7. Replace **SP1 G43 Fuel Price Adjustment** on page **G-6**, with the attached provision

Please access ebsx addenda files, DN01096.001x. on Bid Express® and the Bidding and Letting website.

Thank you for your attention to this matter.

If you have any questions, please contact the Division Proposal Engineer at (828) 331-5200.

Sincerely,

DocuSigned by:

29BD93927CF24F6...

Jeanette L. White, P.E.
Division 14 Project Team Lead



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

J.R. "JOEY" HOPKINS
SECRETARY

March 17, 2025

CONTRACT NO.: DN01096
TIP NO.: N/A
FEDERAL: Helene
WBS: DF18314.2045109, DF18314.2045116, DF18314.2045467,
DF18314.2045468, DF18314.2045469
COUNTY: Henderson
DESCRIPTION: Emergency Repair: Drainage, Erosion Control, Grade, Guardrail, Traffic
Control, and Wall
LOCATION: Various Locations Along SR 1602 (Grant Mountain Rd)

SUBJECT: Mandatory Prebid Meeting

Attendees:	Company:
Jacob Williams	NCDOT
Patrick Eubanks	NCDOT
Dean Hardister	NCDOT
Greg Connor	NCDOT
Kevin Barnett	NCDOT
Kevin Mitchell	NCDOT

Contractor attendees attached.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
OFFICE OF RESIDENT ENGINEER
4142 HAYWOOD ROAD
MILLS RIVER, NC 28759

Telephone: (828) 891-5367
Fax: (828) 891-8842
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
4142 HAYWOOD ROAD
MILLS RIVER, NC 28759

General Items:

5 Locations throughout SR 1602

Contractor's Plan of Operation Start Date:

N/A

Contract Time:

Date of Availability:	April 21, 2025
Completion Date:	April 24, 2026
Begin Work Date:	N/A
Original Calendars to Complete:	369

Contract Review:

All 5 sites are the same project, however use different WBS elements.

Construction Moratorium:

No tree cutting after April 1st of any year.

Any trees that need to be cut after April 1st will need to be coordinated with NCDOT personnel or private engineering firm.

General Provisions:

All wall items will be specialty items for this contract.

Roadway:

- See plans for details.

Traffic Control:

- Lane closures will need to be coordinated with NCDOT as well as other contractors in the area to ensure homeowners will have routes in and out of Chimney Rock.
- If full roadway closure is needed, to be discussed with DOT prior as to inform the public with ample notice.
- Lane closures will need signs starting at paved areas as the road is narrow and will be difficult for civilians to turn around.

Erosion Control Review:

- See plans for details.

Utilities:

No gas utilities in area.

Internet and power lines are present in the area with live lines held temporarily by nearby trees and possibly underground.

General Comments:

Mandatory Prebid Meeting at from 2:09PM –3:50PM

- Hydroseed slope at site 535.
- Slope at 535 may need to be reestablished at failure.
- Site 536 will need graded and seeded.
- There are a few sites without Survey123 locations that fall under the .25-mile limits that need to be addressed possibly with rock embankment.
- ROW may need to be acquired at certain sites depending on the length of construction needed.
- Debris removal will need to be evaluated by the inspector for payment as well as location of waste site.
- Site 555 pipe will need to be a 48" Aluminized or Class IV RCP pipe and be readjusted to center of waterbed.
- Site 555 may need pipe angled downward towards bottom of waterbed.
- Borrow and stone will be needed to fill at site 555 while maintaining water flow.
- Site 539 will need soil removal off property and seeded where it was eroded.

Plan Review:

NCDOT staff and all attending contractors met off SR 1602. Scoped and discussed prospected sites, including but not limited to roadway sites # 535, 536, 537, 539, and 555. Contractors available to ask questions, see above for any answered questions. Any unanswered questions to be answered and posted to the contract bid site prior to bidding date.

Sincerely,

Patrick Eubanks



Engineering Specialist II

Construction Meeting

Project Number = DNO1096

[illegible]

SPECIALTY ITEMS:

(7-1-95)(Rev. 1-16-24)

108-6

SP1 G37

Items listed below will be the specialty items for this contract (see Article 108-6 of the *Standard Specifications*).

Line #	Description
0012-0014	Guardrail
0017-0020	Signing
0022-0033	Erosion Control
0034-0038	Retaining Wall Items

FUEL PRICE ADJUSTMENT:

(11-15-05)(Rev. 1-16-24)

109-8

SP1 G43

Page 1-82, Article 109-8, FUEL PRICE ADJUSTMENTS, add the following:

The base index price for DIESEL #2 FUEL is \$ **2.5616** per gallon. Where any of the following are included as pay items in the contract, they will be eligible for fuel price adjustment.

The pay items and the fuel factor used in calculating adjustments to be made will be as follows:

Description	Units	Fuel Usage Factor Diesel
Unclassified Excavation	Gal/CY	0.29
Borrow Excavation	Gal/CY	0.29
Class IV Subgrade Stabilization	Gal/Ton	0.55
Aggregate Base Course	Gal/Ton	0.55
Sub-Ballast	Gal/Ton	0.55
Erosion Control Stone	Gal/Ton	0.55
Rip Rap, Class _____	Gal/Ton	0.55
Asphalt Concrete Base Course, Type _____	Gal/Ton	0.90 or 2.90
Asphalt Concrete Intermediate Course, Type _____	Gal/Ton	0.90 or 2.90
Asphalt Concrete Surface Course, Type _____	Gal/Ton	0.90 or 2.90
Open-Graded Asphalt Friction Course	Gal/Ton	0.90 or 2.90
Permeable Asphalt Drainage Course, Type _____	Gal/Ton	0.90 or 2.90
Sand Asphalt Surface Course, Type _____	Gal/Ton	0.90 or 2.90
Ultra-thin Bonded Wearing Course	Gal/Ton	0.90 or 2.90
Aggregate for Cement Treated Base Course	Gal/Ton	0.55
Portland Cement for Cement Treated Base Course	Gal/Ton	0.55
> 11" Portland Cement Concrete Pavement	Gal/SY	0.327
Concrete Shoulders Adjacent to > 11" Pavement	Gal/SY	0.327
9" to 11" Portland Cement Concrete Pavement	Gal/SY	0.272
Concrete Shoulders Adjacent to 9" to 11" Pavement	Gal/SY	0.272
< 9" Portland Cement Concrete Pavement	Gal/SY	0.245
Concrete Shoulders Adjacent to < 9" Pavement	Gal/SY	0.245

MINIMIZE REMOVAL OF VEGETATION:

The Contractor shall minimize removal of vegetation within project limits to the maximum extent practicable. Vegetation along stream banks and adjacent to other jurisdictional resources outside the construction limits shall only be removed upon approval of Engineer. No additional payment will be made for this minimization work.

County: HENDERSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0004	0134000000-E	240	DRAINAGE DITCH EXCAVATION	226 CY		
0005	0222000000-E	SP	GEOTEXTILE FOR ROCK EMBANKMENTS	860 SY		
0006	0314000000-E	SP	SELECT MATERIAL, CLASS ***** (VII)	4,400 TON		
0007	0335800000-E	305	48" DRAINAGE PIPE	40 LF		
0008	1077000000-E	SP	#57 STONE	90 TON		
0009	1220000000-E	545	INCIDENTAL STONE BASE	20 TON		
0010	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	90 LF		
0011	2077000000-E	815	6" OUTLET PIPE	25 LF		
0012	3030000000-E	862	STEEL BEAM GUARDRAIL	150 LF		
0013	3288000000-N	862	GUARDRAIL END UNITS, TYPE TL-2	1 EA		
0014	3360000000-E	863	REMOVE EXISTING GUARDRAIL	150 LF		
0015	3642000000-E	876	RIP RAP, CLASS A	60 TON		
0016	3649000000-E	876	RIP RAP, CLASS B	90 TON		
0017	4025000000-E	901	CONTRACTOR FURNISHED, TYPE *** SIGN (E)	5 SF		
0018	4072000000-E	903	SUPPORTS, 3-LB STEEL U-CHANNEL	15 LF		

County: HENDERSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	4102000000-N	904	SIGN ERECTION, TYPE E	1 EA		
0020	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	1 EA		
0021	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0022	6000000000-E	1605	TEMPORARY SILT FENCE	575 LF		
0023	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	10 TON		
0024	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	10 TON		
0025	6012000000-E	1610	SEDIMENT CONTROL STONE	10 TON		
0026	6029000000-E	SP	SAFETY FENCE	100 LF		
0027	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,734 SY		
0028	6042000000-E	1632	1/4" HARDWARE CLOTH	105 LF		
0029	6071010000-E	1642	WATTLE	162 LF		
0030	6084000000-E	1660	SEEDING & MULCHING	0.85 ACR		
0031	6117000000-N	1675	RESPONSE FOR EROSION CONTROL	8 EA		
0032	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	1 EA		
0033	6138000000-E	SP	GENERIC EROSION CONTROL ITEM VEGETATIVE DEBRIS REMOVAL AND DISPOSAL	210 CY		
0034	8252000000-E	425	REINFORCING STEEL (RETAINING WALL)	2,120 LB		
0035	8834000000-N	SP	GENERIC RETAINING WALL ITEM MICROPILE PROOF TESTS	1 EA		

County: HENDERSON

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0036	8834000000-N	SP	GENERIC RETAINING WALL ITEM MICROPILE, AVERAGE LENGTH	22 EA		
0037	8839000000-E	SP	GENERIC RETAINING WALL ITEM MICROPILE, ADDITIONAL LENGTH OVER AVERAGE	40 LF		
0038	8853000000-E	SP	GENERIC RETAINING WALL ITEM SHOTCRETE	16 CY		
0039	0043000000-N	226	GRADING	Lump Sum	L.S.	
0922/Mar20/Q11352.85/D161520810000/E38			Total Amount Of Bid For Entire Project :			

