PROJECT REFERENCE NO.	SHEET NO.
B-4775	EC-3A
ROADWAY DESIGN ENGINEER	HYDRAULICS ENGINEER

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA

SOIL STABILIZATION SUMMARY SHEET

MATTING FOR EROSION CONTROL (DITCHES)

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	14+50	16+00	RT.	105
4	-L-	13+00	14+00	LT.	30
4	-L-	15+00	15+92	LT.	43
	MATTING FOR EROSION CONTROL (SLOPES & SHOULDERS)				
4	-L-	13+00	15+75	RT.	405
				SUBTOTAL	583
MISCELLANEOUS MATTING TO BE INSTALLED AS DIRECTED BY THE ENGINEER					35
				TOTAL	618
				SAY	620
	COIR FIBER MATTING				
INSTALL COIR FIBER MATTING ON STREAMBANKS AND FLOODPLAIN BENCHES AS NEEDED					150

PERMANENT SOIL REINFORCEMENT MAT

CONST SHEET NO.	LINE	FROM STATION	TO STATION	SIDE	ESTIMATE (SY)
4	-L-	14+40	14+50	RT.	10
				SUBTOTAL	10
		ADDITIONAL PSRM TO BE INSTALLED			2
				TOTAL	12
				SAY	12