DocuSign Envelope ID: C7897283-4684-476A-9DEC-138BB2D96359

PROJECT REFERENCE NO.	SHEET NO.
17BPJ4.RJ12	EC-4/CONST.4

0' 20' 40'

NOTES: ANY DEVIATION FROM OPTIONS GIVEN WILL REQUIRE PRIOR APPROVAL BY ENGINEER.

ADDITIONAL EROSION CONTROL DEVICES MAY NEED TO BE INSTALLED AS DIRECTED BY THE ENGINEER.

EROSION CONTROL

NAD 83/ NA 2011



CLEARING AND GRUBBING EROSION CONTROL FOR CONSTRUCTION SHEET 4

TROUT STREAM BUFFER ZONE

DETAIL A
LATERAL BASE DITCH
(Not to Scale)



Min. D = 3 Ft.
B = 2 Ft.
b = 5 Ft.

Type of Liner = Coir Fiber Matting

FROM –L– STA. 12+30 TO –L– STA. 12+80 LT

DETAIL B
STANDARD BASE DITCH
(Not to Scale)



Min. D = 3 Ft.
B = 2 Ft.

Type of Liner = Coir Fiber Matting

FROM –L– STA. 12+13 TO STA. 12+30 LT
FROM –L– STA. 12+80 TO STA. 13+10 LT

SEE RF-1, RF-2, RF-3 AND PROJECT SPECIAL PROVISIONS

REVISIONS

3/3/2021 14:33:55 AM
$FILEL$
$PENTBL$$

wsp
1001 Morehead Square Dr., Suite 610, Charlotte NC, 28203
NC LIC NO. F-0165