

TIP NO
FED AID NO STATE FUNDED
GRADING, PAVING, DRAINAGE, AND CULVERT
BRIDGE NO. 308 ON SR 1500 (WATAUGA RD) OVER WATAUGA CREEK

0.070 MI

GRAHAM COUNTY LAND
COMPANY LLC
ROBBINSVILLE, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum		32000.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		20000.00
0003	0036000000-E	225	UNDERCUT EXCAVATION	50 CY	26.00	1300.00
0004	0043000000-N	226	GRADING	Lump Sum		70000.00
0005	0050000000-E	226	SUPP CLEARING & GRUBBING	1 ACR	1.00	1.00
0006	0195000000-E	265	SELECT GRANULAR MATERIAL	50 CY	95.00	4750.00
0007	0196000000-E	270	GEOTEXTILE SOIL STABILIZATION	50 SY	15.00	750.00
0008	0199000000-E	SP	TEMPORARY SHORING	280 SF	70.00	19600.00
0009	0320000000-E	300	FND CONDIT GEOTEXTILE	153 SY	30.00	4590.00
0010	0536000000-E	310	**** HDPE PIPE CULVTS (8)	220 LF	36.00	7920.00
0011	0570000000-E	310	6" CS PIPE 0.064" SPR BOX	40 LF	40.00	1600.00
0012	1099700000-E	505	CLASS IV SUBGRD STABILIZATION	50 TON	70.00	3500.00
0013	1121000000-E	520	AGGREGATE BASE COURSE	340 TON	55.00	18700.00
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON	55.00	5500.00
0015	1489000000-E	610	ASP CONC BASE CRS B25.0B	150 TON	175.00	26250.00
0016	1519000000-E	610	ASP CONC SURF CRS S9.5B	130 TON	180.00	23400.00
0017	1575000000-E	620	ASP FOR PLANT MIX	15 TON	650.00	9750.00
0018	2286000000-N	840	MASNRY DRAINAGE STRUCT	1 EA	2100.00	2100.00
0019	3569000000-E	867	BARBED WIRE FENCE RESET	400 LF	7.00	2800.00
0020	3635000000-E	876	RIP RAP, CLASS II	9 TON	60.00	540.00
0021	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	70 SY	8.00	560.00
0022	4400000000-E	1110	WORK ZONE SIGNS (STAT)	124 SF	25.00	3100.00
0023	4410000000-E	1110	WORK ZONE SIGNS (BARR)	36 SF	25.00	900.00
0024	4430000000-N	1130	DRUMS	35 EA	50.00	1750.00
0025	4445000000-E	1145	BARRICADES (TYPE III)	16 LF	65.00	1040.00
0026	4455000000-N	1150	FLAGGER	4 DAY	1400.00	5600.00
0027	4465000000-N	1160	TEMPORARY CRASH CUSHIONS	2 EA	7100.00	14200.00
0028	4470000000-N	1160	REM & RES CRASH CUSHION	1 EA	3700.00	3700.00
0029	4485000000-E	1170	PORT CONC BARRIER	70 LF	110.00	7700.00
0030	4589000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (LS) (PORTABLE TRAFFIC SIGNAL SYSTEM) (ACTUATED)	Lump Sum		34000.00
0031	4810000000-E	1205	PAINT PVMT MARKINGS 4"	2,952 LF	1.50	4428.00
0032	4835000000-E	1205	PAINT PVT MKG LINES 24"	18 LF	8.00	144.00
0033	4870000000-E	1205	LINE REMOVAL 24" WIDE	18 LF	11.00	198.00
0034	6000000000-E	1605	TEMPORARY SILT FENCE	1,150 LF	3.25	3737.50
0035	6009000000-E	1610	EROS CONTRL STONE CL B	85 TON	55.00	4675.00
0036	6012000000-E	1610	SEDIMENT CONTROL STONE	85 TON	55.00	4675.00
0037	6015000000-E	1615	TEMPORARY MULCHING	1 ACR	500.00	500.00
0038	6018000000-E	1620	SEED FOR TEMP SEEDING	100 LB	3.00	300.00

TIP NO
FED AID NO STATE FUNDED
GRADING, PAVING, DRAINAGE, AND CULVERT
BRIDGE NO. 308 ON SR 1500 (WATAUGA RD) OVER WATAUGA CREEK

0.070 MI

GRAHAM COUNTY LAND
COMPANY LLC
ROBBINSVILLE, NC

0039	6021000000-E	1620 FERT FOR TEMP SEEDING	0.5 TON	800.00	400.00
0040	6024000000-E	1622 TEMPORARY SLOPE DRAINS	100 LF	16.00	1600.00
0041	6029000000-E	SP SAFETY FENCE	100 LF	3.00	300.00
0042	6030000000-E	1630 SILT EXCAVATION	50 CY	25.00	1250.00
0043	6036000000-E	1631 MATTING FOR EROS CONTROL	2,925 SY	3.00	8775.00
0044	6037000000-E	SP COIR FIBER MAT	100 SY	7.00	700.00
0045	6042000000-E	1632 1/4" HARDWARE CLOTH	240 LF	5.00	1200.00
0046	6045000000-E	SP *** TEMPORARY PIPE (30)	60 LF	60.00	3600.00
0047	6045000000-E	SP *** TEMPORARY PIPE (48)	72 LF	110.00	7920.00
0048	6070000000-N	1639 SPECIAL STILLING BASINS	2 EA	1500.00	3000.00
0049	6071020000-E	SP POLYACRYLAMIDE (PAM)	15 LB	8.00	120.00
0050	6084000000-E	1660 SEEDING AND MULCHING	0.5 ACR	5000.00	2500.00
0051	6090000000-E	1661 SEED FOR REPAIR SEEDING	50 LB	3.00	150.00
0052	6093000000-E	1661 FERT FOR REPAIR SEEDING	0.25 TON	800.00	200.00
0053	6096000000-E	1662 SEED FOR SUPP SEEDING	50 LB	3.00	150.00
0054	6108000000-E	1665 FERTILIZER TOPDRESSING	0.5 TON	800.00	400.00
0055	6111000000-E	SP IMPERVIOUS DIKE	25 LF	70.00	1750.00
0056	6117000000-N	SP RESPONSE FOR EROS CONTROL	13 EA	20.00	260.00
0057	6123000000-E	1670 REFORESTATION	0.1 ACR	5000.00	500.00
0058	6132000000-N	SP GENERIC EROSION CONTROL ITEM (EA) (CONCRETE WASHOUT STRUCTURE)	1 EA	1500.00	1500.00

CULVERT ITEMS

0059	8035000000-N	402 REMV EXIST STR ***** (STATION -L- 12+06.48)	Lump Sum		7000.00
0060	8126000000-N	414 CULV EXCAV @ ***** (STATION -L- 12+06.48)	Lump Sum		20000.00
0061	8133000000-E	414 FND CONDIT MAT, BOX CULV	108 TON	50.00	5400.00
0062	8804000000-N	SP GENERIC CULVERT ITEM (LS) (ALUM BOX CULVERT)	Lump Sum		205000.00
0063	8804000000-N	SP GENERIC CULVERT ITEM (LS) (CHANNEL SUBSTRATE MATERIAL)	Lump Sum		3000.00

CONTRACT TOTAL TOTAL 622933.50

ROADWAY ITEMS SUB-TOTAL 382533.50
CULVERT ITEMS SUB-TOTAL 240400.00

TIP NO
FED AID NO STATE FUNDED
GRADING, PAVING, DRAINAGE, AND CULVERT
BRIDGE NO. 308 ON SR 1500 (WATAUGA RD) OVER WATAUGA CREEK

0.070 MI

BIDDERS IN ORDER

GRAHAM COUNTY LAND COMPANY LLC

1

CONTRACT TOTAL

622933.50