DocuSign Envelope ID: 51C271F2-AF89-46BA-B09A-719797789DE7

TIP NO.	SHEET NO.
B-6032	PMP-1

APPROVED: DocuSigned by: Lloyd D. Brown 33B5ADF17F57488...

DATE: 12/8/2021

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN
JACKSON COUNTY

TIP PROJECT B-6032

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES & MOUNTING
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE

ROAD NAME:	MARKING
SR 1397 (THOMAS VALLEY ROAD)	PAINT
SR 1534 (WILMONT CEMETERY ROAD)	PAINT

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

INDEX

SHEET NO.	DESCRIPTION
PMP-1	PAVEMENT MARKING PLAN COVER SHEET
PMP-2	PAVEMENT MARKING PLAN DETAIL

PAVEMENT MARKING SCHEDULE

FINAL
PAVEMENT MARKINGS

SYMBOL	DESCRIPTION
PAINT (4")	
P1	WHITE EDGELINE
P5	2 FT. - 6 FT./SP WHITE MINISKIP
P13	YELLOW DOUBLE CENTER

PLAN REVIEWED BY: N.C.D.O.T. SIGNING AND DELINEATION UNIT

STEVE BUCHANAN — DIVISION TRAFFIC ENGINEER

_____ — SIGNING & DELINEATION PROJECT DESIGN ENGINEER

DIVISION OF HIGHWAYS · STATE OF NORTH CAROLINA · DEPARTMENT OF TRANSPORTATION · WORK ZONE TRAFFIC CONTROL UNIT

PLAN PREPARED BY: Vaughn & Melton Consulting Engineers

LLOYD DEWAYNE BROWN, P.E. — PROJECT ENGINEER

C. GONZALEZ-MARTELL — PROJECT DESIGN ENGINEER

V&M Vaughn & Melton Consulting Engineers
Asheville, North Carolina
828-253-2796

Raleigh, NC 919-977-9455 · Charlotte, NC 704-357-0488 · Boone, NC 828-355-9933
Tri-Cities, TN 423-467-8401 · Tri-Cities, TN 423-467-8401 · Knoxville, TN 865-546-0800
Charleston, SC 843-974-5650 · Middlesboro, KY 606-248-6600 · Atlanta, GA 770-627-3509
Spartanburg, SC 864-574-4775

Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved

12/6/2021 10:26:36 AM
...\TCP\490141_PMP-1.dgn
User:amfitzpatrick