| PROJECT REFERENCE NO. | SHEET NO. |
|---|---|
| W-5601DUB | 1A |
| INDEX OF SHEETS | |

# INDEX OF SHEETS


| SHEET NUMBER: | SHEET: |
|---|---|
| 1 | TITLE SHEET |
| 1A | INDEX OF SHEETS, GENERAL NOTES, NOTE TO CONTRACTOR AND LIST OF STANDARDS |
| 1B | CONVENTIONAL SYMBOLS |
| 3B–1 | GUARDRAIL SUMMARY SHEET |
| 4 | SITE LOCATIONS |
| 5 | SITE LOCATIONS |
| 6 | SITE LOCATIONS |
| 7 | SITE LOCATIONS |


## GENERAL NOTES:

THE GUARDRAIL LOCATIONS SHOWN ON THESE PLANS MAY BE ADJUSTED DURING THE CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GURADRAIL MATERIAL.

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

APPROXIMATE LOCATION FOR EACH OF THE GUARDRAIL SITES LISTED IN THESE PLANS HAVE BEEN IDENTIFIED AND MARKED IN THE FIELD PRIOR TO THE LET OF THIS CONTRACT.

THERE SHALL BE NO DEVIATIONS FROM THE STANDARD DRAWINGS WITHOUT PRIOR APPROVAL FROM THE ENGINNER.

ALL TRAFFIC CONTROL DESIGN, PLACEMENT, OPERATION, MAINTENANCE, AND UNIFORMITY SHALL BE IN ACCORDANCE WITH THE MOST CURRENT PRACTICES DETAILED IN THE 2018 ROADWAY STANDARD DRAWINGS.

## NOTE TO CONTRACTOR:

ALL NEW INSTALLATION OR REPLACEMENT OF GUARDRAIL AND MATERIALS ON THIS PROJECT SHALL BE FROM THE NuGuard–31 STRONG POST GUARDRAIL SYSTEM OR APPROVED EQUIVALENT. ALL END UNITS AND BRIDGE ATTACHMENTS FOR THESE SITES SHALL BE 31" MASH EQUIVALENT PRODUCTS.

UTILITY OWNERS ON THIS PROJECT ARE:

CITIZENS TELEPHONE COMPANY (COMPORIUM) (828–553–9599)
PSNC ENERGY (877–776–2427)
DUKE ENERGY (800–769–3766)

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

2018 ROADWAY ENGLISH STANDARD DRAWINGS EFF. 01–2018

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:

DIVISION 8 – INCIDENTALS

| STD.NO. | TITLE |
|---|---|
| 862.01 | Guardrail Placement |
| 862.02 | Guardrail Installation |
| 862D01 | Guardrail Placement: 25' Clear Span |