PROJECT REFERENCE NO.	SHEET NO.
80047	2A

TYPICAL SECTION NO. 1

TYPICAL SECTION NO. 2

TYPICAL SECTION NO. 3

SURFACING SCHEDULE

ITEM NO.	DESCRIPTION
C1	PROP. APPROX. 1 1/2" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 165 LBS. PER SQ. YD.
D1	PROP. APPROX. 3" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.OC, AT AN AVERAGE RATE OF 342 LBS. PER SQ YD.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.OC, AT AN AVERAGE RATE OF 456 LBS. PER SQ YD.
T	SHOULDER RECONSTRUCTION
U	EXISTING ASPHALT