STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	80047	PMP-1	

STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION
80047		CONSTRUCTION

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN
CLAY COUNTY

LOCATION: BEGINNING AT INTERSECTION OF SR-1353 AND SR-1169 AND ENDING AT INTERSECTION OF SR-1353 AND US-64

TYPE OF WORK: PAVEMENT MARKING

LIST OF ROADWAY STANDARDS

2018 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 12 - PAVEMENT MARKINGS, MARKERS AND DELINEATION	
1205.01	Pavement Markings - Line Types and Offsets
1205.02	Two-Lane and Multi-Lane Roadways
1205.04	Intersections
1205.05	Turn Lanes
1205.08	Symbols and Word Messages
1205.09	Painted Islands
1250.01	Installation Spacing

INDEX OF SHEETS

PMP-1	PAVEMENT MARKING PLAN TITLE, INDEX OF SHEETS, LIST OF APPLICABLE ROADWAY STANDARD DRAWINGS, GENERAL NOTES, FINAL PAVEMENT MARKING SCHEDULE
PMP-2 THRU PMP-7	PAVEMENT MARKING PLAN

GENERAL NOTES

GENERAL NOTES: 2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

1 INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
EAGLE FORK RD	PAINT	
OLD HWY 64 E	PAINT	
EAST VINEYARD RD	PAINT	
HWY 64 E	PAINT	

2 TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

3 REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

4 UNLESS OTHERWISE SPECIFIED, HEATED-IN-PLACE THERMOPLASTIC MAY BE USED IN LIEU OF EXTRUDED THERMOPLASTIC FOR STOP BARS, SYMBOLS, CHARACTERS AND DIAGONALS. IF HEATED-IN-PLACE IS USED, IT SHALL BE PAID FOR USING THE EXTRUDED THERMOPLASTIC PAY ITEM.

PAVEMENT MARKING SCHEDULE

PAVEMENT MARKINGS

SYMBOL	DESCRIPTION
T1	WHITE STOP BAR
T2	WHITE 3' - 9' MINI-SKIP LINE
T3	WHITE 2' - 6' MINI-SKIP LINE
T4	WHITE EDGE LINE
T5	YELLOW CENTER LINE
T6	WHITE DIAGONAL LINE
UA	RIGHT TURN ARROW
UB	COMBO LEFT/STRAIGHT ARROW
UC	STRAIGHT ARROW
UD	MERGE ARROW
UE	24" YIELD LINE TRIANGLE

PROJECT: 80047

CONTRACT: DN00682