PROJECT REFERENCE NO.	SHEET NO.
80047	1A

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

INDEX OF SHEETS

1	TITLE SHEET
1A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARDS
1B	CONVENTIONAL SYMBOLS
RW01-RW04	ROW CONTROL SHEETS
2A	TYPICAL SECTIONS
2C	DETAIL OF GUARDRAIL ANCHOR UNIT
3B	ROADWAY SUMMARY SHEET
3D	DRAINAGE SUMMARY SHEET
4-13	PLAN SHEETS
PMP1-PMP7	PAVEMENT MARKING PLAN
EC1-EC9	EROSION CONTROL SHEETS
X1-X23	CROSS SECTIONS

GENERAL NOTES

GENERAL NOTES: 2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018

1 CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

2 THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.

3 DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.02 USING 3 FOOT RADII OR AS SHOWN ON THE PLANS. LOCATIONS OF DRIVES WILL BE AS SHOWN ON THE PLANS OR AS DIRECTED BY THE ENGINEER.

4 THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.

5 NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

UTILITY OWNERS:
- BLUE RIDGE MOUNTAIN EMC
DAN FRIZZELL 706-835-5265
- FRONTIER COMMUNICATIONS
JERRY FISHER 828-507-1681

LIST OF ROADWAY STANDARDS

2018 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
DIVISION 8 - INCIDENTALS	
840.31	Concrete Junction Box - 12" thru 66" Pipe
840.36	Traffic Bearing Grated Drop Inlet
862.01	Guardrail Placement
862.02	Guardrail Installation
862.03	Structure Anchor Units
866.04	Barbed Wire Fence - with Wood Posts (2 - 7 Strands)
876.01	Rip Rap in Channels
876.02	Guide for Rip Rap at Pipe Outlets
DIVISION 11 - WORK ZONE TRAFFIC CONTROL	
1101.01	Work Zone Advance Warning Signs
1110.01	Stationary Work Zone Signs
1101.11	Traffic Control Design Tables