DocuSign Envelope ID: 02E0D176-D589-4AAD-9AB6-D7EB2DD8B804

T.I.P.: R-5771

# STATE OF NORTH CAROLINA
# DEPARTMENT OF TRANSPORTATION

| TIP NO. | SHEET NO. |
|---|---|
| R-5771 | SIGN-1 |

APPROVED: DocuSigned by: William J. Hamilton A0560D704648484...

DATE: 3/22/2017

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 32396 ENGINEER WILLIAM J. HAMILTON

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

# SIGNING PLAN
# HENDERSON COUNTY

## LOCATION: SR 1690 (BROADPOINTE DRIVE) INCLUDING BRIDGE #107 OVER McDOWELL CREEK

## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 904.10 | ORIENTATION OF GROUND MOUNTED SIGNS |
| 904.50 | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |

## GENERAL NOTES

- SIGNS FURNISHED BY STATE
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

## SUMMARY OF QUANTITIES

| ITEM NO. DESC. NO. | ITEM NO. SECT. NO. | ITEM DESCRIPTION | QUANTITY | UNIT |
|---|---|---|---|---|
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 50 | L.F. |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 3 | EA. |
| 4155000000 | 907 | DISPOSAL OF SIGN SYSTEM, U-CHANNEL | 3 | EA. |

## INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| SIGN-1 | TITLE SHEET |
| SIGN-2 | TYPE E SIGNS |
| SIGN-3 | EXISTING AND PROPOSED SIGNING DETAIL |



PLAN PREPARED BY: Ramey Kemp & Associates

W.JASON HAMILTON, P.E., PTOE — PROJECT MANAGER

TIMOTHY S. POPELKA, EI — PROJECT ENGINEER

RAMEY KEMP & ASSOCIATES, INC. Transportation Engineers
5808 Faringdon Place, Suite 100
Raleigh, North Carolina 27609
919-872-5115 Tel, 919-878-5416 Fax.
www.rameykemp.com