



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION


ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

May 21, 2021

ADDENDUM # 4

To: Plan Holders

From: Andrew Buchanan 
Assistant Division Proposal Engineer

RE: **Question & Answer**
Contract ID: DN00751
County: Transylvania
Letting Date: May 25, 2021

A prospective bidder has asked the following questions regarding the US 64 Brevard Academy turn lane portion of contract DN00751:

Question #1: *Please provide a typical pavement section for the US64 turn lanes.*

Answer #1: A typical section drawing will not be provided. Please refer to pavement design located at the bottom right corner of sheet CT-2.1 and the cross sections.

Question #2: *If off site borrow is required for proposed widening/slopes, will there be a pay item or incidental?*

Answer #2: Borrow excavation is included in the L.S. Grading pay item.

Question #3: *Will the existing 4' shoulders & entrance on US 64 be removed before widening occurs?*

Answer #3: The paved shoulder and entrance on US 64 will not be removed.

Question #4: *Will the existing entrance to Brevard Academy off US 64 be closed during construction?*

Answer #4: It will need to be closed for short periods of time but it shall not be closed for the duration.

Question #5: *Is the intent of ICT #4 for closing the entrance of Brevard Academy?*

Answer #5: ICT #4 is not associated with the Brevard Academy turn lane portion of this contract. ICT #4 covers a lane closure for the drainage box on S. Caldwell St/US 64 BUS.

Question #6: *Is the entrance being rebuilt with the same typical as the roadway?*

Answer #6: Yes

Question #7: *Plans call for a seal coat on Glade Creek Rd. There is no item on bid schedule. Will it be resurfaced/rebuilt?*

Answer#7: Disregard note on sheet CT-2.1 calling for seal coat on Glade Creek. Glade Creek Rd. will be resurfaced with hot mix.

Question #8: *Will the proposed 18" culvert be using the 654.01 pavement repair details?*

Answer #8: There is no place on the project where a culvert is being installed under existing asphalt.

These revisions do not change bid items or the associated quantities.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.