CONTRACT ID: DN11988718 TIP PROJECT: W-5714K

CONTRACT ID #		SHEET NO.
DN11988718		
STATE PROJECT	F.A. PROJECT NO.	DESCRIPTION
	HSIP-0106(005)	Construction

https://www.google.com/maps/dir/34.9956934,-83.3370857/35.0473668,-83.2282267/@35.0254473,-83.2745648,13.25z/data=!4m2!4m1!3e0?hl=en

N

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

MACON COUNTY

LOCATION:

On: NC 106
From: Georgia State Line
To: SR 1618 Glen Falls Road
Length: 8.6 miles

Type of Work:

Centerline: 14" Sinusoidal Rumble Strips 45,408 LF
Edge Line: Line Removal 90,816 LF
Centerline: 90 Mil Thermoplastic 90,816 LF
Edge Line: 90 Mil Thermoplastic 90,816 LF

STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

TRAFFIC ENGINEERING DIVISION 14