DocuSign Envelope ID: 2BE31C22-FB8E-48C1-A52C-9ED40587F8BE

PROJECT : 47333

TIP NO.	SHEET NO.
47333	SIGN-1

APPROVED: DocuSigned by: J.B. Setzer 6F60A1CE17FE459...

DATE: 5/9/2018 1:52:11 PM PDT

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 17355 ENGINEER J.B. SETZER

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLAN
HENDERSON COUNTY

LOCATION: TURN LANES ON NC 191 (HAYWOOD ROAD) AND SR 1331 (BANNER FARM ROAD)

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHEILDS
903.10	GROUND MOUNTED SIGN SUPPORT
904.10	ORIENTATION OF GROUND MOUNTED SIGN
904.20	SECONDARY SIGN MOUNTING
904.50	MOUNTING ON TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POST

GENERAL NOTES

. SIGNS FURNISHED BY STATE

.

. ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.

. IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.

. WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER

. ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.

. WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.

. THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

. DO NOT BEGIN FABRICATION FOR TYPES A & B SIGNS MOUNTED ON OVERHEAD STRUCTURES OR STEEL SUPPORTS UNTIL "S" DIMENSIONS HAVE BEEN FIELD VERIFIED.

. SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4102000000	904	SIGN ERECTION, TYPE E	2	EA
4108000000	904	SIGN ERECTION, TYPE F	5	EA
4915000000	1264	7' U-CHANNEL POSTS	7	EA

INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET
SIGN-2	TYPE 'E' AND 'F' SIGNS
SIGN-3	PROPOSED SIGNS

PLAN PREPARED BY: Vaughn & Melton Engineering

JOEL SETZER, P.E. — PROJECT ENGINEER

COURTNEY EVANS, EIT — PROJECT DESIGN ENGINEER

V&M Vaughn & Melton Consulting Engineers
Asheville, North Carolina 828-253-2796
Raleigh, NC 919-577-9455 · Tri-Cities, TN 423-467-8401 · Charleston, SC 843-974-5650 · Spartanburg, SC 864-574-4775 · Charlotte, NC 704-357-0488 · Tri-Cities, TN 423-467-8401 · Middlesboro, KY 606-248-6600 · Boone, NC 828-355-9933 · Knoxville, TN 865-546-5800 · Atlanta, GA 770-427-3509

Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved

5/9/2018
V:\Asheville\transportation\31732-01, NC 191 at Banner Farm Road, Henderson Co\Traffic\Signing\CADD\Signing Layout Plans\47333_SIGN-1.dgn
User:cjmartell