T.I.P.: WBS 47851

CONTRACT:

| TIP NO. | SHEET NO. |
|---|---|
| WBS 47851 | SIGN-1 |

APPROVED: _____

DATE: _____

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 046300 ENGINEER NICHOLAS E. BURNS

DocuSigned by: Nicholas E. Burns 7/8/2019

77B48AEA400A4E8...

# STATE OF NORTH CAROLINA
# DEPARTMENT OF TRANSPORTATION

# SIGNING PLAN
# HAYWOOD COUNTY

## LOCATION: ROAD REALIGNMENT FOR US 276 (PIGEON ROAD) AND SR 1924 (SONOMA ROAD)

## GENERAL NOTES

- SIGNS FURNISHED BY STATE
- SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR PAVEMENT MARKINGS. SEE TRAFFIC CONTROL PLANS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER.
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- THE BACKGROUND FOR TYPE E & F SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.
- SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 904.10 | ORIENTATION OF GROUND MOUNTED SIGNS |
| 904.50 | MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS |

## SUMMARY OF QUANTITIES

| ITEM NO. DESC. NO. | ITEM NO. SECT. NO. | ITEM DESCRIPTION | QUANTITY | UNIT |
|---|---|---|---|---|
| 4072000000 | 903 | SUPPORTS, 3 LB STEEL U-CHANNEL | 82 | L.F. |
| 4102000000 | 904 | SIGN ERECTION, TYPE E | 2 | EA. |
| 4108000000 | 904 | SIGN ERECTION, TYPE F | 2 | EA. |
| 4116100000 | 904 | SIGN ERECTION, RELOCATE SIGN TYPE E | 3 | EA. |
| 4192000000 | 907 | DISPOSAL OF SUPPORT, U-CHANNEL | 2 | EA. |
| 4238000000 | 907 | DISPOSAL OF SIGN, D, E OR F | 2 | EA. |

## "E" SIGNS

(401) QUANTITY REQ'D 1

(402) QUANTITY REQ'D 1

## "F" SIGNS

(501) QUANTITY REQ'D 1

(502) QUANTITY REQ'D 1

## INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| SIGN-1 | TITLE SHEET, SIGN DESIGN, E SIGNS, F SIGNS, NOTES, AND QUANTITIES |
| SIGN-2 | PROPOSED SIGNS |


PLAN REVIEWED BY: N.C.D.O.T. HIGHWAY DIVISION 14

JONATHAN WOODARD — NCDOT PROJECT MANAGER

ETHAN MILLER — NCDOT PROJECT ENGINEER

DIVISION OF HIGHWAYS · STATE OF NORTH CAROLINA · DEPARTMENT OF TRANSPORTATION · WORK ZONE TRAFFIC CONTROL UNIT

PLAN PREPARED BY: Ramey Kemp & Associates

NICHOLAS E. BURNS, P.E. — PROJECT MANAGER

ZACHARY M. ESPOSITO, E.I. — PROJECT ENGINEER


RAMEY KEMP & ASSOCIATES, INC.
Transportation Engineers
8307 University Executive Park Drive, Suite 260
Charlotte, North Carolina 28262
704-549-4200 Tel. 704-549-4277 Fax.
www.rameykemp.com