

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
NC	17BP.14.R.24	1A	15

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

GEOTECHNICAL ENGINEERING UNIT

STRUCTURE SUBSURFACE INVESTIGATION

PROJECT 17BP.14.R.24
COUNTY TRANSYLVANIA
PROJECT DESCRIPTION REPLACE STRUCTURE
NO. 870113 ON SR 1346 OVER NICHOLSON
CREEK
SITE DESCRIPTION PROPOSED BRIDGE ON
SR 1346 OVER NICHOLSON CREEK

CAUTION NOTICE

THE SUBSURFACE INFORMATION AND THE SUBSURFACE INVESTIGATION ON WHICH IT IS BASED WAS MADE FOR THE PURPOSE OF STUDY, PLANNING AND DESIGN, AND NOT FOR CONSTRUCTION OR PAY PURPOSES. THE VARIOUS FIELD BORING LOGS, ROCK CORES, AND SOIL TEST DATA AVAILABLE MAY BE REVIEWED OR INSPECTED IN RALEIGH BY CONTACTING THE N. C. DEPARTMENT OF TRANSPORTATION, GEOTECHNICAL UNIT @ (919) 250-4088. NEITHER THE SUBSURFACE PLANS AND REPORTS, NOR THE FIELD BORING LOGS, ROCK CORES, OR SOIL TEST DATA IS PART OF THE CONTRACT.


THE BIDDER OR CONTRACTOR IS CAUTIONED THAT DETAILS SHOWN ON THE SUBSURFACE PLANS ARE PRELIMINARY ONLY AND IN MANY CASES THE FINAL DESIGN DETAILS ARE DIFFERENT. FOR BIDDING AND CONSTRUCTION PURPOSES, REFER TO THE CONSTRUCTION PLANS AND DOCUMENTS FOR FINAL DESIGN INFORMATION ON THIS PROJECT. THE DEPARTMENT DOES NOT WARRANT OR GUARANTEE THE SUFFICIENCY OR ACCURACY OF THE INVESTIGATION MADE, NOR THE INTERPRETATIONS MADE OR OPINION OF THE DEPARTMENT AS TO THE TYPE OF MATERIALS AND CONDITIONS TO BE ENCOUNTERED. THE BIDDER OR CONTRACTOR IS CAUTIONED TO MAKE SUCH INDEPENDENT SUBSURFACE INVESTIGATIONS AS HE DEEMS NECESSARY TO SATISFY HIMSELF AS TO CONDITIONS TO BE ENCOUNTERED ON THIS PROJECT. THE CONTRACTOR SHALL HAVE NO CLAIM FOR ADDITIONAL COMPENSATION OR FOR AN EXTENSION OF TIME FOR ANY REASON RESULTING FROM THE ACTUAL CONDITIONS ENCOUNTERED AT THE SITE DIFFERING FROM THOSE INDICATED IN THE SUBSURFACE INFORMATION.

NOTE - THE INFORMATION CONTAINED HEREIN IS NOT IMPLIED OR GUARANTEED BY THE N. C. DEPARTMENT OF TRANSPORTATION AS BEING ACCURATE NOR IT IS CONSIDERED TO BE PART OF THE PLANS, SPECIFICATIONS, OR CONTRACT FOR THE PROJECT.

NOTE - BY HAVING REQUESTED THIS INFORMATION THE CONTRACTOR SPECIFICALLY WAIVES ANY CLAIMS FOR INCREASED COMPENSATION OR EXTENSION OF TIME BASED ON DIFFERENCES BETWEEN THE CONDITIONS INDICATED HEREIN AND THE ACTUAL CONDITIONS AT THE PROJECT SITE.

GENERAL SOIL AND ROCK STRATA DESCRIPTIONS AND INDICATED BOUNDARIES ARE BASED ON A GEOTECHNICAL INTERPRETATION OF ALL AVAILABLE SUBSURFACE DATA AND MAY NOT NECESSARILY REFLECT THE ACTUAL SUBSURFACE CONDITIONS BETWEEN BORINGS OR BETWEEN SAMPLED STRATA WITHIN THE BOREHOLE. THE LABORATORY SAMPLE DATA AND THE IN SITU (IN-PLACE) TEST DATA CAN BE RELIED ON ONLY TO THE DEGREE OF RELIABILITY INHERENT IN THE STANDARD TEST METHOD. THE OBSERVED WATER LEVELS OR SOIL MOISTURE CONDITIONS INDICATED IN THE SUBSURFACE INVESTIGATIONS ARE AS RECORDED AT THE TIME OF THE INVESTIGATION. THESE WATER LEVELS OR SOIL MOISTURE CONDITIONS MAY VARY CONSIDERABLY WITH TIME ACCORDING TO CLIMATIC CONDITIONS INCLUDING TEMPERATURES, PRECIPITATION AND WIND, AS WELL AS OTHER NON-CLIMATIC FACTORS.

INVESTIGATED BY S&ME, INC. PERSONNEL J. WILLIAMSON
CHECKED BY STEWART S. LANEY L. CAMPOS
SUBMITTED BY S&ME, INC. K. HILL
DATE 2/8/2013 N. PAGE
C. ODOM
R. OSWALD
J. JACKSON



SEAL

SIGNATURE

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
NC	17BP.14.R.24	1B	15

STATE OF NORTH CAROLINA

DEPARTMENT OF TRANSPORTATION

DIVISION OF HIGHWAYS

GEOTECHNICAL ENGINEERING UNIT

STRUCTURE

SUBSURFACE INVESTIGATION

PROJECT 17BP.14.R.24
COUNTY TRANSYLVANIA
PROJECT DESCRIPTION REPLACE STRUCTURE
NO. 870113 ON SR 1346 OVER NICHOLSON
CREEK
SITE DESCRIPTION PROPOSED BRIDGE ON
SR 1346 OVER NICHOLSON CREEK





TABLE OF CONTENTS



NCDOT Geotechnical Unit Soil and Rock Classification Sheet	Sheets 2A & 2B
Site Vicinity Map	Sheet 3
Field Exploration Plan	Sheet 4
Test Boring Logs	Sheets 5 – 11
Site Photographs	Sheets 12 – 15

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL UNIT SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

SOIL DESCRIPTION										GRADATION																																																																																									
SOIL IS CONSIDERED TO BE THE UNCONSOLIDATED, SEMI-CONSOLIDATED OR WEATHERED EARTH MATERIALS WHICH CAN BE PENETRATED WITH A CONTINUOUS FLIGHT POWER AUGER, AND WHICH YIELDS LESS THAN 100 BLOWS PER FOOT ACCORDING TO STANDARD PENETRATION TEST (AASHTO T206, ASTM D-1586). SOIL CLASSIFICATION IS BASED ON THE AASHTO SYSTEM AND BASIC DESCRIPTIONS GENERALLY SHALL INCLUDE: CONSISTENCY, COLOR, TEXTURE, MOISTURE, AASHTO CLASSIFICATION, AND OTHER PERTINENT FACTORS SUCH AS MINERALOGICAL COMPOSITION, ANGULARITY, STRUCTURE, PLASTICITY, ETC. EXAMPLE: VERY STIFF, GRAY SILTY CLAY, MOIST WITH INTERBEDDED FINE SAND LAYERS, HIGHLY PLASTIC, A-7-6										WELL GRADED - INDICATES A GOOD REPRESENTATION OF PARTICLE SIZES FROM FINE TO COARSE UNIFORM - INDICATES THAT SOIL PARTICLES ARE ALL APPROXIMATELY THE SAME SIZE. (ALSO POORLY GRADED) GAP-GRADED - INDICATES A MIXTURE OF UNIFORM PARTICLES OF TWO OR MORE SIZES.																																																																																									
										ANGULARITY OF GRAINS																																																																																									
SOIL LEGEND AND AASHTO CLASSIFICATION										MINERALOGICAL COMPOSITION																																																																																									
										MINERAL NAMES SUCH AS QUARTZ, FELDSPAR, MICA, TALC, KAOLIN, ETC. ARE USED IN DESCRIPTIONS WHENEVER THEY ARE CONSIDERED OF SIGNIFICANCE.																																																																																									
GENERAL CLASS. GRANULAR MATERIALS (≤35% PASSING #200) SILT-CLAY MATERIALS (>35% PASSING #200) ORGANIC MATERIALS										COMPRESSIBILITY																																																																																									
										SLIGHTLY COMPRESSIBLE MODERATELY COMPRESSIBLE HIGHLY COMPRESSIBLE										LIQUID LIMIT LESS THAN 30 LIQUID LIMIT 31-50 LIQUID LIMIT GREATER THAN 50																																																																															
GROUP CLASS. A-1-a, A-1-b, A-2-4, A-2-5, A-2-6, A-2-7, A-4, A-5, A-6, A-7, A-7-5, A-7-6, A-3, A-3, A-6, A-7										PERCENTAGE OF MATERIAL																																																																																									
										SYMBOL										<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>ORGANIC MATERIAL</th> <th>GRANULAR SOILS</th> <th>SILT-CLAY SOILS</th> <th>OTHER MATERIAL</th> </tr> </thead> <tbody> <tr> <td>TRACE OF ORGANIC MATTER</td> <td>2 - 3%</td> <td>3 - 5%</td> <td>TRACE</td> </tr> <tr> <td>LITTLE ORGANIC MATTER</td> <td>3 - 5%</td> <td>5 - 12%</td> <td>LITTLE</td> </tr> <tr> <td>MODERATELY ORGANIC</td> <td>5 - 10%</td> <td>12 - 20%</td> <td>SOME</td> </tr> <tr> <td>HIGHLY ORGANIC</td> <td>>10%</td> <td>>20%</td> <td>HIGHLY</td> </tr> <tr> <td></td> <td></td> <td></td> <td>1 - 10%</td> </tr> <tr> <td></td> <td></td> <td></td> <td>10 - 20%</td> </tr> <tr> <td></td> <td></td> <td></td> <td>20 - 35%</td> </tr> <tr> <td></td> <td></td> <td></td> <td>35% AND ABOVE</td> </tr> </tbody> </table>										ORGANIC MATERIAL	GRANULAR SOILS	SILT-CLAY SOILS	OTHER MATERIAL	TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE	LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE	MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME	HIGHLY ORGANIC	>10%	>20%	HIGHLY				1 - 10%				10 - 20%				20 - 35%				35% AND ABOVE																																		
ORGANIC MATERIAL	GRANULAR SOILS	SILT-CLAY SOILS	OTHER MATERIAL																																																																																																
TRACE OF ORGANIC MATTER	2 - 3%	3 - 5%	TRACE																																																																																																
LITTLE ORGANIC MATTER	3 - 5%	5 - 12%	LITTLE																																																																																																
MODERATELY ORGANIC	5 - 10%	12 - 20%	SOME																																																																																																
HIGHLY ORGANIC	>10%	>20%	HIGHLY																																																																																																
			1 - 10%																																																																																																
			10 - 20%																																																																																																
			20 - 35%																																																																																																
			35% AND ABOVE																																																																																																
% PASSING # 10 # 40 # 200										GROUND WATER																																																																																									
										TRACE OF ORGANIC MATTER LITTLE ORGANIC MATTER MODERATELY ORGANIC HIGHLY ORGANIC										WATER LEVEL IN BORE HOLE IMMEDIATELY AFTER DRILLING. STATIC WATER LEVEL AFTER 24 HOURS. PERCHED WATER, SATURATED ZONE OR WATER BEARING STRATA HOLE CAVE SPRING OR SEEPAGE																																																																															
LIQUID LIMIT PLASTIC INDEX GROUP INDEX										MISCELLANEOUS SYMBOLS																																																																																									
										USUAL TYPES OF MAJOR MATERIALS STONE FRAGS. GRAVEL AND SAND FINE SAND SILTY OR CLAYEY GRAVEL AND SAND SILTY SOILS CLAYEY SOILS										<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td></td> <td>ROADWAY EMBANKMENT WITH SOIL DESCRIPTION</td> <td></td> <td>SPT TEST BORING</td> <td></td> <td>SAMPLE DESIGNATIONS</td> </tr> <tr> <td></td> <td>SOIL SYMBOL</td> <td></td> <td>AUGER BORING</td> <td></td> <td>S - BULK SAMPLE</td> </tr> <tr> <td></td> <td>ARTIFICIAL FILL OTHER THAN ROADWAY EMBANKMENTS</td> <td></td> <td>CORE BORING</td> <td></td> <td>SS - SPLIT SPOON SAMPLE</td> </tr> <tr> <td></td> <td>INFERRED SOIL BOUNDARIES</td> <td></td> <td>MONITORING WELL</td> <td></td> <td>ST - SHELBY TUBE SAMPLE</td> </tr> <tr> <td></td> <td>INFERRED ROCK LINE</td> <td></td> <td>PIEZOMETER</td> <td></td> <td>RS - ROCK SAMPLE</td> </tr> <tr> <td></td> <td>ALLUVIAL SOIL BOUNDARY</td> <td></td> <td>INSTALLATION</td> <td></td> <td>RT - RECOMPACTED TRIAXIAL SAMPLE</td> </tr> <tr> <td></td> <td>DIP/DIP DIRECTION OF ROCK STRUCTURES</td> <td></td> <td>SLOPE INDICATOR</td> <td></td> <td>CBR - CBR SAMPLE</td> </tr> <tr> <td></td> <td>SOUNDING ROD</td> <td></td> <td>SPT N-VALUE</td> <td></td> <td></td> </tr> </table>											ROADWAY EMBANKMENT WITH SOIL DESCRIPTION		SPT TEST BORING		SAMPLE DESIGNATIONS		SOIL SYMBOL		AUGER BORING		S - BULK SAMPLE		ARTIFICIAL FILL OTHER THAN ROADWAY EMBANKMENTS		CORE BORING		SS - SPLIT SPOON SAMPLE		INFERRED SOIL BOUNDARIES		MONITORING WELL		ST - SHELBY TUBE SAMPLE		INFERRED ROCK LINE		PIEZOMETER		RS - ROCK SAMPLE		ALLUVIAL SOIL BOUNDARY		INSTALLATION		RT - RECOMPACTED TRIAXIAL SAMPLE		DIP/DIP DIRECTION OF ROCK STRUCTURES		SLOPE INDICATOR		CBR - CBR SAMPLE		SOUNDING ROD		SPT N-VALUE																								
	ROADWAY EMBANKMENT WITH SOIL DESCRIPTION		SPT TEST BORING		SAMPLE DESIGNATIONS																																																																																														
	SOIL SYMBOL		AUGER BORING		S - BULK SAMPLE																																																																																														
	ARTIFICIAL FILL OTHER THAN ROADWAY EMBANKMENTS		CORE BORING		SS - SPLIT SPOON SAMPLE																																																																																														
	INFERRED SOIL BOUNDARIES		MONITORING WELL		ST - SHELBY TUBE SAMPLE																																																																																														
	INFERRED ROCK LINE		PIEZOMETER		RS - ROCK SAMPLE																																																																																														
	ALLUVIAL SOIL BOUNDARY		INSTALLATION		RT - RECOMPACTED TRIAXIAL SAMPLE																																																																																														
	DIP/DIP DIRECTION OF ROCK STRUCTURES		SLOPE INDICATOR		CBR - CBR SAMPLE																																																																																														
	SOUNDING ROD		SPT N-VALUE																																																																																																
GEN. RATING AS A SUBGRADE EXCELLENT TO GOOD FAIR TO POOR FAIR TO POOR POOR UNSUITABLE										ABBREVIATIONS																																																																																									
										P.I. OF A-7-5 ≤ L.L. - 30 : P.I. OF A-7-6 > L.L. - 30										AR - AUGER REFUSAL BT - BORING TERMINATED CL - CLAY CPT - CONE PENETRATION TEST CSE. - COARSE DMT - DILATOMETER TEST DPT - DYNAMIC PENETRATION TEST e - VOID RATIO F. - FINE FOSS. - FOSSILIFEROUS FRAC. - FRACTURED FRAGS. - FRAGMENTS MED. - MEDIUM PMT - PRESSUREMETER TEST SD. - SAND, SANDY SL. - SILT, SILTY SLL. - SLIGHTLY TRC. - TRICONE REFUSAL W - UNIT WEIGHT W _d - DRY UNIT WEIGHT W - MOISTURE CONTENT V. - VERY VST - VANE SHEAR TEST																																																																															
CONSISTENCY OR DENSENESS										EQUIPMENT USED ON SUBJECT PROJECT																																																																																									
										<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>PRIMARY SOIL TYPE</th> <th>COMPACTNESS OR CONSISTENCY</th> <th>RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)</th> <th>RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT²)</th> </tr> </thead> <tbody> <tr> <td rowspan="4">GENERALLY GRANULAR MATERIAL (NON-COHESIVE)</td> <td>VERY LOOSE</td> <td><4</td> <td></td> </tr> <tr> <td>LOOSE</td> <td>4 TO 10</td> <td></td> </tr> <tr> <td>MEDIUM DENSE</td> <td>10 TO 30</td> <td>N/A</td> </tr> <tr> <td>DENSE</td> <td>30 TO 50</td> <td></td> </tr> <tr> <td rowspan="6">GENERALLY SILT-CLAY MATERIAL (COHESIVE)</td> <td>VERY SOFT</td> <td><2</td> <td><0.25</td> </tr> <tr> <td>SOFT</td> <td>2 TO 4</td> <td>0.25 TO 0.5</td> </tr> <tr> <td>MEDIUM STIFF</td> <td>4 TO 8</td> <td>0.5 TO 1</td> </tr> <tr> <td>STIFF</td> <td>8 TO 15</td> <td>1 TO 2</td> </tr> <tr> <td>VERY STIFF</td> <td>15 TO 30</td> <td>2 TO 4</td> </tr> <tr> <td>HARD</td> <td>>30</td> <td>>4</td> </tr> </tbody> </table>										PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)	GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	<4		LOOSE	4 TO 10		MEDIUM DENSE	10 TO 30	N/A	DENSE	30 TO 50		GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT	<2	<0.25	SOFT	2 TO 4	0.25 TO 0.5	MEDIUM STIFF	4 TO 8	0.5 TO 1	STIFF	8 TO 15	1 TO 2	VERY STIFF	15 TO 30	2 TO 4	HARD	>30	>4	<table border="1" style="width: 100%; border-collapse: collapse;"> <tr> <td><input type="checkbox"/> MOBILE B- _____</td> <td><input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER</td> <td><input checked="" type="checkbox"/> AUTOMATIC</td> <td><input type="checkbox"/> MANUAL</td> </tr> <tr> <td><input type="checkbox"/> DIEDRICH D-50</td> <td><input type="checkbox"/> 8" HOLLOW AUGERS</td> <td colspan="2">CORE SIZE:</td> </tr> <tr> <td><input type="checkbox"/> CME-550x</td> <td><input type="checkbox"/> HARD FACED FINGER BITS</td> <td><input type="checkbox"/> -B _____</td> <td></td> </tr> <tr> <td><input type="checkbox"/> CME-750</td> <td><input type="checkbox"/> TUNG.-CARBIDE INSERTS</td> <td><input type="checkbox"/> -N _____</td> <td></td> </tr> <tr> <td><input type="checkbox"/> PORTABLE HOIST</td> <td><input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER</td> <td><input type="checkbox"/> -H _____</td> <td></td> </tr> <tr> <td><input checked="" type="checkbox"/> OTHER CME-45B</td> <td><input type="checkbox"/> TRICONE _____" STEEL TEETH</td> <td colspan="2">HAND TOOLS:</td> </tr> <tr> <td><input type="checkbox"/> OTHER _____</td> <td><input type="checkbox"/> TRICONE _____" TUNG.-CARB.</td> <td><input type="checkbox"/> POST HOLE DIGGER</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> CORE BIT</td> <td><input checked="" type="checkbox"/> HAND AUGER</td> <td></td> </tr> <tr> <td></td> <td><input checked="" type="checkbox"/> OTHER 3-1/4" H.S.A.</td> <td><input checked="" type="checkbox"/> SOUNDING ROD</td> <td></td> </tr> <tr> <td></td> <td><input type="checkbox"/> OTHER _____</td> <td><input type="checkbox"/> VANE SHEAR TEST</td> <td></td> </tr> <tr> <td></td> <td></td> <td><input checked="" type="checkbox"/> OTHER DCP</td> <td></td> </tr> </table>										<input type="checkbox"/> MOBILE B- _____	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	<input checked="" type="checkbox"/> AUTOMATIC	<input type="checkbox"/> MANUAL	<input type="checkbox"/> DIEDRICH D-50	<input type="checkbox"/> 8" HOLLOW AUGERS	CORE SIZE:		<input type="checkbox"/> CME-550x	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -B _____		<input type="checkbox"/> CME-750	<input type="checkbox"/> TUNG.-CARBIDE INSERTS	<input type="checkbox"/> -N _____		<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> -H _____		<input checked="" type="checkbox"/> OTHER CME-45B	<input type="checkbox"/> TRICONE _____" STEEL TEETH	HAND TOOLS:		<input type="checkbox"/> OTHER _____	<input type="checkbox"/> TRICONE _____" TUNG.-CARB.	<input type="checkbox"/> POST HOLE DIGGER			<input type="checkbox"/> CORE BIT	<input checked="" type="checkbox"/> HAND AUGER			<input checked="" type="checkbox"/> OTHER 3-1/4" H.S.A.
PRIMARY SOIL TYPE	COMPACTNESS OR CONSISTENCY	RANGE OF STANDARD PENETRATION RESISTANCE (N-VALUE)	RANGE OF UNCONFINED COMPRESSIVE STRENGTH (TONS/FT ²)																																																																																																
GENERALLY GRANULAR MATERIAL (NON-COHESIVE)	VERY LOOSE	<4																																																																																																	
	LOOSE	4 TO 10																																																																																																	
	MEDIUM DENSE	10 TO 30	N/A																																																																																																
	DENSE	30 TO 50																																																																																																	
GENERALLY SILT-CLAY MATERIAL (COHESIVE)	VERY SOFT	<2	<0.25																																																																																																
	SOFT	2 TO 4	0.25 TO 0.5																																																																																																
	MEDIUM STIFF	4 TO 8	0.5 TO 1																																																																																																
	STIFF	8 TO 15	1 TO 2																																																																																																
	VERY STIFF	15 TO 30	2 TO 4																																																																																																
	HARD	>30	>4																																																																																																
<input type="checkbox"/> MOBILE B- _____	<input type="checkbox"/> 6" CONTINUOUS FLIGHT AUGER	<input checked="" type="checkbox"/> AUTOMATIC	<input type="checkbox"/> MANUAL																																																																																																
<input type="checkbox"/> DIEDRICH D-50	<input type="checkbox"/> 8" HOLLOW AUGERS	CORE SIZE:																																																																																																	
<input type="checkbox"/> CME-550x	<input type="checkbox"/> HARD FACED FINGER BITS	<input type="checkbox"/> -B _____																																																																																																	
<input type="checkbox"/> CME-750	<input type="checkbox"/> TUNG.-CARBIDE INSERTS	<input type="checkbox"/> -N _____																																																																																																	
<input type="checkbox"/> PORTABLE HOIST	<input type="checkbox"/> CASING <input type="checkbox"/> W/ ADVANCER	<input type="checkbox"/> -H _____																																																																																																	
<input checked="" type="checkbox"/> OTHER CME-45B	<input type="checkbox"/> TRICONE _____" STEEL TEETH	HAND TOOLS:																																																																																																	
<input type="checkbox"/> OTHER _____	<input type="checkbox"/> TRICONE _____" TUNG.-CARB.	<input type="checkbox"/> POST HOLE DIGGER																																																																																																	
	<input type="checkbox"/> CORE BIT	<input checked="" type="checkbox"/> HAND AUGER																																																																																																	
	<input checked="" type="checkbox"/> OTHER 3-1/4" H.S.A.	<input checked="" type="checkbox"/> SOUNDING ROD																																																																																																	
	<input type="checkbox"/> OTHER _____	<input type="checkbox"/> VANE SHEAR TEST																																																																																																	
		<input checked="" type="checkbox"/> OTHER DCP																																																																																																	
TEXTURE OR GRAIN SIZE										U.S. STD. SIEVE SIZE OPENING (MM)																																																																																									
																				<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>BOULDER (BLDR.)</th> <th>COBBLE (COB.)</th> <th>GRAVEL (GR.)</th> <th>COARSE SAND (CSE. SD.)</th> <th>FINE SAND (F. SD.)</th> <th>SILT (SL.)</th> <th>CLAY (CL.)</th> </tr> </thead> <tbody> <tr> <td>GRAIN MM 305</td> <td>75</td> <td>2.0</td> <td>0.25</td> <td>0.05</td> <td>0.005</td> <td></td> </tr> <tr> <td>IN. 12"</td> <td>3"</td> <td></td> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>										BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)	GRAIN MM 305	75	2.0	0.25	0.05	0.005		IN. 12"	3"																																																						
BOULDER (BLDR.)	COBBLE (COB.)	GRAVEL (GR.)	COARSE SAND (CSE. SD.)	FINE SAND (F. SD.)	SILT (SL.)	CLAY (CL.)																																																																																													
GRAIN MM 305	75	2.0	0.25	0.05	0.005																																																																																														
IN. 12"	3"																																																																																																		
SOIL MOISTURE - CORRELATION OF TERMS										PLASTICITY																																																																																									
																				<table border="1" style="width: 100%; border-collapse: collapse;"> <thead> <tr> <th>SOIL MOISTURE SCALE (ATTERBERG LIMITS)</th> <th>FIELD MOISTURE DESCRIPTION</th> <th>GUIDE FOR FIELD MOISTURE DESCRIPTION</th> </tr> </thead> <tbody> <tr> <td>LL - LIQUID LIMIT</td> <td>- SATURATED - (SAT.)</td> <td>USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE</td> </tr> <tr> <td>PL - PLASTIC LIMIT</td> <td>- WET - (W)</td> <td>SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE</td> </tr> <tr> <td>OM - OPTIMUM MOISTURE SHRINKAGE LIMIT</td> <td>- MOIST - (M)</td> <td>SOLID; AT OR NEAR OPTIMUM MOISTURE</td> </tr> <tr> <td></td> <td>- DRY - (D)</td> <td>REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE</td> </tr> </tbody> </table>										SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION	LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE	PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE	OM - OPTIMUM MOISTURE SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE		- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																							
SOIL MOISTURE SCALE (ATTERBERG LIMITS)	FIELD MOISTURE DESCRIPTION	GUIDE FOR FIELD MOISTURE DESCRIPTION																																																																																																	
LL - LIQUID LIMIT	- SATURATED - (SAT.)	USUALLY LIQUID; VERY WET, USUALLY FROM BELOW THE GROUND WATER TABLE																																																																																																	
PL - PLASTIC LIMIT	- WET - (W)	SEMISOLID; REQUIRES DRYING TO ATTAIN OPTIMUM MOISTURE																																																																																																	
OM - OPTIMUM MOISTURE SHRINKAGE LIMIT	- MOIST - (M)	SOLID; AT OR NEAR OPTIMUM MOISTURE																																																																																																	
	- DRY - (D)	REQUIRES ADDITIONAL WATER TO ATTAIN OPTIMUM MOISTURE																																																																																																	
NONPLASTIC LOW PLASTICITY MED. PLASTICITY HIGH PLASTICITY										PLASTICITY INDEX (PI) 0-5 6-15 16-25 26 OR MORE																																																																																									
																				DRY STRENGTH VERY LOW SLIGHT MEDIUM HIGH																																																																															
COLOR DESCRIPTIONS MAY INCLUDE COLOR OR COLOR COMBINATIONS (TAN, RED, YEL-BRN, BLUE-GRAY) MODIFIERS SUCH AS LIGHT, DARK, STREAKED, ETC. ARE USED TO DESCRIBE APPEARANCE.										REVISIONS																																																																																									
																				REVISED 10/08/2009																																																																															

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION DIVISION OF HIGHWAYS GEOTECHNICAL UNIT SOIL AND ROCK LEGEND, TERMS, SYMBOLS, AND ABBREVIATIONS

ROCK DESCRIPTION		TERMS AND DEFINITIONS	
<p>HARD ROCK IS NON-COASTAL PLAIN MATERIAL THAT WHEN TESTED, WOULD YIELD SPT REFUSAL. AN INFERRED ROCK LINE INDICATES THE LEVEL AT WHICH NON-COASTAL PLAIN MATERIAL WOULD YIELD SPT REFUSAL. SPT REFUSAL IS PENETRATION BY A SPLIT SPOON SAMPLER EQUAL TO OR LESS THAN 0.1 FOOT PER 60 BLOWS. IN NON-COASTAL PLAIN MATERIAL, THE TRANSITION BETWEEN SOIL AND ROCK IS OFTEN REPRESENTED BY A ZONE OF WEATHERED ROCK. ROCK MATERIALS ARE TYPICALLY DIVIDED AS FOLLOWS:</p>		<p>ALLUVIUM (ALLUV.) – SOILS WHICH HAVE BEEN TRANSPORTED BY WATER. AQUIFER – A WATER BEARING FORMATION OR STRATA. ARENACEOUS – APPLIED TO ROCKS THAT HAVE BEEN DERIVED FROM SAND OR THAT CONTAIN SAND. ARGILLACEOUS – APPLIED TO ALL ROCKS OR SUBSTANCES COMPOSED OF CLAY MINERALS, OR HAVING A NOTABLE PROPORTION OF CLAY IN THEIR COMPOSITION, AS SHALE, SLATE, ETC. ARTESIAN – GROUND WATER THAT IS UNDER SUFFICIENT PRESSURE TO RISE ABOVE THE LEVEL AT WHICH IT IS ENCOUNTERED, BUT WHICH DOES NOT NECESSARILY RISE TO OR ABOVE THE GROUND SURFACE. CALCAREOUS (CALC.) – SOILS WHICH CONTAIN APPRECIABLE AMOUNTS OF CALCIUM CARBONATE. COLLUVIUM – ROCK FRAGMENTS MIXED WITH SOIL DEPOSITED BY GRAVITY ON SLOPE OR AT BOTTOM OF SLOPE. CORE RECOVERY (REC.) – TOTAL LENGTH OF ALL MATERIAL RECOVERED IN THE CORE BARREL DIVIDED BY TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. DIKE – A TABULAR BODY OF IGNEOUS ROCK THAT CUTS ACROSS THE STRUCTURE OF ADJACENT ROCKS OR CUTS MASSIVE ROCK. DIP – THE ANGLE AT WHICH A STRATUM OR ANY PLANAR FEATURE IS INCLINED FROM THE HORIZONTAL. DIP DIRECTION (DIP AZIMUTH) – THE DIRECTION OR BEARING OF THE HORIZONTAL TRACE OF THE LINE OF DIP, MEASURED CLOCKWISE FROM NORTH. FAULT – A FRACTURE OR FRACTURE ZONE ALONG WHICH THERE HAS BEEN DISPLACEMENT OF THE SIDES RELATIVE TO ONE ANOTHER PARALLEL TO THE FRACTURE. FISSILE – A PROPERTY OF SPLITTING ALONG CLOSELY SPACED PARALLEL PLANES. FLOAT – ROCK FRAGMENTS ON SURFACE NEAR THEIR ORIGINAL POSITION AND DISLODGED FROM PARENT MATERIAL. FLOOD PLAIN (F.P.) – LAND BORDERING A STREAM, BUILT OF SEDIMENTS DEPOSITED BY THE STREAM. FORMATION (FM.) – A MAPPABLE GEOLOGIC UNIT THAT CAN BE RECOGNIZED AND TRACED IN THE FIELD. JOINT – FRACTURE IN ROCK ALONG WHICH NO APPRECIABLE MOVEMENT HAS OCCURRED. LEDGE – A SHELF-LIKE RIDGE OR PROJECTION OF ROCK WHOSE THICKNESS IS SMALL COMPARED TO ITS LATERAL EXTENT. LENS – A BODY OF SOIL OR ROCK THAT THINS OUT IN ONE OR MORE DIRECTIONS. MOTTLED (MOT.) – IRREGULARLY MARKED WITH SPOTS OF DIFFERENT COLORS. MOTTLING IN SOILS USUALLY INDICATES POOR AERATION AND LACK OF GOOD DRAINAGE. PERCHED WATER – WATER MAINTAINED ABOVE THE NORMAL GROUND WATER LEVEL BY THE PRESENCE OF AN INTERVENING IMPERVIOUS STRATUM. RESIDUAL SOIL – SOIL FORMED IN PLACE BY THE WEATHERING OF ROCK. ROCK QUALITY DESIGNATION (R.Q.D.) – A MEASURE OF ROCK QUALITY DESCRIBED BY: TOTAL LENGTH OF ROCK SEGMENTS EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF CORE RUN AND EXPRESSED AS A PERCENTAGE. SAPROLITE (SAP.) – RESIDUAL SOIL WHICH RETAINS THE RELIC STRUCTURE OR FABRIC OF THE PARENT ROCK. SILL – AN INTRUSIVE BODY OF IGNEOUS ROCK OF APPROXIMATELY UNIFORM THICKNESS AND RELATIVELY THIN COMPARED WITH ITS LATERAL EXTENT, WHICH HAS BEEN EMPLACED PARALLEL TO THE BEDDING OR SCHISTOSITY OF THE INTRODUCED ROCKS SLICKENSIDE – POLISHED AND STRIATED SURFACE THAT RESULTS FROM FRICTION ALONG A FAULT OR SLIP PLANE. STANDARD PENETRATION TEST (PENETRATION RESISTANCE) (SPT) – NUMBER OF BLOWS (N OR B.P.F.) OF A 140 LB. HAMMER FALLING 30 INCHES REQUIRED TO PRODUCE A PENETRATION OF 1 FOOT INTO SOIL WITH A 2 INCH OUTSIDE DIAMETER SPLIT SPOON SAMPLER. SPT REFUSAL IS LESS THAN 0.1 FOOT PENETRATION WITH 60 BLOWS. STRATA CORE RECOVERY (SREC.) – TOTAL LENGTH OF STRATA MATERIAL RECOVERED DIVIDED BY TOTAL LENGTH OF STRATUM AND EXPRESSED AS A PERCENTAGE. STRATA ROCK QUALITY DESIGNATION (S.R.Q.D.) – A MEASURE OF ROCK QUALITY DESCRIBED BY: TOTAL LENGTH OF ROCK SEGMENTS WITHIN A STRATUM EQUAL TO OR GREATER THAN 4 INCHES DIVIDED BY THE TOTAL LENGTH OF STRATA AND EXPRESSED AS A PERCENTAGE. TOPSOIL (T.S.) – SURFACE SOILS USUALLY CONTAINING ORGANIC MATTER.</p>	
WEATHERED ROCK (WR)		NON-COASTAL PLAIN MATERIAL THAT YIELDS SPT N VALUES > 100 BLOWS PER FOOT.	
CRYSTALLINE ROCK (CR)		FINE TO COARSE GRAIN IGNEOUS AND METAMORPHIC ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES GRANITE, GNEISS, GABBRO, SCHIST, ETC.	
NON-CRYSTALLINE ROCK (NCR)		FINE TO COARSE GRAIN METAMORPHIC AND NON-COASTAL PLAIN SEDIMENTARY ROCK THAT WOULD YIELD SPT REFUSAL IF TESTED. ROCK TYPE INCLUDES PHYLLITE, SLATE, SANDSTONE, ETC.	
COASTAL PLAIN SEDIMENTARY ROCK (CP)		COASTAL PLAIN SEDIMENTS CEMENTED INTO ROCK, BUT MAY NOT YIELD SPT REFUSAL. ROCK TYPE INCLUDES LIMESTONE, SANDSTONE, CEMENTED SHELL BEDS, ETC.	
WEATHERING			
FRESH	ROCK FRESH, CRYSTALS BRIGHT, FEW JOINTS MAY SHOW SLIGHT STAINING. ROCK RINGS UNDER HAMMER IF CRYSTALLINE.		
VERY SLIGHT (V. SL.)	ROCK GENERALLY FRESH, JOINTS STAINED, SOME JOINTS MAY SHOW THIN CLAY COATINGS IF OPEN, CRYSTALS ON A BROKEN SPECIMEN FACE SHINE BRIGHTLY. ROCK RINGS UNDER HAMMER BLOWS IF OF A CRYSTALLINE NATURE.		
SLIGHT (SL.)	ROCK GENERALLY FRESH, JOINTS STAINED AND DISCOLORATION EXTENDS INTO ROCK UP TO 1 INCH. OPEN JOINTS MAY CONTAIN CLAY. IN GRANITOID ROCKS SOME OCCASIONAL FELDSPAR CRYSTALS ARE DULL AND DISCOLORED. CRYSTALLINE ROCKS RING UNDER HAMMER BLOWS.		
MODERATE (MOD.)	SIGNIFICANT PORTIONS OF ROCK SHOW DISCOLORATION AND WEATHERING EFFECTS. IN GRANITOID ROCKS, MOST FELDSPARS ARE DULL AND DISCOLORED, SOME SHOW CLAY. ROCK HAS DULL SOUND UNDER HAMMER BLOWS AND SHOWS SIGNIFICANT LOSS OF STRENGTH AS COMPARED WITH FRESH ROCK.		
MODERATELY SEVERE (MOD. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. IN GRANITOID ROCKS, ALL FELDSPARS DULL AND DISCOLORED AND A MAJORITY SHOW KAOLINIZATION. ROCK SHOWS SEVERE LOSS OF STRENGTH AND CAN BE EXCAVATED WITH A GEOLOGIST'S PICK. ROCK GIVES "CLUNK" SOUND WHEN STRUCK. <i>IF TESTED, WOULD YIELD SPT REFUSAL.</i>		
SEVERE (SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC CLEAR AND EVIDENT BUT REDUCED IN STRENGTH TO STRONG SOIL. IN GRANITOID ROCKS ALL FELDSPARS ARE KAOLINIZED TO SOME EXTENT. SOME FRAGMENTS OF STRONG ROCK USUALLY REMAIN. <i>IF TESTED, YIELDS SPT N VALUES > 100 BPF.</i>		
VERY SEVERE (V. SEV.)	ALL ROCK EXCEPT QUARTZ DISCOLORED OR STAINED. ROCK FABRIC ELEMENTS ARE DISCERNIBLE BUT THE MASS IS EFFECTIVELY REDUCED TO SOIL STATUS, WITH ONLY FRAGMENTS OF STRONG ROCK REMAINING. SAPROLITE IS AN EXAMPLE OF ROCK WEATHERED TO A DEGREE SUCH THAT ONLY MINOR VESTIGES OF THE ORIGINAL ROCK FABRIC REMAIN. <i>IF TESTED, YIELDS SPT N VALUES < 100 BPF.</i>		
COMPLETE	ROCK REDUCED TO SOIL. ROCK FABRIC NOT DISCERNIBLE, OR DISCERNIBLE ONLY IN SMALL AND SCATTERED CONCENTRATIONS. QUARTZ MAY BE PRESENT AS DIKES OR STRINGERS. SAPROLITE IS ALSO AN EXAMPLE.		
ROCK HARDNESS			
VERY HARD	CANNOT BE SCRATCHED BY KNIFE OR SHARP PICK. BREAKING OF HAND SPECIMENS REQUIRES SEVERAL HARD BLOWS OF THE GEOLOGIST'S PICK.		
HARD	CAN BE SCRATCHED BY KNIFE OR PICK ONLY WITH DIFFICULTY. HARD HAMMER BLOWS REQUIRED TO DETACH HAND SPECIMEN.		
MODERATELY HARD	CAN BE SCRATCHED BY KNIFE OR PICK. GOUGES OR GROOVES TO 0.25 INCHES DEEP CAN BE EXCAVATED BY HARD BLOW OF A GEOLOGIST'S PICK. HAND SPECIMENS CAN BE DETACHED BY MODERATE BLOWS.		
MEDIUM HARD	CAN BE GROOVED OR GOUGED 0.05 INCHES DEEP BY FIRM PRESSURE OF KNIFE OR PICK POINT. CAN BE EXCAVATED IN SMALL CHIPS TO PEICES 1 INCH MAXIMUM SIZE BY HARD BLOWS OF THE POINT OF A GEOLOGIST'S PICK.		
SOFT	CAN BE GROVED OR GOUGED READILY BY KNIFE OR PICK. CAN BE EXCAVATED IN FRAGMENTS FROM CHIPS TO SEVERAL INCHES IN SIZE BY MODERATE BLOWS OF A PICK POINT. SMALL, THIN PIECES CAN BE BROKEN BY FINGER PRESSURE.		
VERY SOFT	CAN BE CARVED WITH KNIFE. CAN BE EXCAVATED READILY WITH POINT OF PICK. PIECES 1 INCH OR MORE IN THICKNESS CAN BE BROKEN BY FINGER PRESSURE. CAN BE SCRATCHED READILY BY FINGER NAIL.		
FRACTURE SPACING		BEDDING	
TERM	SPACING	TERM	THICKNESS
VERY WIDE	MORE THAN 10 FEET	VERY THICKLY BEDDED	> 4 FEET
WIDE	3 TO 10 FEET	THICKLY BEDDED	1.5 - 4 FEET
MODERATELY CLOSE	1 TO 3 FEET	THINLY BEDDED	0.16 - 1.5 FEET
CLOSE	0.16 TO 1 FEET	VERY THINLY BEDDED	0.03 - 0.16 FEET
VERY CLOSE	LESS THAN 0.16 FEET	THICKLY LAMINATED	0.008 - 0.03 FEET
		THINLY LAMINATED	< 0.008 FEET
INDURATION			
FOR SEDIMENTARY ROCKS, INDURATION IS THE HARDENING OF THE MATERIAL BY CEMENTING, HEAT, PRESSURE, ETC.			
FRIABLE	RUBBING WITH FINGER FREES NUMEROUS GRAINS; GENTLE BLOW BY HAMMER DISINTEGRATES SAMPLE.		
MODERATELY INDURATED	GRAINS CAN BE SEPARATED FROM SAMPLE WITH STEEL PROBE; BREAKS EASILY WHEN HIT WITH HAMMER.		
INDURATED	GRAINS ARE DIFFICULT TO SEPARATE WITH STEEL PROBE; DIFFICULT TO BREAK WITH HAMMER.		
EXTREMELY INDURATED	SHARP HAMMER BLOWS REQUIRED TO BREAK SAMPLE; SAMPLE BREAKS ACROSS GRAINS.		
		BENCH MARK: BM1 RR SPIKE IN POWER POLE	
		ELEVATION: 2141.02'	
NOTES:			



SCALE:
AS SHOWN

DRAWN BY:
LAC

CHECKED BY:
SSL


DATE:
2/8/2013





SITE VICINITY MAP
REPLACE STRUCTURE NO 870113
ON SR 1136 OVER NICHOLSON CREEK
TRANSYLVANIA COUNTY, NORTH CAROLINA

PROJECT NO.: 17BP.14.R.24

SHEET NO.
3



LEGEND

-  APPROXIMATE BORING LOCATION
-  APPROXIMATE SOUNDING ROD LOCATION

SCALE: 1" = 40'	DATE: 2/25/2015
PROJECT NO. 17BP.14.R.24	DRAWN BY: MIK
CHECKED BY: SSL	


WWW.SMEINC.COM
 ENGINEERING LICENSE NO: F-0176

FIELD EXPLORATION PLAN
REPLACE STRUCTURE No. 870113
 ON SR 1346 OVER NICHOLSON CREEK
 TRANSYLVANIA COUNTY, NORTH CAROLINA

SHEET NO.
4



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT


WBS 17BP.14.R.24	TIP N/A	COUNTY Transylvania	GEOLOGIST J. Williamson
SITE DESCRIPTION Replace Bridge 870113 on SR 1346 Over Nicholson Creek			GROUND WTR (ft)
BORING NO. EB1-B	STATION 12+75	OFFSET 8 ft LT	ALIGNMENT -L-
COLLAR ELEV. 2,139.7 ft	TOTAL DEPTH 38.6 ft	NORTHING 558,395	EASTING 881,480
DRILL RIG/HAMMER EFF./DATE CME-45B 87% 10/7/2011		DRILL METHOD 3 1/4" HSA	HAMMER TYPE Automatic
DRILLER C. Odom	START DATE 04/24/12	COMP. DATE 04/24/12	SURFACE WATER DEPTH N/A

ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	L O G	SOIL AND ROCK DESCRIPTION	DEPTH (ft)
			0.5ft	0.5ft	0.5ft	0	25	50	75	100					
2140														GROUND SURFACE	0.0
	2,138.7	1.0	1	1	1								M	ROADWAY EMBANKMENT Brown Fine Silty SAND (A-2-4), trace mica	
	2,136.2	3.5	1	WOH	1								M	ROADWAY EMBANKMENT	3.8
2135	2,133.7	6.0	1	WOH	4								W	Brown Sandy SILT (A-4), trace mica, trace gravel	5.5
	2,131.2	8.5	13	14	10								M	ALLUVIAL Dark Gray Sandy SILT (A-4), trace mica	8.0
2130													M	RESIDUUM Red Brown Gravelly SAND (A-1-b)	12.0
	2,126.2	13.5	8	8	12								M	RESIDUUM Tan Brown Sandy SILT (A-4), trace mica	
2125													M		
	2,121.2	18.5	8	16	36								M		
2120													M		
	2,116.2	23.5	46	54/0.3									M	WEATHERED ROCK (Gneiss)	22.0
2115													M		
	2,111.2	28.5	18	27	49								M	RESIDUUM Brown Sandy SILT (A-4)	27.5
2110													M		
	2,106.2	33.5	9	12	22								M		
2105													M		
	2,101.2	38.5	60/0.1										M	WEATHERED ROCK (Gneiss)	37.0
														Boring Terminated with Standard Penetration Test Refusal at Elevation 2,101.1 ft On Rock (Gneiss)	38.6
														1) 3-1/4" Hollow Stem Augers Advanced to 38.5 Feet	

PROJECT: 17BP.14.R.24		BORING LOG: HA2-A	
SITE DESCRIPTION: REPLACE BRIDGE 870113 ON SR 1346 OVER NICHOLSON CREEK			
DATE PERFORMED: 5/15/2012	ELEVATION: 2140.8 Feet	COUNTY: TRANSYLVANIA	NOTES: Dynamic Cone Penetrometer Testing performed in general accordance with ASTM STP-399.
PERFORMED BY: J. Williamson	TOTAL DEPTH: 9 Feet	ALIGNMENT: -L-	
NORTHING: 558447	WATER LEVEL: Dry	OFFSET: 31 ft LT	
EASTING: 881477	STATION: 13+21		

HAND AUGER / DYNAMIC CONE PENETROMETER SOUNDING RECORD

DEPTH (FEET)	DESCRIPTION
0 - 1.5	ROADWAY EMBANKMENT: Brown Silty Fine SAND (A-2-4) , Some Gravel
1.5 - 3	ROADWAY EMBANKMENT: Tan Orange Sandy SILT (A-4) , Moist
3 - 5	ROADWAY EMBANKMENT: Tan Orange Sandy SILT (A-4) , Wet
5 - 8	ALLUVIAL: Brown Sandy GRAVEL (A-1-b) , Saturated
8 - 9	ALLUVIAL: Gray Silty CLAY (A-7-5) , Trace Mica, Saturated
Hand Auger terminated at 9 feet	



9751 Southern Pine Boulevard
 Charlotte, North Carolina 28723
 Phone: (704) 523-4726 • Fax: (704) 525-3953



NCDOT GEOTECHNICAL ENGINEERING UNIT

BORELOG REPORT

WBS 17BP.14.R.24		TIP N/A		COUNTY Transylvania		GEOLOGIST J. Williamson										
SITE DESCRIPTION Replace Bridge 870113 on SR 1346 Over Nicholson Creek							GROUND WTR (ft)									
BORING NO. EB2-B		STATION 13+20		OFFSET 14 ft LT		ALIGNMENT -L-	0 HR. 5.4									
COLLAR ELEV. 2,140.7 ft		TOTAL DEPTH 50.0 ft		NORTHING 558,439		EASTING 881,493	24 HR. FIAD									
DRILL RIG/HAMMER EFF./DATE CME-45B 87% 10/7/2011				DRILL METHOD 3 1/4" HSA		HAMMER TYPE Automatic										
DRILLER C. Odom		START DATE 05/04/12		COMP. DATE 05/04/12		SURFACE WATER DEPTH N/A										
ELEV (ft)	DRIVE ELEV (ft)	DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT					SAMP. NO.	LOG MOI	SOIL AND ROCK DESCRIPTION	DEPTH (ft)		
			0.5ft	0.5ft	0.5ft	0	25	50	75	100						
2145																
2140	2,139.7	1.0	3	2	1									2,140.7	GROUND SURFACE	0.0
	2,137.2	3.5	WOH	WOH	WOH									2,137.7	ROADWAY EMBANKMENT Red Brown Sandy SILT (A-4)	3.0
2135	2,134.7	6.0	WOH	1	0									2,135.2	ROADWAY EMBANKMENT Dark Brown Sandy CLAY (A-6)	5.5
	2,132.2	8.5	12	9	3									2,132.7	ROADWAY EMBANKMENT Orange Brown Sandy SILT (A-4)	8.0
2130	2,127.2	13.5	3	2	1									2,128.7	ALLUVIAL Orange Sandy GRAVEL (A-1-b)	12.0
2125	2,122.2	18.5	4	6	8										RESIDUUM Brown Sandy SILT (A-5)	
2120	2,117.2	23.5	6	17	52									2,118.7	RESIDUUM Brown Sandy SILT (A-4), trace mica	22.0
2115	2,112.2	28.5	9	20	33											
2110	2,107.2	33.5	12	22	40											
2105	2,102.2	38.5	43	57/0.2										2,103.7	WEATHERED ROCK (Gneiss)	37.0
2100	2,097.2	43.5	60/0.3											2,093.7	RESIDUUM Brown Sandy SILT (A-4), trace mica	47.0
2095	2,092.2	48.5	29	63	27									2,090.7	RESIDUUM Brown Sandy SILT (A-4), trace mica	50.0
															Boring Terminated at Elevation 2,090.7 ft In Hard Residual Silt (A-4)	
															1) 3-1/4" Hollow Stem Augers Advanced to 48.5 Feet	

NCDOT BORE SINGLE 113.GPJ NC_DOT.GDT 2/25/15



**NCDOT GEOTECHNICAL ENGINEERING UNIT
FIELD PENETROMETER LOG (ENGLISH)**

PROJECT NUMBER	17.BP.14.R.24	ID		CO	TRANSYLVANIA	GEO	J. WILLIAMSON
SITE DESC	REPLACE BRIDGE 870113 ON SR 1346 OVER NICHOLSON CREEK						
BORING NUMBER	RS1-A	STA	12+97	OFFSET	43 FT	LT	ALIGNMENT -L-
ELEVATION	2135.2 FT	TOTAL DEPTH	10.0 FT	NORTH	558,429	EAST	881,457
DRILL METHOD	ROD SOUNDING					DRILLER	N. PAGE
START DATE	05/15/12	COMP DATE	05/15/12	SURFACE WTR DEPTH	0.4 FT	DEPTH TO ROCK	N/A FT

DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMPLE NO. & INTERVAL	MOI	ORIGIN	SOIL & ROCK DESCRIPTION <small>SOIL or ROCK NAME (w/ color, density/consistency, texture, plasticity, organics, other)</small>
	0.5 ft	0.5 ft	TOTAL	0	25	50	75				
0	1		1								
2	1		3								
1	1		2								
1	2		3								
5	7		11								
	5		11								
	10		20								
	15		30								
	12		24								
10	25		50								
15											
20											
25											
30											
35											

Rod Sounding Terminated at Elevation 2125.2

NOTES Terminated at 10.0 Feet

DECK TO DATUM DISTANCE _____ FT

SIGNATURE _____ DATE _____

NOTES _____

RED LINE



**NCDOT GEOTECHNICAL ENGINEERING UNIT
FIELD PENETROMETER LOG (ENGLISH)**

PROJECT NUMBER	17.BP.14.R.24	ID		CO	TRANSYLVANIA	GEO	J. WILLIAMSON
SITE DESC	REPLACE BRIDGE 870113 ON SR 1346 OVER NICHOLSON CREEK						
BORING NUMBER	RS1-B	STA	12+93	OFFSET	4 FT	RT	ALIGNMENT -L-
ELEVATION	2134.9 FT	TOTAL DEPTH	7.5 FT	NORTH	558,407	EAST	881,498
DRILL METHOD	ROD SOUNDING					DRILLER	N. PAGE
START DATE	05/15/12	COMP DATE	05/15/12	SURFACE WTR DEPTH	0.5 FT	DEPTH TO ROCK	7.5 FT

DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMPLE NO. & INTERVAL	MOI	ORIGIN	SOIL & ROCK DESCRIPTION <small>(w/ color, density/consistency, texture, plasticity, organics, other)</small>
	0.5 ft	0.5 ft	TOTAL	0	25	50	75				
0	0	0	0								
0	0	0	0								
0	0	0	0								
4	23	23	27								
5	22	23	45								
10	10	10	20								
22	33	33	55								
70			70/0.5								
											Rod Sounding Refusal at Elevation 2127.4
10											
15											
20											
25											
30											
35											

NOTES Refusal at 7.5 Feet

SIGNATURE _____ DATE _____

NOTES _____

DECK TO DATUM DISTANCE _____ FT



**NCDOT GEOTECHNICAL ENGINEERING UNIT
FIELD PENETROMETER LOG (ENGLISH)**

PROJECT NUMBER	17.BP.14.R.24	ID		CO	TRANSYLVANIA	GEO	J. WILLIAMSON
SITE DESC	REPLACE BRIDGE 870113 ON SR 1346 OVER NICHOLSON CREEK						
BORING NUMBER	RS2-B	STA	13+07	OFFSET	2 FT	LT	ALIGNMENT -L-
ELEVATION	2135.0 FT	TOTAL DEPTH	4.1 FT	NORTH	558,422	EAST	881,498
DRILL METHOD	ROD SOUNDING					DRILLER	N. PAGE
START DATE	05/15/12	COMP DATE	05/15/12	SURFACE WTR DEPTH	0.6 FT	DEPTH TO ROCK	4.1 FT

DEPTH (ft)	BLOW COUNT			BLOWS PER FOOT				SAMPLE NO. & INTERVAL	MOI	ORIGIN	SOIL & ROCK DESCRIPTION <small>SOIL or ROCK NAME (w/ color, density/consistency, texture, plasticity, organics, other)</small>
	0.5 ft	0.5 ft	TOTAL	0	25	50	75				
0	3		3								
1	0		1								
1	0		1								
37	30		67								
5	100/0.1		100/0.1								Rod Sounding Refusal at Elevation 2130.9
10											
15											
20											
25											
30											
35											

NOTES Refusal at 4.1 Feet

SIGNATURE _____ DATE _____

NOTES _____

RED LINE

DECK TO DATUM DISTANCE _____ FT




Photograph No. 1:
View looking north up-station from south approach



Photograph No. 2:
View looking south down-station from north approach



Photograph No. 3:
View looking west upstream from bridge deck



Photograph No. 4:
View looking east downstream from bridge deck



Photograph No. 5:
View looking south at End Bent 1B side



Photograph No. 6:
View looking south at End Bent 1A side



Photograph No. 7:
View looking north at End Bent 2B side



Photograph No. 8:
View looking north at End Bent 2A side