PROJECT REFERENCE NO.	SHEET NO.
14BJ02011	PMP-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKINIG PLAN
CHEROKEE COUNTY

LOCATION 1: INTERSECTION OF US64 & OLD US64 SR1687

LOCATION 2: 1.0 MILE FROM INTERSECTION OF US64 & SR1687

INDEX

SHEET NO.	DESCRIPTION
PMP-1	PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET
PMP-2 THRU PMP-4	PAVEMENT MARKING DETAIL

GENERAL NOTES

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THEIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS

STD. NO.	TITLE
1205.01	PAVEMENT MARKING - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKING - TWO LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKING - INTERSECTIONS
1250.01	RAISED PAVEMENT MARKERS- INSTALLATION SPACING
1253.01	RAISED PAVEMENT MARKERS - SNOWPLOWABLES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

ROADWAY STANDARD DRAWING

SHEET NO.	DESCRIPTION	
		PAVEMENT MARKINGS
T2	WHITE STOPBAR	THERMOPLASTIC (24", 120 MIL)
T8	2 FT. - 6 FT SP WHITE MINISKIP	THERMOPLASTIC (4", 120 MIL)
TI	YELLOW DOUBLE CENTER LINE	
TA	WHITE EDGELINE	THEMOPLASTIC (4", 90 MIL)
PA	WHITE EDGE LINE	PAINT
PI	YELLOW DOUBLE CENTER	
		MARKERS
ME	YELLOW & YELLOW	SNOWPLOWABLE RAISED PAVEMENT MARKERS

CONTRACT: DN00562 PROJECT: WBS#: 14B.102011