



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

August 3, 2021

ADDENDUM # 1

To: Plan Holders
From: Josh Deyton, P.E.
Project Team Lead



RE: **Pay Item Addition & Pre-Bid Meeting Minutes**
Contract ID: DN00737
County: Jackson
Letting Date: August 10, 2021

The above contract has experienced the following revisions:

1. Pay Item Addition:

On page T-4 of the proposal, after item 0065 CONCRETE WASHOUT STRUCTURE, add the following item:

0066 000100000-E 200 CLEARING & GRUBBING..ACRE(S) LUMP SUM

See attached revised page T-4 showing this item addition.

2. Pre-Bid Meeting Minutes & Sign-In Sheet

See attached meeting minutes and sign in sheet.

Please access ebs addenda files on Bid Express®.

Thank you for your attention to this matter.

County : Jackson

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0057	6087000000-E	1660	MOWING	3 ACR		
0058	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0059	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0060	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	75 LB		
0061	6108000000-E	1665	FERTILIZER TOPDRESSING	1.75 TON		
0062	6111000000-E	SP	IMPERVIOUS DIKE	15 LF		
0063	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0064	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	4 EA		
0065	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	4 EA		
0066	0001000000-E	200	CLEARING & GRUBBING .. ACRE(S)	Lump Sum	L.S.	

0854/Aug03/Q57321.6/D221125230000/E66

Total Amount Of Bid For Entire Project :

MANDATORY PREBID MEETING DN00737

August 2, 2021

10:00 A.M.

- Everyone must sign the sign-in sheet to be eligible to bid on the project.
- Date of availability 10/15/2021
- Completion date 4/15/2023
- Liquidated damages: \$200 per day for overall completion and \$850 per day for ICT #1.
- No tree cutting between April 15 and October 15.
- Six months delay for milling and paving after horizontal drains have been installed. There is a plan error regarding the Summary of Embankment Waiting Periods. The plans should read 6 months waiting period to match the proposal.
- Specialty Items are the horizontal drains. (Does not count against the contractor 40% that must be performed by the prime)
- Certified payroll since the project has federal funds.
- Lump Sum Traffic Control (Includes signs, message boards, Arrow Boards, TMA, Drums, or anything else to do with traffic control)
- Construction sequence – Install toe drains, then mid-slope drains, followed by surface drainage and repairs at-grade. (See “Standard Horizontal Drain Detail”)
- There are no erosion control plans but still will need to keep up the NPDES and follow NCDOT BEST MANAGEMENT PRACTICES. NCDOT staff will assist with the location of the erosion devices. Any silt generated by the Jack and Bore or the drilling operation for Horizontal Drains must be retained onsite. Basins will be installed if needed to retain silt from leaving the project.
- Plans show the locations access roads for the horizontal drains.
- The necessary surveying will be performed by NCDOT forces. NCDOT will identify the clearing limits and ROW.
- A pipe diversion for the spring head will need to be installed to dewater the jurisdictional stream when installing the 30” pipe. The impervious dike will need to be installed right before the stream disappears into the ground. There is no permit to touch the jurisdictional stream therefore safety fence needs to be installed to delineate the stream.
- The project will only be cleared only enough to perform the work for installing the horizontal drains, installing the 30” pipe for the jurisdictional stream and installing erosion control devices.
- The benches to install the horizontal drains are shown in the plan details therefore the suitable equipment should be used to be able to operate within the area given in the detail. The embankment slope will have to be recompacted after the benches are removed. There is no detail for the access road at the toe of the slope, but Class A rip rap might be needed since the toe of the slope could be saturated.
- There is a fiber optic utility line in the location of the Jack and Bore. The line has been located and Frontier wants to have a representative onsite when working in the vicinity. Two-week notice must be given to Frontier when work is to take place. The NCDOT will coordinate with Frontier once notice is given.

- All grading is incidental to the horizontal drain line item. If more grading is required for silt basins, then work will be covered with a supplemental agreement.
- Clearing item will be added as an amendment the contract line items.

PRE-BID CONFERENCE ATTENDANCE

Contract No.: **DW00737**

Date: **8/2/2011** Location: District Office - Whittier - District 2

PLEASE PRINT

NAME	Company	TITLE	Phone	E-MAIL ADDRESS
Brian Templeton	NEDOT/Risk		828-497-7333	btdtempleton@ncdot.gov
John Paul	WMC Parings		828-734-0888	john.paul@wmcparings.com
Blake Anderson	Adams Contracting	PM	828-478-4626	adamscontracting3@gmail.com
Rance Adams	Adams Contracting	President	828-471-4444	adamscontracting3@gmail.com
Alex Keith	WMC Parings	PM	819-790-1400	alex.keith@wmcparings.com
Kyle Johnson	Site Development	Site Admin	828-921-2213	alex.keith@wmcparings.com
Deu MUNEZ	GENERALIZATION INTL	Project Developer Eng.	601-527-9927	dm@gsi.us
KEE SHEPARD	NEDOT	Roadside Engr. Field Ops	828-694-2192	kshepard@ncdot.gov
Matthew Tanner	NEDOT	RE	828-447-7333	mtanner@ncdot.gov
Ron Wiktaki	NEDOT-Road Engr/Arch	Field CP Engr.	828-283-2075	wiktaki@ncdot.gov
Joshy Vohra	NEDOT-GEOTECH Engr		828-779-9482	jvohra@ncdot.gov
JENNETTE WHITE	NEDOT-Reg. Dev.	Dir. H. Sr Project Engr.	828-550-6039	jwhite@ncdot.gov
Nick Henry	Watson	PM	828-224-1404	nick@watsoncontracting.com
Dave Melony	NEDOT	DEO	828-586-2141	dmelony@ncdot.gov