PROJECT REFERENCE NO.	SHEET NO.
15614.1050014	2A-1

ROADWAY DESIGN ENGINEER
NORTH CAROLINA PROFESSIONAL SEAL 035683 ENGINEER DAVID J. CLODFO
6/18/2021
DocuSigned by: David J. Clodfo
304D6E5D37B44C...

PAVEMENT DESIGN ENGINEER
NORTH CAROLINA PROFESSIONAL SEAL 050909 ENGINEER ZACHARY T. SHULER
6/18/2021
DocuSigned by: Zachary Shuler
A827E4D01CE43F...

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT SCHEDULE

(FINAL PAVEMENT DESIGN)

C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YARD.
U	EXISTING PAVEMENT
V	MILL 1½" OF EXISTING ASPHALT PAVEMENT

NOTES: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS OTHERWISE SHOWN.
PATCHING TO BE DETERMINED BY THE ENGINEER.



TYPICAL SECTION NO. 1

-L- STA. 756+00.00 TO -L- STA. 772+00.00

6/2/99
10-JUN-2021 10:26
c:\work\ncdot\ncdot-pw.bentley.com_ncdot-pw-01\christian st. clare\dms25747\us441_RDY_TYP.dgn
$$$$USERNAME$$$$