

8/17/99

INDEX OF SHEETS, LIST OF STANDARD DRAWINGS, & GENERAL NOTES

|                       |           |
|-----------------------|-----------|
| PROJECT REFERENCE NO. | SHEET NO. |
| DF18314.2045452       | 1A        |

INDEX OF SHEETS

LIST OF STANDARD DRAWINGS

GENERAL NOTES

| SHEET NUMBER   | SHEET                                                |
|----------------|------------------------------------------------------|
| 1              | TITLE SHEET                                          |
| 1A             | INDEX OF SHEETS, GENERAL NOTES AND STANDARD DRAWINGS |
| 1B             | CONVENTIONAL SYMBOLS                                 |
| 2A-1           | PAVEMENT SCHEDULE AND TYPICAL SECTIONS               |
| 2C-1 THRU 2C-2 | DETAILS IN LIEU OF STANDARDS                         |
| 2G-1 THRU 2G-5 | GEOTECHNICAL DETAIL SHEETS                           |
| 3B-1           | ROADWAY SUMMARIES                                    |
| 3D-1           | DRAINAGE SUMMARY SHEET                               |
| 3P-1           | PARCEL SUMMARIES                                     |
| 4 THRU 5       | PLAN AND PROFILE SHEET                               |
| RW-1           | RIGHT OF WAY SHEET                                   |
| EC-1 THRU EC-7 | EROSION CONTROL SHEETS                               |
| RF-1           | REFORESTATION DETAIL SHEET                           |
| X-1            | CROSS-SECTION SUMMARY                                |
| X-2 THRU X-17  | CROSS-SECTION SHEETS                                 |

2024 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2024 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO. TITLE

DIVISION 2 - EARTHWORK  
200.02 Method of Clearing - Method II  
225.02 Guide for Grading Subgrade - Secondary and Local  
225.04 Method for Obtaining Superelevation - Two Lane Pavement

DIVISION 3 - PIPE CULVERTS  
300.01 Method of Pipe Installation

DIVISION 5 - SUBGRADE, BASES AND SHOULDERS  
560.01 Method of Shoulder Construction -  
High Side of Superelevated Curve - Method I

DIVISION 8 - INCIDENTALS  
806.01 Concrete Right-of-Way Marker  
876.01 Rip Rap in Channels and Ditches

DIVISION 11 - WORK ZONE TRAFFIC CONTROL  
1101.01 Work Zone Advance Warning Signs  
1101.02 Temporary Lane Closures  
1101.03 Temporary Road Closures  
1101.04 Temporary Shoulder Closures  
1101.05 Work Zone Vehicle Accesses  
1101.11 Traffic Control Design Tables  
1110.01 Stationary Work Zone Signs  
1110.02 Portable Work Zone Signs  
1130.01 Drums  
1135.01 Cones  
1145.01 Barricades - Type III  
1150.01 Flaggers  
1180.01 Skinny Drums

EFF. 01-16-2024  
REV.

2024 SPECIFICATIONS  
EFFECTIVE: 01-16-2024  
REVISED:

GRADING AND SURFACING OR RESURFACING AND WIDENING:  
THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. WHERE NO GRADE LINES ARE SHOWN, THE PROFILES SHOWN DENOTE THE TOP ELEVATION OF THE EXISTING PAVEMENT ALONG THE CENTER LINE OF SURVEY ON WHICH THE PROPOSED RESURFACING WILL BE PLACED. GRADE LINES MAY BE ADJUSTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:  
CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD 11.

SIDE ROADS:  
THE CONTRACTOR WILL BE REQUIRED TO DO ALL NECESSARY WORK TO PROVIDE SUITABLE CONNECTIONS WITH ALL ROADS, STREETS, AND DRIVES ENTERING THIS PROJECT. THIS WORK WILL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PARTICULAR ITEMS INVOLVED.

SUBSURFACE PLANS:  
NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION OF THE SUBSURAFCE CONDITIONS.

UTILITIES:  
UTILITIES PRESENT ON THIS PROJECT ARE: DUKE ENERGY AND AT&T. CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL UTILITIES WITHIN WORK AREAS BEFORE STARTING WORK.

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

RIGHT-OF-WAY MARKERS:  
ALL RIGHT-OF-WAY MARKERS ON THIS PROJECT SHALL BE PLACED BY CONTRACT.

6/28/2026  
X:\Raleigh\24-0176.002 - Riverside Drive\05-CAD\Riverside Dr\Roadway\Proj\RiversideDr\_Rd.psh01A.dgn  
acceder