

EARTHWORK SUMMARY

STATION	STATION	EXCAVATION		EMBANKMENT	BORROW	TOTAL WASTE
		TOTAL UNCLASS.	UNDERCUT			
-L- 10+98.98	-L-23+60.00	2,372		657		1,715
	SUBTOTAL	2,372		657		1,715
	TOTAL	2,372		657		1,715
MATERIAL FOR SHOULDER CONSTRUCTION						
LOSS DUE TO CLEARING & GRUBBING						
WASTE IN LIEU OF BORROW						
	PROJECT TOTAL	2,372		657		1,715
EST. 5% TO REPLACE TOP SOIL ON BORROW PIT						
	GRAND TOTAL	2,372		657		1,715
	SAY	2,400				

Note: Approximate quantities only. Unclassified Excavation, Fine Grading, and Clearing and Grubbing will be paid for at the contract lump sum price for "Grading."

Note: Earthwork quantities are calculated by the roadway designer. No subsurface data provided is available for this project.