

5/14/99
7/2/2025
\\\$:\Projects\624-0175.002 - Riverside Drive\05-CAD\Riverside Dr-Roadway\XSC\RiversideDr-Rdy.X1.dgn

CROSS SECTION SUMMARY

Station	Uncl. Exc.	Embt.
L	(cu. yd.)	(cu. yd.)
10+98.98	0	0
11+00.00	2	0
11+50.00	137	24
12+00.00	130	22
12+50.00	128	24
13+00.00	118	21
13+20.00	51	7
13+50.00	67	15
14+00.00	107	33
14+50.00	116	34
15+00.00	109	29
15+50.00	115	24
16+00.00	130	27
16+50.00	254	49
17+00.00	260	59
17+50.00	80	32
18+00.00	2	8
18+12.00	1	1
18+50.00	87	27
19+00.00	243	61
19+50.00	144	26
20+00.00	19	2
20+50.00	17	8
20+92.00	12	6
21+00.00	3	0
21+50.00	12	2
22+00.00	9	2
22+50.00	9	2
22+70.00	2	3
23+00.00	2	11
23+50.00	3	12
23+60.00	3	0

Note: Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Note: Approximate quantities only. Unclassified excavation, shoulder borrow, fine grading, and clearing and grubbing will be paid for at the lump sum price for "Grading".