


| BILL OF MATERIALS PROVIDED BY MAGGIE VALLEY SANITARY DISTRICT | | |
|---|-------|-----------|
| DESCRIPTION | UNITS | QUANTITY* |
| 6" WATER LINE (DIP) | LF | 260 |
| 6" RESTRAINED WATER LINE (TR FLEX PIPE) | LF | 75 |
| DUCTILE IRON WATER PIPE FITTINGS | LBS | 705 |
| 6" DI CAP W/ 2" THREADED PLUG | EA | 1 |
| MEGA-LUG KITS | EA | 10 |
| THREADED ROD | LF | 100 |
| CONCRETE FOR THRUST BLOCKING | CY | 5 |
| 2" CTS TUBE FOR TEMPORARY WATER LINE | LF | 335 |
| TAPPING SADDLE | EA | 1 |
| 6" VALVE | EA | 1 |
| FIRE HYDRANT | EA | 1 |
| FIRE HYDRANT LEG | LF | 49 |
| 6" SLEEVE | EA | 1 |
| *QUANTITIES ARE APPROXIMATE AND MAY BE FIELD ADJUSTED | | |

DF18314.2044188

UC-4

THIS SHEET CORRESPONDS TO ROADWAY PLAN SHEET 4.



UTILITY CONSTRUCTION PLANS ONLY

PREPARED BY

VHB Engineering, Inc., P.C. (C-3705)
940 Main Campus Drive, Suite 500
Raleigh, NC 27606

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED