

STATE OF NORTH CAROLINA

DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY


Station -L-	Uncl. Exc. (cu.yd.)	Embt. (cu. yd.)
11+10.13	0	0
11+50.00	45	0
12+00.00	74	0
12+50.00	25	0
13+00.00	0	0
Station -L-	Uncl. Exc. (cu.yd.)	Embt. (cu. yd.)
13+50.00	0	44
14+00.00	0	106
14+50.00	1	77
15+00.00	1	19
15+50.00	3	5
16+00.00	2	1
Station -DRWY-	Uncl. Exc. (cu.yd.)	Embt. (cu. yd.)
09+89.38	0	0
10+00.00	0	2
10+50.00	4	12
10+59.45	2	0

Note: Approximate quantities only. Clearing and Grubbing, Borrow Excavation, Fine Grading, Removal of Existing Asphalt Pavement and Breaking of Existing Asphalt Pavement will be paid for at the lump sum for "Grading".

DF18314.2044188


4RDI    X-1A

NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
HAYWOOD COUNTY



ROADWAY DESIGN UNIT

PREPARED BY

**Vhb**

VHB Engineering NC, P.C. (C-3705)  
540 Main Campus Drive, Suite 500  
Raleigh, NC 27605