

SUMMARY OF EARTHWORK

IN CUBIC YARDS

STATION	STATION	UNCL EXCAV.	EMBANK. + %	AGGREGATE SHOULDER BORROW CY (TONS)	WASTE
15 + 40.01	18 + 35.32	204		204 (420)	
SUBTOTALS:		204		204 (420)	
PROJECT TOTALS:		204		204 (420)	
GRAND TOTALS:		204		204 (420)	
SAY:		220		220 (420)	

NOTE: QUANTITIES ARE APPROXIMATE ONLY. THE RESIDENT ENGINEER WILL USE METHODS INCLUDING BUT NOT LIMITED TO RECROSS-SECTIONING, TRUCK MEASUREMENTS, AND AERIAL SURVEYS TO COMPUTE FINAL QUANTITIES WHICH THE CONTRACTOR WILL BE PAID.

HS-2414N

FINAL3B-1

NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROADWAY DESIGN UNIT

ROADWAY DESIGN
ENGINEER

06/26/2026

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED