



PROJECT: DF18314.2045330

CONTRACT:

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING & PAVEMENT MARKING PLAN
HENDERSON COUNTY

LOCATION: BRIDGE #440197 OVER REEDY PATCH CREEK
ON SR 1702 (EDNEY INN ROAD)

PROJECT REFERENCE NO.	SHEET NO.
DF18314.2045330	PMP - 1
APPROVED: Discussed by:  15E6C7D156374893	
DATE: 7/2/2026	
SEAL	
	
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED	

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - CONTRACT STANDARDS AND DEVELOPMENT UNIT- N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2024 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.12	PAVEMENT MARKINGS - BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS - TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

INDEX

SHEET NO.	DESCRIPTION
PMP-1	SIGNING & PAVEMENT MARKING PLAN TITLE/SCHEDULE
PMP-2	SIGNING & PAVEMENT MARKING PLAN

PAY ITEM NOTES

1 DISPOSAL OF SIGN SYSTEM, U-CHANNEL

SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4155000000 4810000000	907 1205	DISPOSAL OF SIGN SYSTEM, U-CHANNEL PAINT PAVEMENT MARKING LINES (4")	1 4480	EA LF

GENERAL NOTES


- THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.
- A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:
- | | | |
|-------------|---------|--------|
| ROAD NAME | MARKING | MARKER |
| -L- SR 1702 | PAINT | NONE |
- B) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.
- C) REMOVE ALL RESIDUE AND SURFACE LAITANCE BY ACCEPTABLE METHODS ON CONCRETE BRIDGE DECKS PRIOR TO PLACING PAINT PAVEMENT MARKING MATERIAL.
- D) IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- E) ALL EXISTING SIGNS ON U-CHANNEL SUPPORT(S) WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- F) SEE ROADWAY PLANS FOR GUARD/GUIDE RAIL DETAILS.

FINAL PAVEMENT MARKING SCHEDULE

MATERIAL	SYMBOL	DESCRIPTION
PAVEMENT MARKING		
PAINT (4")		
	P1	WHITE EDGELINE
	P13	YELLOW DOUBLE CENTER

PLAN PREPARED FOR: N.C.D.O.T. SIGNING AND DELINEATION UNIT

KELVIN L. JORDAN SIGNING & DELINEATION REGIONAL ENGINEER



PLAN PREPARED BY: HNTB NORTH CAROLINA, P.C.

J. ANDREW WAGNER, PE PROJECT ENGINEER
GARRETT D. BERRY DESIGN TECHNICIAN

HNTB HNTB NORTH CAROLINA, P.C.
4000 CENTER AT NORTH HILLS ST STE 500
RALEIGH, NORTH CAROLINA 27609
NC License No: C-1554
(919) 546-8997