

12/2/2016

INDEX OF SHEETS, GENERAL NOTES, and LIST OF STANDARDS

PROJECT REFERENCE NO.
B-5921

SHEET NO.
1A

ROADWAY DESIGN
ENGINEER
8/16/2026
NORTH CAROLINA
PROFESSIONAL
SEAL
017265
NIV5 ENGINEERS & CONSULTANTS, INC.
3300 REGENCY PARKWAY, SUITE 100
CARY, NC 27513
P: 919.851.1912
www.NV5.com
NC License # P-1383

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

NIV5

NV5 ENGINEERS & CONSULTANTS, INC.
3300 REGENCY PARKWAY, SUITE 100
CARY, NC 27513
P: 919.851.1912
www.NV5.com
NC License # P-1383

INDEX OF SHEETS		GENERAL NOTES	2024 SPECIFICATION EFFECTIVE: 01-16-2024 REVISED:	LIST OF STANDARDS	2024 SPECIFICATION EFFECTIVE: 01-16-2024 REVISED:
<u>SHEET NUMBER</u>	<u>SHEET</u>	GRADE LINE: GRADING AND SURFACING:	The following Roadway Standards as appear in "Roadway Standard Drawings" Contracts Standards and Development Unit N. C. Department of Transportation - Raleigh, N. C., Dated January 16, 2024 are applicable to this project and by reference hereby are considered a part of these plans:	STD.NO.	TITLE
1	TITLE SHEET			DIVISION 2 - EARTHWORK 200.02 Method of Clearing - Method II 225.02 Guide for Grading Subgrade - Secondary and Local 225.04 Method of Obtaining Superelevation - Two Lane Pavement 275.01 Rock Plating	
1A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARDS	CLEARING:		DIVISION 3 - PIPE CULVERTS 300.01 Method of Pipe Installation (Use Detail in Lieu of Standards for Sheets 1 and 2 of 2) 310.10 Driveway Pipe Construction	
1B	CONVENTIONAL SYMBOLS			DIVISION 4 - MAJOR STRUCTURES 423.01 Bridge Approach Fills - Type 1 Approach Fill for Bridge Abutment	
2A-1	PAVEMENT SCHEDULE AND TYPICAL SECTIONS	SUPERELEVATION:		DIVISION 5 - SUBGRADE, BASES AND SHOULDERS 560.01 Method of Shoulder Construction - High Side of Superelevated Curve - Method I	
2C-1 THRU 2C-5	DETAILS IN LIEU OF STANDARDS			DIVISION 6 - ASPHALT BASES AND PAVEMENTS 654.01 Pavement Repairs	
3B-1	ROADWAY SUMMARIES	SHOULDER CONSTRUCTION:		DIVISION 8 - INCIDENTALS 806.01 Concrete Right-of-Way Marker 815.02 Subsurface Drain 840.00 Concrete Base Pad for Drainage Structures 840.31 Concrete Junction Box - 12" thru 66" Pipe 840.32 Brick Junction Box - 12" thru 66" Pipe 840.36 Traffic Bearing Grated Drop Inlet - for Steel (840.37) Double Frame and Grates 840.37 Steel Grate and Frame 840.54 Manhole Frame and Cover 840.66 Drainage Structure Steps 846.01 Concrete Curb, Gutter and Curb & Gutter 846.04 Drop Inlet Installation in Shoulder Berm Gutter 862.01 Guardrail Placement (Use Details in Lieu of Standards for Sheets 4, 6, 12 and 14 of 15) 862.02 Guardrail Installation (Use Detail in Lieu of Standard for Sheet 5 of 9) 862.03 Structure Anchor Units (Use Detail in Lieu of Standards for Sheet 6 and 8 of 9) 876.01 Rip Rap in Channels and Ditches 876.02 Guide for Rip Rap at Pipe Outlets	
3D-1	DRAINAGE SUMMARIES				
3G-1	GEOTECHNICAL SUMMARIES	SIDE ROADS:			
4	PLAN SHEET				
5	PROFILE SHEET				
TMP-1 THRU TMP-6	TRANSPORTATION MANAGEMENT PLANS				
PMP-1 THRU PMP-2	PAVEMENT MARKING PLANS				
EC-1 THRU EC-5	EROSION CONTROL PLANS				
SIGN-1 THRU SIGN-4	SIGNING PLANS				
UO-1 THRU UO-2	UTILITY BY OTHERS PLANS				
X-1	CROSS-SECTION SUMMARY				
X-2 THRU X-7	CROSS-SECTIONS				
S-1 THRU S-20	STRUCTURE PLANS				
W-1 THRU W-3	WALL PLANS				