



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

September 17, 2026

DANIEL H. JOHNSON
SECRETARY

ADDENDUM # 1

Contract No. DN01160
TIP No.: BN-0003
Federal Aid No.: 5114301
WBS Element: 51143.3.1
County: JACKSON
Description: Grading, Drainage, Paving, Signals, And Structure on SR 1580 (E. Hometown Pl) from US 23 Bus (W Main St) to Existing Trail in Jackson County

Letting Date: September 22, 2026

Plan Holders

Content Summary: Provision Changes

The above contract has experienced the following revisions:

1. Replace CONCRETE WHEEL STOP on page R-8, with the attached provision

These revisions do not change bid items or the associated quantities.

There is no ebsx addenda file associated with this addendum.

Thank you for your attention to this matter.

If you have any questions, please contact the Division Proposal Engineer at (828) 331-5200.

Sincerely,

Signed by:

29BD93927CF24F6...

Jeanette L. White, P.E.
Highway Division 14, Project Development-
Team Lead

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS - DIVISION 14
253 WEBSTER ROAD
SYLVA, NC 28779

Telephone: (828) 331-5200
Fax: (828) 331-5201
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
253 WEBSTER ROAD
SYLVA, NC 28779

The Contractor/supplier can use the electronic ticketing system of their choice to meet the requirements of this provision.

Measurement and Payment

No measurement or payment will be made for utilizing an electronic ticketing system as the cost of such shall be included in the contract price bid for the material being provided.

CONCRETE WHEEL STOP:

(9-8-26)

PSP 8 R005

Description

The work shall consist of furnishing and installing wheel stops as shown in the plans or as directed by the Engineer.

Materials

Refer to Division 10 of the *Standard Specifications*.

Item	Section
Portland Cement Concrete	1000
Reinforcing Steel	1070
Galvanized Steel	1076

Provide precast concrete wheel stops meeting the following requirements:

1. Factory cast anchor holes.
2. Chamfered edges.
3. Color shall be natural concrete unless otherwise shown in the plans.

Provide galvanized steel anchor pins.

Anchor pins shall be:

1. Minimum 5/8-inch diameter.
2. Minimum 18-inch length.
3. Quantity and placement as recommended by the manufacturer and shown on the plans.

Submit shop drawings and product information to the Engineer for review prior to ordering materials.

Construction Methods

Prior to installation:

1. Verify pavement surface is complete and accepted.
2. Verify wheel stop locations do not conflict with accessible routes, curb ramps, utilities, drainage structures, or vehicle overhang requirements.

Install wheel stops in accordance with the manufacturer's recommendations and at the locations and orientation shown in the plans.

Install wheel stops:

1. Plumb and level as required.
2. In continuous contact with the pavement surface.
3. Aligned perpendicular to parking stall striping unless otherwise shown in the plans.

4. Securely anchored with steel pins driven into the pavement and underlying material. Replace cracked, chipped, broken, or otherwise damaged wheel stops as directed by the Engineer.

Measurement and Payment

Concrete Wheel Stops will be measured at the contract unit price per each. Such price and payment will be considered full compensation for furnishing all materials including anchor pins, concrete, reinforcing steel, drilling, anchoring, tools, labor, equipment, and incidentals necessary to complete the work.

Repair any damage to pavement resulting from installation at no additional cost to the Department.

Payment will be made under:

Pay Item	Pay Unit
Concrete Wheel Stop	Each

FENCE RESET:

(2-20-14)(Rev. 1-16-24)

867

SPD 8-940

Revise the *Standard Specifications* as follows:

Page 8-49, Article 867-2 CONSTRUCTION METHODS, line 11, add the following as the first sentence in the second paragraph:

The fence will be removed and reset on the same day to prevent the escape of livestock.

TIMBER AND LUMBER:

(4-21-26)

235, 866, 1046, 1050, 1082, 1084, 1089, 1540

SP10 R82

Revise the *Standard Specifications* as follows:

Page 2-23, Article 235-2 MATERIALS, line 26, add the following as the third sentence of the fourth paragraph.

Use pressure treated wood bases meeting the requirements of Section 1082.

Page 8-45, Article 866-2 MATERIALS, line 26, replace “1076-7” with “1050-8”.

Page 10-73, Subarticle 1046-3(C) Treated Timber Posts, line 8, replace “treated southern pine” with “pressure treated southern pine”.

Page 10-76, Subarticle 1050-2(A) General, line 3, replace “Use treated southern pine meeting Articles 1082-2 and 1082-3” with “Use pressure treated southern pine meeting Articles 1082-2 and 1082-3”.

Page 10-76, Subarticle 1050-2(A) General, lines 15-16, replace “All round posts” with “All round wood posts and braces”.