

SUMMARY OF EARTHWORK  
(IN CUBIC YARDS)

Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste
-L2- STA. 11+90.00	-L2- STA. 19+60.00	238	77	77	238
PROJECT TOTALS:					
PROJECT TOTALS:		238	77	77	238
Waste in Lieu of Borrow					
Replace Topsoil on Borrow Pit (5%)					
GRAND TOTALS:		238	77	77	238
SAY:		240		80	

NOTES:

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR BY THE CONTRACT LUMP SUM PRICE FOR "GRADING".

ALL EARTHWORK QUANTITIES WERE DERIVED FROM ORD QUANTITIES BY NAMED BOUNDARY REPORT(S) AS DESCRIBED IN THE ORD QUICKSTART TRAINING.


PAVEMENT REMOVAL SUMMARY  
IN SQUARE YARDS

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP	CONCRETE REMOVAL	CONCRETE BREAKUP
-L2-	11+90.00	18+65.00	CL	1500			
		TOTAL:		1500			
		SAY:		1500			

DF18314.  
2045061


FINAL3B-2

NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION  
HENDERSON COUNTY



HIGHWAY DIVISION 14

PREPARED BY



KISINGER CAMPO  
& ASSOCIATES

NC FIRM LICENSE No: C-1506

301 Fayetteville St.,  
Suite 1500  
Raleigh, NC 27601  
(919) 882-7839

REVISIONS