

Station	Station	Uncl. Excav.	Embank. +%	Borrow	Waste
-L6- STA. 10+90.00	-L6- STA. 11+90.00	200	12	12	200
PROJECT TOTALS:					
PROJECT TOTALS:		200	12	12	200
Waste in Lieu of Borrow					
Replace Topsoil on Borrow Pit (5%)					
GRAND TOTALS:		200	12	12	200
SAY:		205		15	

SURVEY LINE	Station	Station	LOCATION LT/RT/CL	ASPHALT REMOVAL	ASPHALT BREAKUP	CONCRETE REMOVAL	CONCRETE BREAKUP
-L6-	10+90.00	11+90.00	CL	230			
		TOTAL:		230			
		SAY:		230			

APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR BY THE CONTRACT LUMP SUM PRICE FOR "GRADING".

<p>NOTES:</p> <p>APPROXIMATE QUANTITIES ONLY. UNCLASSIFIED EXCAVATION, BORROW EXCAVATION, FINE GRADING, CLEARING AND GRUBBING, AND REMOVAL OF EXISTING PAVEMENT WILL BE PAID FOR BY THE CONTRACT LUMP SUM PRICE FOR "GRADING".</p> <p>ALL EARTHWORK QUANTITIES WERE DERIVED FROM ORD QUANTITIES BY NAMED BOUNDARY REPORT(S) AS DESCRIBED IN THE ORD QUICKSTART TRAINING.</p>

[illegible]

REVISIONS