

TIP NO 11.700 MI
 FED AID NO STATE FUNDED
 MILLING,PAVING,PAVEMENT MARKING, CURB RAMPS, TC
 US 23 BUS, US 276, NC 209 AND VARIOUS SECONDARY ROUTES THROUGHOUT HAYWOOD COUNTY

		WNC PAVING INC		APAC ATLANTIC INC DBA	
		WAYNESVILLE, NC		HARRISON CONSTRUCTION COMPANY	
				ASHEVILLE, NC	
ROADWAY ITEMS					
0001	0000100000-N	800	MOBILIZATION	Lump Sum	154500.00
					200000.00
0002	1245000000-E	SP	SHOULDER RECONSTRUCTION	21.93 SMI	6800.00
					149124.00
0003	1297000000-E	607	MILL ASP PVMT ***** DTH (4.5)	13,820 SY	8.80
					121616.00
					13.50
					186570.00
0004	1308000000-E	607	MILLN ASPHALT PVMT ***** (0")(4.5")	610 SY	12.80
					7808.00
					15.50
					9455.00
0005	1503000000-E	610	ASP CONC INTR CRS I19.0C	2,470 TON	103.15
					254780.50
					120.00
					296400.00
0006	1519000000-E	610	ASP CONC SURF CRS S9.5B	4,363 TON	100.84
					439964.92
					112.00
					488656.00
0007	1520000000-E	SP	ASP CONC SURF CRS S9.5B LEVEL	4,690 TON	100.84
					472939.60
					115.00
					539350.00
0008	1523000000-E	610	ASP CONC SURF CRS S9.5C	1,235 TON	110.56
					136541.60
					130.00
					160550.00
0009	1575000000-E	620	ASP FOR PLANT MIX	800 TON	507.27
					405816.00
					725.00
					580000.00
0010	1704000000-E	SP	PATCHING EXIST PAVEMENT	4,930 TON	163.00
					803590.00
					175.00
					862750.00
0011	2605000000-N	848	CONCRETE CURB RAMPS	38 EA	4675.00
					177650.00
					4450.00
					169100.00
0012	2830000000-N	858	ADJ MANHOLES	36 EA	1000.00
					36000.00
					1200.00
					43200.00
0013	2845000000-N	858	ADJ METER OR VALVE BOXES	13 EA	1200.00
					15600.00
					1200.00
					15600.00
0014	4413000000-E	SP	WORK ZONE ADV/GEN WARN SIGN	1,195 SF	9.00
					10755.00
					8.74
					10444.30
0015	4457000000-N	SP	TEMP TRAFFIC CONTROL (SP)	Lump Sum	75540.00
					200000.00
0016	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	7 EA	183.75
					1286.25
					175.00
					1225.00
0017	4810000000-E	1205	PAINT PVMT MARKINGS 4"	485,584 LF	0.14
					67981.76
					0.13
					63125.92
0018	4835000000-E	1205	PAINT PVT MKG LINES 24"	52 LF	5.25
					273.00
					5.00
					260.00
0019	4845000000-N	1205	PAINT PVT MKG SYMBOL	7 EA	78.75
					551.25
					75.00
					525.00
0020	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) 50 MIL 4" WHITE THERMOPLASTIC	3,800 LF	0.66
					2508.00
					0.62
					2356.00
0021	4890000000-E	SP	GENERIC PAVEMENT MARKING ITEM (LF) 50 MIL 4" YELLOW THERMOPLASTIC	9,000 LF	0.66
					5940.00
					0.62
					5580.00
0022	4891000000-E	1205	GENERIC PVMT MARKING ITEM (LF) 1205 24" 90MIL THERMO MARKING LINE	892 LF	10.50
					9366.00
					10.00
					8920.00
0023	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM (EA) NON-CAST IRON SNOWPLOWABLE PAVEMENT MARK	567 EA	41.00
					23247.00
					46.25
					26223.75
0024	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	800 LF	12.02
					9616.00
					9.25
					7400.00
0025	7456000000-E	1726	LEAD-IN CABLE(*****)(14-2)	1,020 LF	3.36
					3427.20
					2.50
					2550.00
0026	4447000000-E	SP	PED CHANNEL DEVICES	50 LF	40.00
					2000.00
					38.00
					1900.00
0027	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) AUDIBLE WARNING DEVICES	5 EA	150.00
					750.00
					144.50
					722.50
0028	4600000000-N	SP	GENERIC TRAFFIC CONTROL ITEM (EA) TEMPORARY CURB RAMPS	2 EA	500.00
					1000.00
					476.25
					952.50
CONTRACT TOTAL				TOTAL	3390172.08
				TOTAL	4024167.97
ROADWAY ITEMS				SUB-TOTAL	3390172.08
				SUB-TOTAL	4024167.97

OCT 12, 2021 02:36 PM

HAYWOOD

2:00 PM 2 / 2 001
OCT 12 2021 DN00756

2022CPT.14.04.10441, 2022CPT.14.04.20441

TIP NO

11.700 MI

FED AID NO STATE FUNDED

MILLING,PAVING,PAVEMENT MARKING, CURB RAMPS, TC

US 23 BUS, US 276, NC 209 AND VARIOUS SECONDARY ROUTES THROUGHOUT HAYWOOD COUNTY

BIDDERS IN ORDER

CONTRACT TOTAL

WNC PAVING INC	1	3390172.08
APAC ATLANTIC INC DBA HARRISON CONSTRUCTION COMPANY	2	4024167.97