PROJECT REFERENCE NO.	SHEET NO.
WBS: 47315.3.1	PM-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN

HAYWOOD COUNTY

LOCATION: ALONG NC SR-1173 PLOTT CREEK RD. AND HAZELWOOD AVE

TYPE OF WORK: SIDEWALK, CURB AND GUTTER AND DRAINAGE

N
NC GRID
NAD 83 NA 2011



ROADWAY STANDARD DRAWINGS

2018 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 16, 2018 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
1205.01	Pavement Markings - Line Types and Offsets
1205.07	Pavement Markings - Pedestrian Crosswalks

INDEX

PM-1 PAVEMENT MARKING PLAN TITLE SHEET

PM2-PM6 PAVEMENT MARKING DETAILS

PAVEMENT MARKING SCHEDULE

8" STANDARD WHITE CROSSWALK LINES- CW1

24" WHITE STOP BAR- SB1

24" WHITE HIGH-VIS CROSSWALK LINES- CW2

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR AS DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
NC SR-1173 PLOTT CREEK RD. AND HAZELWOOD AVE	THERMOPLASTIC	

PLACE ONE (1) APPLICATION OF THERMOPLASTIC PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE.

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

TIP: EB-5859

CONTRACT: DN00690

03/08/99

29-AUG-2019 15:04
U:\plott creek sidewalk\plott creek sidewalk\paint\plottcreekcrosswalk_Sgn_PMP.dgn
mcorr AT DIV14-301560L