

PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.14.02.20201, 2027CPT.14.02.20221	11	13

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1520000000-E LEVELING COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2830000000-N ADJ. OF MANHOLES
								MI	FT			SMI	TON	SY	TONS	TONS	TONS	TONS	TONS	EA
2027CPT.14.02.20201	Cherokee	1	SR-1556 / MARTINS CREEK RD	FROM SR 1558 TO SR 1564	1	2	2WU	4.500	18	0.600	5.100	9.14	1,350			4,160		342	1,500	
TOTAL FOR MAP NO. 1								4.500				9.14	1,350			4,160		342	1,500	
2027CPT.14.02.20201	Cherokee	2	SR-1326 / JOE BROWN HWY	FROM TENN ST TO SR 1365	2	2	2WU	1.730	24	18.800	20.530	3.48	519	815	1,275			102	404	16
TOTAL FOR MAP NO. 2								1.730				3.48	519	815	1,275			102	404	16
2027CPT.14.02.20201	Cherokee	3	SR-1576 / CRISP RD	FROM SR 1305 TO SR 1508	1	2	2WU	1.280	18	0.890	2.170	2.50	384			1,070		81	230	
TOTAL FOR MAP NO. 3								1.280				2.50	384			1,070		81	230	
2027CPT.14.02.20201	Cherokee	4	SR-1565 / FOLK SCHOOL RD	FROM SR-1564 TO CLAY CO LINE	1	2	2WU	0.560	18	0.000	0.560	1.12	170			400		26	9	
TOTAL FOR MAP NO. 4								0.560				1.12	170			400		26	9	
TOTAL FOR PROJ NO. 2027CPT.14.02.20201								8.070				16.24	2,423	815	1,275	5,630		551	2,143	16
2027CPT.14.02.20221	Clay	5	SR-1115 / MCDONALD RD	FROM US 69 TO EOP	3	2	2WU	1.463	18	0.580	2.043	2.76	439				1,225	183	2,300	
TOTAL FOR MAP NO. 5								1.463				2.76	439				1,225	183	2,300	
2027CPT.14.02.20221	Clay	6	SR-1155 / JACK RABBIT RD	FROM HWY 175 TO EOM	1	2	2WU	1.250	20	0.000	1.250	1.84	375			910		136	1,600	
TOTAL FOR MAP NO. 6								1.250				1.84	375			910		136	1,600	
TOTAL FOR PROJ NO. 2027CPT.14.02.20221								2.713				4.60	814			910	1,225	319	3,900	
GRAND TOTAL								10.783				20.84	3,237	815	1,275	6,540	1,225	870	6,043	16