DocuSign Envelope ID: 04CC25D5-8935-40A3-AB14-6670DA165890

| PROJ. REFERENCE NO. | SHEET NO. |
|---|---|
| 14SP.20221.3 | PMP-1 |

# PAVEMENT MARKING PLAN




## ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C. DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES AND OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - TWO LANE & MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |
| 1261.01 | GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING |
| 1261.02 | GUARDRAIL AND BARRIER DELINEATORS - TYPES & MOUNTING |
| 1262.01 | GUARDRAIL END DELINEATION |

## GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A.) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE

| ROAD NAME: | MARKING |
|---|---|
| SR 1353 (OLD US 64) | PAINT |

B.) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C.) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

## FINAL PAVEMENT MARKING SCHEDULE

| SYMBOL | DESCRIPTION | QUANTITY BREAKDOWN | PAY ITEM | TOTAL QUANTITY |
|---|---|---|---|---|
| | | PAVEMENT MARKING LINES | | |
| PA | WHITE SOLID EDGE LINE | 1439 FT | PAINT (4") | 2878 FT |
| P8 | 2 FT. - 6 FT./SP WHITE MINISKIP | 39 FT | PAINT (4") | 78 FT |
| PI | YELLOW DOUBLE CENTER LINE | 1426 FT | PAINT (4") | 2852 FT |
| P2 | WHITE STOP BAR | 41 FT | PAINT (24") | 82 FT |

SCALE: 1" = 30'

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

V&M
Vaughn & Melton
Consulting Engineers
Asheville, North Carolina 828-253-2796
Charlotte, North Carolina 704-357-0488
Tri-Cities, Tennessee 423-467-8401
865-546-5800
Middlesboro, Kentucky 606-248-6600
Spartanburg, South Carolina 864-574-4775
Copyright © 2006 Vaughn & Melton, Inc.
All Rights Reserved

APPROVED: Lloyd DeWayne Brown DATE: 5/29/2018 14:13:09 AM PDT
DocuSigned by: 5395ADF1F57488...

SEAL
NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
WORK ZONE TRAFFIC CONTROL

PAVEMENT MARKING PLAN

5/21/2018
V:\Asheville\transportation\3\236-03 WTC 14SP.20221.3 Clay 101\Traffic\TrafficControl\TCP\BD-5IL101_pmp-1.dgn
User:jdaves