STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

# INDEX OF SHEETS


| | |
| --- | --- |
| 1 | TITLE SHEET |
| 2 | INDEX OF SHEETS, GENERAL NOTES AND LIST OF STANDARDS |
| 3 | CONVENTIONAL SYMBOLS |
| 3A | GUARDRAIL & EARTHWORK SUMMARY SHEET |
| 3B-3C | TYPICAL SECTIONS |
| 3D | BOX CULVERT DETAILS |
| 3E | TEMPORARY STREAM DIVERSION DETAIL |
| 4-6 | PLAN SHEETS |
| EC1-EC10 | EROSION CONTROL PLANS |
| C1 | SURVEY CONTROL SHEET |
| S1-S4 | STRIPING PLAN |
| X1-X26 | CROSS SECTIONS |
| P1-P6 | PROFILE SHEETS |


# GENERAL NOTES

GENERAL NOTES: 2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012

1 CARE SHALL BE TAKEN TO PREVENT DAMAGE TO EXISTING UTILITIES DURING CONSTRUCTION. ANY DAMAGE TO THESE UTILITIES SHALL BE REPAIRED AT THE CONTRACTOR'S EXPENSE.

2 THE CONTRACTOR SHALL MAINTAIN THE SITE IN A MANNER SO THAT WORKMEN AND PUBLIC SHALL BE PROTECTED FROM INJURY.

# LIST OF ROADWAY STANDARDS

2012 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 17, 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

| STD. NO. | TITLE |
| --- | --- |
| DIVISION 2 - EARTHWORK | |
| 200.03 | Method of Clearing - Method III |
| 225.02 | Guide for Grading Subgrade |
| 225.04 | Method of Obtaining Superelevation |
| DIVISION 3 - PIPE CULVERTS | |
| 300.01 | Method of Pipe Installation |
| DIVISION 5 - SUBGRADE, BASES AND SHOULDERS | |
| 560.01 | Method of Shoulder Construction |
| DIVISION 7 - CONCRETE PAVEMENTS AND SHOULDERS | |
| 700.05 | Tying Proposed Pavement to Existing Pavement |
| DIVISION 8 - INCIDENTALS | |
| 862.01 | Guardrail Placement |
| 862.02 | Guardrail Installation |
| 862.03 | Structure Anchor Units |
| DIVISION 11 - WORK ZONE TRAFFIC CONTROL | |
| 1101.01 | Detail Drawing for Two Way Undivided Work Zone Warning Signs |
| 1101.02 | Temporary Lane Closures |
| DIVISION 12 - PAVEMENT MARKINGS, MARKERS AND DELINEATION | |
| 1205.01 | Line Types and Offsets |
| DIVISION 16 - EROSION CONTROL AND ROADSIDE DEVELOPEMENT | |
| 1605.01 | Temporary Silt Fence |
| 1606.01 | Special Sediment Control Fence |
| 1607.01 | Gravel Construction Entrance |
| 1631.01 | Matting Installation |
| 1640.01 | Coir Fiber Baffle |