PROJECT REFERENCE NO.	SHEET NO.
43936.3.1; 2016CPT.14.03.10561.1	PM-1

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PAVEMENT MARKING PLAN

MACON COUNTY

LOCATION: ALONG NC HWY 19 /74 NEAR MACON/CHEROKEE COUNTY LINE

TYPE OF WORK: GRADING, PAVING, BOX CULVERT INSTALLATION, GUARDRAIL INSTALLATION

ROADWAY STANDARD DRAWINGS

2012 ROADWAY STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" - Highway Design Branch - N.C. Department of Transportation - Raleigh, N.C., dated January 17, 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.

STD. NO.	TITLE
1205.01	Pavement Markings- Line Types and Offsets
1205.02	Pavement Markings- 2 Lane and Multilane Roadways

INDEX

PM-1	PAVEMENT MARKING PLAN TITLE SHEET
PM2-PM4	PAVEMENT MARKING DETAIL

PAVEMENT MARKING SCHEDULE

FINAL
PAVEMENT MARKINGS

CLI	YELLOW DOUBLE CENTER	4" THERMO (50 MIL)
ETI	WHITE EDGELINE	4" THERMO (50 MIL)
CWG	WHITE GORE LINE	8" THERMO (50 MIL)

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR AS DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
HWY 19 / 74	THERMOPLASTIC	N/A

PLACE ONE (1) APPLICATION OF THERMOPLASTIC PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE.

A) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES

B) REMOVE/REPLACE ANY CONFLICTING/DAMGED PAVEMENT MARKINGS AND MARKERS.

CONTRACT: DN00534 TIP: SS-4914BO WBS ELEMENT:43936.3.1;2016PT.14.03.10561.1

09/08/99

09-AUG-2016 11:06
S:\Dist3\Macon\DN00534\DN00378\toptonrealign\dgn\pavement marking\DN00378_pvmntmkg_Rdy_dsn.dgn
arbrown4 AT DI4CAD272166