

PROJECT NO.	SHEET NO.	TOTAL NO.
2027CPT.14.04.20871, 2027CPT.14.04.20381 2027CPT.14.04.10381,	12	14

SUMMARY OF QUANTITIES

PROJECT NO	COUNTY	MAP NO	ROUTE	DESCRIPTION	TYP NO	LANES	LANE TYPE	LENGTH	WIDTH	BEGIN MP	END MP	1245000000-E SHOULDER RECONSTRUCTION	1260000000-E AGGREGATE SHOULDER BORROW	1297000000-E 1½" MILLING	1330000000-E INCIDENTAL MILLING	1519000000-E SURFACE COURSE, S9.5B	1523000000-E SURFACE COURSE, S9.5C	1575000000-E ASPHALT BINDER FOR PLANT MIX	1704000000-E PATCHING EXISTING PAVEMENT	2549000000-E 2'-6" CURB & GUTTER	2612500000-N REMOVE AND REPLACE CONCRETE CURB RAMPS	2815000000-N ADJ. OF DROP INLET	2830000000-N ADJ. OF MANHOLES	2845000000-N ADJ. OF METER OR VALVE BOX	6000000000-E TEMPORARY SILT FENCE	6029000000-E SAFETY FENCE	6117500000-N CONCRETE WASHOUT STRUCTURE	7444000000-E INDUCTIVE LOOP SAWCUT	7456100000-E LEAD-IN CABLE (14-2)	
								MI	FT			SMI	TON	SY	SY	TONS	TONS	TONS	TONS	LF	EA	EA	EA	EA	EA	EA	EA	EA	EA	EA
2027CPT.14.04.20871	Swain	1	SR-1195 / HWY 19A	FROM US 19 TO JCL	1	2	2WU	1.420	20	0.000	1.420	2.84	426				1,591	108	292											
TOTAL FOR MAP NO. 1							1.420					2.84	426				1,591	108	292											
2027CPT.14.04.20871	Swain	2	SR-1333 / TOOT HOLLOW RD/WATER ST	FROM SR 1364 TO SR 1337	1	2	2WU	1.670	20	0.000	1.670	3.34	501				1,736	126	500				2	3						
TOTAL FOR MAP NO. 2							1.670					3.34	501				1,736	126	500				2	3						
TOTAL FOR PROJ NO. 2027CPT.14.04.20871							3.090					6.18	927				3,327	234	792				2	3						
2027CPT.14.04.20381	Graham	3	SR-1223 / BEECH CREEK RD	FROM NC 143 TO EOM	2	2		2.310	20	0.000	2.310	4.62	693			1,964		137	192											
TOTAL FOR MAP NO. 3							2.310					4.62	693			1,964		137	192											
TOTAL FOR PROJ NO. 2027CPT.14.04.20381							2.310					4.62	693			1,964		137	192											
2027CPT.14.04.10381	Graham	4	US-129	FROM AIRPORT RD TO FIVE POINT RD	1	2	2WD	1.070	36	10.210	11.280	2.08	321		420		2,044	131	221											
TOTAL FOR MAP NO. 4							1.070					2.08	321		420		2,044	131	221											
2027CPT.14.04.10381	Graham	5	US-129	FROM JORDAN ST TO NC 143B	3	2	2WD	0.430	33	11.540	11.970			8,740	1,546		858	51	12	60	1	2		22	50	50	1	678.00	100.00	
TOTAL FOR MAP NO. 5							0.430							8,740	1,546		858	51	12	60	1	2		22	50	50	1	678.00	100.00	
2027CPT.14.04.10381	Graham	6	US-129	FROM NC 143B TO MOOSE BRANCH RD	3	2	2WU	0.450	24	11.970	12.420			6,653	1,316		664	39												
TOTAL FOR MAP NO. 6							0.450							6,653	1,316		664	39												
2027CPT.14.04.10381	Graham	7	NC-143 BUS	FROM US 129 TO JUNLUSKA RD	3	2	2WU	0.540	40	3.430	2.890			13,305			1,158	69	19				16	20						
TOTAL FOR MAP NO. 7							0.540							13,305			1,158	69	19				16	20						
2027CPT.14.04.10381	Graham	8	NC-143 BUS	FROM JUNLUSKA RD TO SNOWBIRD	1	2	2WU	0.340	27	2.890	2.550	0.64	102				558	34	24			2								
TOTAL FOR MAP NO. 8							0.340					0.64	102				558	34	24			2								
TOTAL FOR PROJ NO. 2027CPT.14.04.10381							2.830					2.72	423	28,698	3,282		5,282	324	276	60	1	4	16	42	50	50	1	678.00	100.00	
GRAND TOTAL							8.230					13.52	2,043	28,698	3,282	1,964	8,609	695	1,260	60	1	4	18	45	50	50	1	678.00	100.00	