



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

JOSH STEIN
GOVERNOR

DANIEL H. JOHNSON
SECRETARY

October 23, 2025

ADDENDUM # 2

Contract No. DN01135
TIP No.: N/A
Federal Aid No.: HELENE
WBS Element: DF18314.2045413, DF18314.2045408, DF18314.2045405,
DF18314.2045404, DF18314.2045233, DF18314.2045234,
DF18314.2045231, DF18314.2045480, DF18314.2045481,
DF18314.2045230, DF18314.2045121, DF18314.2045126

County: Henderson
Description: Grading, Drainage, Paving, Slope Repairs & Culverts Along SR 1594
& SR 1569 Bearwallow Mountain Rd Between US 74A And Old
Clear Creek Rd In Henderson County

Letting Date: October 28, 2025

Plan Holders

Content Summary: Questions and Responses

A bidder has posed the following questions; the Department has provided corresponding responses:

Question 1. The quantity provided for Temporary Shoring is this the SF face of the Wire Fence?

Response 1: The quantity provided for the Temporary Shoring is the SF of the temporary shoring wall face.

Question 2. Are the Soil Nails for this Temporary Shoring included in the Quantity of Line Item 91 Item 8847000000-E Generic Retaining Wall Item Soil Nail Slope Stabilization? Or Are these Soil Nails Incidental to the Temp Shoring Item?

Response 2: They are incidental per the shoring special provision.

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS - DIVISION 14
253 WEBSTER ROAD
SYLVA, NC 28779

Telephone: (828) 331-5200
Fax: (828) 331-5201
Customer Service: 1-877-368-4968

Location:
253 WEBSTER ROAD
SYLVA, NC 28779

Website: www.ncdot.gov

Question 3. I see we are given some different options according to the Spec book for proposed backfill of the MSE Wall. Is there a preferred material we are supposed to backfill with? Is there a pay item for this backfill material? Is this Backfill Incidental to the Temp Shoring Item?

Response 3: See standard shoring provision section (A) for backfill specs.

Question 4. How does the Geotextiles and Geogrids get paid for? Can the Department provide quantities for these items? Would this work be incidental to the Temp Shoring Item?

Response 4: They are incidental per the shoring special provision.

Question 5. When we enter Phase 2 of the MOT (Traffic Management) plan on site 5, what exactly gets removed? Are we to leave the soil nails in place or the wire baskets and Geogrid? How much needs to be removed vs how much we can leave?

Response 5: Temporary Shoring #1 will need to be removed as excavations are performed to:

- 1) remove the temporary alignment
- 2) remove the temporary pipe extension
- 3) install the remaining segments of the 60" pipe

Temporary Shoring #2 will need to be removed to a sufficient depth to permit full-depth pavement to be placed in the final roadway location.

Question 6. Does the Temporary pavement that the barrier wall sits on have a pay item or is this incidental to other Temp MOT (Traffic Management Plans) items?

Response 6: Temporary pavement is included in the total pavement pay items.

Question 7. For the Temporary Pavement markings called out in the Phasing Notes. Where do these items get paid for? Would the Thermoplastic Pavement markings item include these temp markings or are they incidental to other items?

Response 7: The temporary pavement markings are Paint. A quantity for paint was included in the pay items.

Question 8. We were hoping that you would be able to share a summary sheet which breaks down all the pay items including provided quantities by site number, is this something you have and can provide?

Response 8: See attachment.

Question 9. It looks like there was already some temporary repairs made at some of these slides. It looks like the previous repairs primarily used rock embankments to build up some of these shoulders. Are we allowed to reuse the existing material on site or are we expected to haul this material out and bring in new stone?

Response 9: The contractor is responsible for placing suitable materials. Re-use of the existing materials is acceptable if it meets the spec and at the discretion of the engineer.

These revisions do not change bid items or the associated quantities.

There is no ebsx addenda file associated with this addendum.

Thank you for your attention to this matter.

If you have any questions, please contact the Division Proposal Engineer at (828) 331-5200.

Sincerely,

Signed by:

29BD93927CF24F6...

Jeanette L. White, P.E.
Highway Division 14
Project Development - Team Lead

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045121	0000100000-N	MOBILIZATION	LS	0.084	
DF18314.2045121	0000400000-N	CONSTRUCTION SURVEYING	LS	0.084	
DF18314.2045121	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045121	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045121	0043000000-N	GRADING	LS	0.084	
DF18314.2045121	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045121	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045121	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	60	
DF18314.2045121	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	55	
DF18314.2045121	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045121	2209000000-E	ENDWALLS	CY	2.3	
DF18314.2045121	3628000000-E	RIP RAP, CLASS I	TON	15	
DF18314.2045121	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	100	
DF18314.2045121	4025000000-E	CONTRACTOR FURNISHED, TYPE *** SIGN	SF	8 (E)	
DF18314.2045121	4072000000-E	SUPPORTS, 3-LB STEEL U-CHANNEL	LF	26	
DF18314.2045121	4102000000-N	SIGN ERECTION, TYPE E	EA	1	
DF18314.2045121	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045121	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045121	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045121	4430000000-N	DRUMS	EA	21	
DF18314.2045121	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	470	
DF18314.2045121	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045121	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045121	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045121	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045121	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045121	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045121	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045121	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045121	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045121	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045121	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045121	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045121	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045121	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045121	6084000000-E	SEEDING & MULCHING	ACR	0.8	

DF18314.2045121	6087000000-E	MOWING	ACR	0.6
DF18314.2045121	6090000000-E	SEED FOR REPAIR SEEDING	LB	3
DF18314.2045121	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045121	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045121	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045121	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045121	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045121	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045126	0000100000-N	MOBILIZATION	LS	0.084	
DF18314.2045126	0000400000-N	CONSTRUCTION SURVEYING	LS	0.084	
DF18314.2045126	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045126	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045126	0043000000-N	GRADING	LS	0.084	
DF18314.2045126	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045126	0241000000-E	GENERIC GRADING ITEM	SY	1310	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045126	0314000000-E	SELECT MATERIAL, CLASS *****	TON	2189	(VII)
DF18314.2045126	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045126	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	60	
DF18314.2045126	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	60	
DF18314.2045126	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045126	3642000000-E	RIP RAP, CLASS A	TON	13	
DF18314.2045126	3649000000-E	RIP RAP, CLASS B	TON	57	
DF18314.2045126	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045126	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045126	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045126	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045126	4430000000-N	DRUMS	EA	21	
DF18314.2045126	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	500	
DF18314.2045126	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045126	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045126	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045126	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045126	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045126	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045126	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045126	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045126	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045126	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045126	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045126	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045126	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045126	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045126	6084000000-E	SEEDING & MULCHING	ACR	0.8	
DF18314.2045126	6087000000-E	MOWING	ACR	0.6	

DF18314.2045126	6090000000-E	SEED FOR REPAIR SEEDING	LB	3
DF18314.2045126	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045126	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045126	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045126	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045126	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045126	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045230	8834000000-N	GENERIC RETAINING WALL ITEM	EA	6	SOIL NAIL PROOF TESTS
DF18314.2045230	8834000000-N	GENERIC RETAINING WALL ITEM	EA	1	SOIL NAIL PROOF TESTS
DF18314.2045230	8847000000-E	GENERIC RETAINING WALL ITEM	SF	6360	SOIL NAIL SLOPE STABILIZATION
DF18314.2045230	8847000000-E	GENERIC RETAINING WALL ITEM	SF	610	SOIL NAIL SLOPE STABILIZATION
DF18314.2045230	0000100000-N	MOBILIZATION	LS	0.084	
DF18314.2045230	0000400000-N	CONSTRUCTION SURVEYING	LS	0.084	
DF18314.2045230	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045230	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045230	0043000000-N	GRADING	LS	0.084	
DF18314.2045230	0057000000-E	UNDERCUT EXCAVATION	CY	750	
DF18314.2045230	0194000000-E	SELECT GRANULAR MATERIAL, CLASS III	CY	500	
DF18314.2045230	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	260	
DF18314.2045230	0318000000-E	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	TON	20	
DF18314.2045230	0321000000-E	FOUNDATION CONDITIONING GEOTEXTILE	SY	50	
DF18314.2045230	0576000000-E	*** CS PIPE CULVERTS, ***** THICK	LF	42	(60", 0.105")
DF18314.2045230	0588000000-E	18" CS PIPE CULVERTS, 0.064" THICK	LF	84	
DF18314.2045230	1099500000-E	SHALLOW UNDERCUT	CY	100	
DF18314.2045230	1099700000-E	CLASS IV SUBGRADE STABILIZATION	TON	200	
DF18314.2045230	1112000000-E	GEOTEXTILE FOR SUBGRADE STABILIZATION	SY	300	
DF18314.2045230	1121000000-E	AGGREGATE BASE COURSE	TON	200	
DF18314.2045230	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045230	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	260	
DF18314.2045230	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	200	
DF18314.2045230	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	25	
DF18314.2045230	2022000000-E	SUBDRAIN EXCAVATION	CY	70	
DF18314.2045230	2026000000-E	GEOTEXTILE FOR SUBSURFACE DRAINS	SY	200	
DF18314.2045230	2036000000-E	SUBDRAIN COARSE AGGREGATE	CY	40	
DF18314.2045230	2044000000-E	6" PERFORATED SUBDRAIN PIPE	LF	200	
DF18314.2045230	2070000000-N	SUBDRAIN PIPE OUTLET	EA	1	
DF18314.2045230	2077000000-E	6" OUTLET PIPE	LF	6	
DF18314.2045230	2220000000-E	REINFORCED ENDWALLS	CY	5.9	
DF18314.2045230	2253000000-E	PIPE COLLARS	CY	0.5	
DF18314.2045230	2286000000-N	MASONRY DRAINAGE STRUCTURES	EA	2	
DF18314.2045230	2366000000-N	FRAME WITH TWO GRATES, STD 840.24	EA	1	
DF18314.2045230	2367000000-N	FRAME WITH TWO GRATES, STD 840.29	EA	1	
DF18314.2045230	2577000000-E	CONCRETE EXPRESSWAY GUTTER	LF	180	

DF18314.2045230	3649000000-E	RIP RAP, CLASS B	TON	40
DF18314.2045230	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	350
DF18314.2045230	4025000000-E	CONTRACTOR FURNISHED, TYPE *** SIGN	SF	9 (E)
DF18314.2045230	4072000000-E	SUPPORTS, 3-LB STEEL U-CHANNEL	LF	42
DF18314.2045230	4102000000-N	SIGN ERECTION, TYPE E	EA	3
DF18314.2045230	4155000000-N	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	EA	1
DF18314.2045230	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48
DF18314.2045230	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	220
DF18314.2045230	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	2
DF18314.2045230	4430000000-N	DRUMS	EA	40
DF18314.2045230	4465000000-N	TEMPORARY CRASH CUSHIONS	EA	2
DF18314.2045230	4470000000-N	REMOVE & RESET TEMPORARY CRASH CUSHION	EA	2
DF18314.2045230	4485000000-E	PORTABLE CONCRETE BARRIER	LF	170
DF18314.2045230	4500000000-E	REMOVE AND RESET PORTABLE CONCRETE BARRIER	LF	170
DF18314.2045230	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	2600
DF18314.2045230	4810000000-E	PAINT PAVEMENT MARKING LINES (4")	LF	2600
DF18314.2045230	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40
DF18314.2045230	6000000000-E	TEMPORARY SILT FENCE	LF	1479
DF18314.2045230	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	83
DF18314.2045230	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	236
DF18314.2045230	6012000000-E	SEDIMENT CONTROL STONE	TON	111
DF18314.2045230	6015000000-E	TEMPORARY MULCHING	ACR	0.9
DF18314.2045230	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	60
DF18314.2045230	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.3
DF18314.2045230	6024000000-E	TEMPORARY SLOPE DRAINS	LF	102
DF18314.2045230	6029000000-E	SAFETY FENCE	LF	76
DF18314.2045230	6030000000-E	SILT EXCAVATION	CY	290
DF18314.2045230	6036000000-E	MATTING FOR EROSION CONTROL	SY	2000
DF18314.2045230	6037000000-E	COIR FIBER MAT	SY	20
DF18314.2045230	6042000000-E	1/4" HARDWARE CLOTH	LF	166
DF18314.2045230	6084000000-E	SEEDING & MULCHING	ACR	3
DF18314.2045230	6087000000-E	MOWING	ACR	2.4
DF18314.2045230	6090000000-E	SEED FOR REPAIR SEEDING	LB	10
DF18314.2045230	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045230	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	75
DF18314.2045230	6108000000-E	FERTILIZER TOPDRESSING	TON	2.3
DF18314.2045230	6114500000-N	SPECIALIZED HAND MOWING	MHR	2

DF18314.2045230	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	5
DF18314.2045230	6117500000-N	CONCRETE WASHOUT STRUCTURE	EA	1
DF18314.2045230	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	3 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045231	8834000000-N	GENERIC RETAINING WALL ITEM	EA	6	SOIL NAIL PROOF TESTS
DF18314.2045231	8847000000-E	GENERIC RETAINING WALL ITEM	SF	6070	SOIL NAIL SLOPE STABILIZATION
DF18314.2045231	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045231	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045231	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045231	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045231	0043000000-N	GRADING	LS	0.083	
DF18314.2045231	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045231	1330000000-E	INCIDENTAL MILLING	SY	70	
DF18314.2045231	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	140	
DF18314.2045231	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	100	
DF18314.2045231	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	15	
DF18314.2045231	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045231	4025000000-E	CONTRACTOR FURNISHED, TYPE *** SIGN	SF	25 (E)	
DF18314.2045231	4072000000-E	SUPPORTS, 3-LB STEEL U-CHANNEL	LF	62	
DF18314.2045231	4102000000-N	SIGN ERECTION, TYPE E	EA	3	
DF18314.2045231	4155000000-N	DISPOSAL OF SIGN SYSTEM, U-CHANNEL	EA	2	
DF18314.2045231	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045231	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045231	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045231	4430000000-N	DRUMS	EA	21	
DF18314.2045231	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	640	
DF18314.2045231	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045231	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045231	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045231	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045231	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045231	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045231	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045231	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045231	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045231	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045231	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045231	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045231	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045231	6042000000-E	1/4" HARDWARE CLOTH	LF	42	

DF18314.2045231	6084000000-E	SEEDING & MULCHING	ACR	0.8
DF18314.2045231	6087000000-E	MOWING	ACR	0.6
DF18314.2045231	6090000000-E	SEED FOR REPAIR SEEDING	LB	3
DF18314.2045231	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045231	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045231	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045231	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045231	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045231	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045233	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045233	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045233	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045233	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045233	0043000000-N	GRADING	LS	0.083	
DF18314.2045233	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045233	0241000000-E	GENERIC GRADING ITEM	SY	1180	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045233	0314000000-E	SELECT MATERIAL, CLASS *****	TON	2105	(VII)
DF18314.2045233	0318000000-E	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	TON	10	
DF18314.2045233	0321000000-E	FOUNDATION CONDITIONING GEOTEXTILE	SY	20	
DF18314.2045233	0594000000-E	24" CS PIPE CULVERTS, 0.064" THICK	LF	52	
DF18314.2045233	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045233	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	80	
DF18314.2045233	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	70	
DF18314.2045233	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045233	3642000000-E	RIP RAP, CLASS A	TON	38	
DF18314.2045233	3649000000-E	RIP RAP, CLASS B	TON	63	
DF18314.2045233	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045233	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045233	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045233	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045233	4430000000-N	DRUMS	EA	21	
DF18314.2045233	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	620	
DF18314.2045233	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045233	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045233	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045233	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045233	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045233	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045233	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045233	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045233	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045233	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045233	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045233	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045233	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045233	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045233	6084000000-E	SEEDING & MULCHING	ACR	0.8	

DF18314.2045233	6087000000-E	MOWING	ACR	0.6
DF18314.2045233	6090000000-E	SEED FOR REPAIR SEEDING	LB	3
DF18314.2045233	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045233	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045233	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045233	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045233	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045233	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045234	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045234	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045234	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045234	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045234	0043000000-N	GRADING	LS	0.083	
DF18314.2045234	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045234	0318000000-E	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	TON	10	
DF18314.2045234	0321000000-E	FOUNDATION CONDITIONING GEOTEXTILE	SY	10	
DF18314.2045234	0576000000-E	**" CS PIPE CULVERTS, *****" THICK	LF	12	(60", 0.105")
DF18314.2045234	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045234	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	50	
DF18314.2045234	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	50	
DF18314.2045234	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045234	2253000000-E	PIPE COLLARS	CY	2.9	
DF18314.2045234	2495000000-E	GENERIC DRAINAGE ITEM	CY	8.3	MODIFIED CONCRETE ENDWALL
DF18314.2045234	3628000000-E	RIP RAP, CLASS I	TON	35	
DF18314.2045234	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	120	
DF18314.2045234	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045234	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045234	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045234	4430000000-N	DRUMS	EA	21	
DF18314.2045234	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	410	
DF18314.2045234	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045234	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045234	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045234	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045234	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045234	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045234	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045234	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045234	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045234	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045234	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045234	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045234	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045234	6042000000-E	1/4" HARDWARE CLOTH	LF	42	

DF18314.2045234	6084000000-E	SEEDING & MULCHING	ACR	0.8
DF18314.2045234	6087000000-E	MOWING	ACR	0.6
DF18314.2045234	6090000000-E	SEED FOR REPAIR SEEDING	LB	3
DF18314.2045234	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045234	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045234	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045234	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045234	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045234	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	Category	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045404	0001 Roadway Items	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045404	0001 Roadway Items	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045404	0001 Roadway Items	0043000000-N	GRADING	LS	0.083	
DF18314.2045404	0001 Roadway Items	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	30	
DF18314.2045404	0001 Roadway Items	0199000000-E	TEMPORARY SHORING	SF	840	
DF18314.2045404	0001 Roadway Items	0241000000-E	GENERIC GRADING ITEM	SY	870	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045404	0001 Roadway Items	0314000000-E	SELECT MATERIAL, CLASS *****	TON	1980	(VII)
DF18314.2045404	0001 Roadway Items	0318000000-E	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	TON	10	
DF18314.2045404	0001 Roadway Items	0321000000-E	FOUNDATION CONDITIONING GEOTEXTILE	SY	30	
DF18314.2045404	0001 Roadway Items	0576000000-E	**" CS PIPE CULVERTS, ***** THICK	LF	56	(60", 0.105")
DF18314.2045404	0001 Roadway Items	1121000000-E	AGGREGATE BASE COURSE	TON	150	
DF18314.2045404	0001 Roadway Items	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045404	0001 Roadway Items	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	90	
DF18314.2045404	0001 Roadway Items	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	75	
DF18314.2045404	0001 Roadway Items	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045404	0001 Roadway Items	2220000000-E	REINFORCED ENDWALLS	CY	5.9	
DF18314.2045404	0001 Roadway Items	3628000000-E	RIP RAP, CLASS I	TON	40	
DF18314.2045404	0001 Roadway Items	3642000000-E	RIP RAP, CLASS A	TON	13	
DF18314.2045404	0001 Roadway Items	3649000000-E	RIP RAP, CLASS B	TON	65	
DF18314.2045404	0001 Roadway Items	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	210	
DF18314.2045404	0001 Roadway Items	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045404	0001 Roadway Items	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	220	
DF18314.2045404	0001 Roadway Items	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	2	
DF18314.2045404	0001 Roadway Items	4430000000-N	DRUMS	EA	25	
DF18314.2045404	0001 Roadway Items	4465000000-N	TEMPORARY CRASH CUSHIONS	EA	2	
DF18314.2045404	0001 Roadway Items	4470000000-N	REMOVE & RESET TEMPORARY CRASH CUSHION	EA	2	
DF18314.2045404	0001 Roadway Items	4485000000-E	PORTABLE CONCRETE BARRIER	LF	140	
DF18314.2045404	0001 Roadway Items	4500000000-E	REMOVE AND RESET PORTABLE CONCRETE BARRIER	LF	140	
DF18314.2045404	0001 Roadway Items	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	570	
DF18314.2045404	0001 Roadway Items	4810000000-E	PAINT PAVEMENT MARKING LINES (4")	LF	2150	
DF18314.2045404	0001 Roadway Items	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045404	0001 Roadway Items	6000000000-E	TEMPORARY SILT FENCE	LF	740	
DF18314.2045404	0001 Roadway Items	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	42	
DF18314.2045404	0001 Roadway Items	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	118	
DF18314.2045404	0001 Roadway Items	6012000000-E	SEDIMENT CONTROL STONE	TON	56	
DF18314.2045404	0001 Roadway Items	6015000000-E	TEMPORARY MULCHING	ACR	0.5	
DF18314.2045404	0001 Roadway Items	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	30	
DF18314.2045404	0001 Roadway Items	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.2	
DF18314.2045404	0001 Roadway Items	6024000000-E	TEMPORARY SLOPE DRAINS	LF	51	
DF18314.2045404	0001 Roadway Items	6029000000-E	SAFETY FENCE	LF	38	
DF18314.2045404	0001 Roadway Items	6030000000-E	SILT EXCAVATION	CY	145	
DF18314.2045404	0001 Roadway Items	6036000000-E	MATTING FOR EROSION CONTROL	SY	1000	
DF18314.2045404	0001 Roadway Items	6037000000-E	COIR FIBER MAT	SY	10	
DF18314.2045404	0001 Roadway Items	6042000000-E	1/4" HARDWARE CLOTH	LF	83	

DF18314.2045404	0001 Roadway Items	6045000000-E	**" TEMPORARY PIPE	LF	20 (48")
DF18314.2045404	0001 Roadway Items	6084000000-E	SEEDING & MULCHING	ACR	1.5
DF18314.2045404	0001 Roadway Items	6087000000-E	MOWING	ACR	1.2
DF18314.2045404	0001 Roadway Items	6090000000-E	SEED FOR REPAIR SEEDING	LB	5
DF18314.2045404	0001 Roadway Items	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045404	0001 Roadway Items	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	38
DF18314.2045404	0001 Roadway Items	6108000000-E	FERTILIZER TOPDRESSING	TON	1.2
DF18314.2045404	0001 Roadway Items	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045404	0001 Roadway Items	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	3
DF18314.2045404	0001 Roadway Items	6117500000-N	CONCRETE WASHOUT STRUCTURE	EA	1
DF18314.2045404	0001 Roadway Items	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	2 PREFABRICATED CONCRETE WASHOUT

WBS	Category	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045405	0001 Roadway Items	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045405	0001 Roadway Items	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045405	0001 Roadway Items	0043000000-N	GRADING	LS	0.083	
DF18314.2045405	0001 Roadway Items	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045405	0001 Roadway Items	0241000000-E	GENERIC GRADING ITEM	SY	660	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045405	0001 Roadway Items	0314000000-E	SELECT MATERIAL, CLASS *****	TON	1785	(VII)
DF18314.2045405	0001 Roadway Items	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045405	0001 Roadway Items	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	40	
DF18314.2045405	0001 Roadway Items	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	40	
DF18314.2045405	0001 Roadway Items	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	5	
DF18314.2045405	0001 Roadway Items	3642000000-E	RIP RAP, CLASS A	TON	13	
DF18314.2045405	0001 Roadway Items	3649000000-E	RIP RAP, CLASS B	TON	38	
DF18314.2045405	0001 Roadway Items	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045405	0001 Roadway Items	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045405	0001 Roadway Items	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045405	0001 Roadway Items	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045405	0001 Roadway Items	4430000000-N	DRUMS	EA	21	
DF18314.2045405	0001 Roadway Items	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	330	
DF18314.2045405	0001 Roadway Items	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045405	0001 Roadway Items	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045405	0001 Roadway Items	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045405	0001 Roadway Items	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045405	0001 Roadway Items	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045405	0001 Roadway Items	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045405	0001 Roadway Items	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045405	0001 Roadway Items	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045405	0001 Roadway Items	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045405	0001 Roadway Items	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045405	0001 Roadway Items	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045405	0001 Roadway Items	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045405	0001 Roadway Items	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045405	0001 Roadway Items	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045405	0001 Roadway Items	6084000000-E	SEEDING & MULCHING	ACR	0.8	
DF18314.2045405	0001 Roadway Items	6087000000-E	MOWING	ACR	0.6	
DF18314.2045405	0001 Roadway Items	6090000000-E	SEED FOR REPAIR SEEDING	LB	3	
DF18314.2045405	0001 Roadway Items	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1	
DF18314.2045405	0001 Roadway Items	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19	
DF18314.2045405	0001 Roadway Items	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6	
DF18314.2045405	0001 Roadway Items	6114500000-N	SPECIALIZED HAND MOWING	MHR	1	
DF18314.2045405	0001 Roadway Items	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2	
DF18314.2045405	0001 Roadway Items	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1	PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045408	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045408	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045408	0043000000-N	GRADING	LS	0.083	
DF18314.2045408	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045408	0241000000-E	GENERIC GRADING ITEM	SY	720	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045408	0314000000-E	SELECT MATERIAL, CLASS *****	TON	385	(VII)
DF18314.2045408	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045408	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	80	
DF18314.2045408	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	70	
DF18314.2045408	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045408	3642000000-E	RIP RAP, CLASS A	TON	13	
DF18314.2045408	3649000000-E	RIP RAP, CLASS B	TON	50	
DF18314.2045408	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045408	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045408	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045408	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045408	4430000000-N	DRUMS	EA	21	
DF18314.2045408	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	670	
DF18314.2045408	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045408	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045408	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045408	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045408	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045408	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045408	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045408	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045408	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045408	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045408	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045408	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045408	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045408	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045408	6084000000-E	SEEDING & MULCHING	ACR	0.8	
DF18314.2045408	6087000000-E	MOWING	ACR	0.6	
DF18314.2045408	6090000000-E	SEED FOR REPAIR SEEDING	LB	3	
DF18314.2045408	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1	
DF18314.2045408	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19	

DF18314.2045408	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045408	6114500000-N	SPECIALIZED HAND MOWING	MHR	0.5
DF18314.2045408	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045408	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045413	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045413	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045413	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045413	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045413	0043000000-N	GRADING	LS	0.083	
DF18314.2045413	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	75	
DF18314.2045413	1330000000-E	INCIDENTAL MILLING	SY	70	
DF18314.2045413	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	80	
DF18314.2045413	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	70	
DF18314.2045413	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045413	3635000000-E	RIP RAP, CLASS II	TON	80	
DF18314.2045413	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	460	
DF18314.2045413	4025000000-E	CONTRACTOR FURNISHED, TYPE *** SIGN	SF	7 (E)	
DF18314.2045413	4072000000-E	SUPPORTS, 3-LB STEEL U-CHANNEL	LF	13	
DF18314.2045413	4102000000-N	SIGN ERECTION, TYPE E	EA	1	
DF18314.2045413	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045413	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045413	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045413	4430000000-N	DRUMS	EA	21	
DF18314.2045413	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	630	
DF18314.2045413	4709000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (24", 90 MILS)	LF	20	
DF18314.2045413	6000000000-E	TEMPORARY SILT FENCE	LF	1152	
DF18314.2045413	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	104	
DF18314.2045413	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	295	
DF18314.2045413	6012000000-E	SEDIMENT CONTROL STONE	TON	102	
DF18314.2045413	6015000000-E	TEMPORARY MULCHING	ACR	1.2	
DF18314.2045413	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	75	
DF18314.2045413	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.4	
DF18314.2045413	6024000000-E	TEMPORARY SLOPE DRAINS	LF	128	
DF18314.2045413	6029000000-E	SAFETY FENCE	LF	95	
DF18314.2045413	6030000000-E	SILT EXCAVATION	CY	363	
DF18314.2045413	6036000000-E	MATTING FOR EROSION CONTROL	SY	2500	
DF18314.2045413	6037000000-E	COIR FIBER MAT	SY	25	
DF18314.2045413	6042000000-E	1/4" HARDWARE CLOTH	LF	208	
DF18314.2045413	6070000000-N	SPECIAL STILLING BASINS	EA	1	

DF18314.2045413	6071030000-E	COIR FIBER BAFFLE	LF	415
DF18314.2045413	6084000000-E	SEEDING & MULCHING	ACR	3.8
DF18314.2045413	6087000000-E	MOWING	ACR	3
DF18314.2045413	6090000000-E	SEED FOR REPAIR SEEDING	LB	13
DF18314.2045413	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045413	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	94
DF18314.2045413	6108000000-E	FERTILIZER TOPDRESSING	TON	2.9
DF18314.2045413	6111000000-E	IMPERVIOUS DIKE	LF	80
DF18314.2045413	6114500000-N	SPECIALIZED HAND MOWING	MHR	3
DF18314.2045413	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	7
DF18314.2045413	6117500000-N	CONCRETE WASHOUT STRUCTURE	EA	1
DF18314.2045413	6120000000-E	CULVERT DIVERSION CHANNEL	CY	74
DF18314.2045413	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	4 PREFABRICATED CONCRETE WASHOUT
DF18314.2045413	8804000000-N	GENERIC CULVERT ITEM	LS	1 ALUMINUM BOX CULVERT
DF18314.2045413	8818000000-E	GENERIC CULVERT ITEM	TON	740 CULVERT BACKFILL

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045480	8834000000-N	GENERIC RETAINING WALL ITEM	EA	3	SOIL NAIL PROOF TESTS
DF18314.2045480	8847000000-E	GENERIC RETAINING WALL ITEM	SF	2720	SOIL NAIL SLOPE STABILIZATION
DF18314.2045480	0000100000-N	MOBILIZATION	LS	0.083	
DF18314.2045480	0000400000-N	CONSTRUCTION SURVEYING	LS	0.083	
DF18314.2045480	0001000000-E	CLEARING & GRUBBING .. ACRE(S)	LS	0.1	
DF18314.2045480	0008000000-E	SUPPLEMENTARY CLEARING & GRUBBING	ACR	1	
DF18314.2045480	0043000000-N	GRADING	LS	0.083	
DF18314.2045480	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045480	1330000000-E	INCIDENTAL MILLING	SY	70	
DF18314.2045480	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	60	
DF18314.2045480	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	50	
DF18314.2045480	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045480	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045480	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045480	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045480	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045480	4430000000-N	DRUMS	EA	21	
DF18314.2045480	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	500	
DF18314.2045480	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045480	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045480	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045480	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045480	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045480	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045480	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045480	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045480	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045480	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045480	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045480	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045480	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045480	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045480	6084000000-E	SEEDING & MULCHING	ACR	0.8	
DF18314.2045480	6087000000-E	MOWING	ACR	0.6	
DF18314.2045480	6090000000-E	SEED FOR REPAIR SEEDING	LB	3	

DF18314.2045480	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1
DF18314.2045480	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19
DF18314.2045480	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045480	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045480	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045480	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT

WBS	PayItem	Description	UOM	Quantity	Supplemental
DF18314.2045481	0000100000-N	MOBILIZATION	LS	0.084	
DF18314.2045481	0000400000-N	CONSTRUCTION SURVEYING	LS	0.084	
DF18314.2045481	0043000000-N	GRADING	LS	0.084	
DF18314.2045481	0196000000-E	GEOTEXTILE FOR SOIL STABILIZATION	SY	15	
DF18314.2045481	0241000000-E	GENERIC GRADING ITEM	SY	620	GEOTEXTILE FOR ROCK EMBANKMENTS, TYPE 2
DF18314.2045481	0314000000-E	SELECT MATERIAL, CLASS *****	TON	410	(VII)
DF18314.2045481	1330000000-E	INCIDENTAL MILLING	SY	140	
DF18314.2045481	1491000000-E	ASPHALT CONC BASE COURSE, TYPE B25.0C	TON	50	
DF18314.2045481	1519000000-E	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	TON	50	
DF18314.2045481	1575000000-E	ASPHALT BINDER FOR PLANT MIX	TON	10	
DF18314.2045481	3642000000-E	RIP RAP, CLASS A	TON	13	
DF18314.2045481	3649000000-E	RIP RAP, CLASS B	TON	28	
DF18314.2045481	3656000000-E	GEOTEXTILE FOR DRAINAGE	SY	66	
DF18314.2045481	4400000000-E	WORK ZONE SIGNS (STATIONARY)	SF	48	
DF18314.2045481	4405000000-E	WORK ZONE SIGNS (PORTABLE)	SF	124	
DF18314.2045481	4424500000-N	TEMPORARY PORTABLE TRAFFIC SIGNAL SYSTEM	EA	0.4	
DF18314.2045481	4430000000-N	DRUMS	EA	21	
DF18314.2045481	4685000000-E	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	LF	400	
DF18314.2045481	4835000000-E	PAINT PAVEMENT MARKING LINES (24")	LF	40	
DF18314.2045481	6000000000-E	TEMPORARY SILT FENCE	LF	370	
DF18314.2045481	6006000000-E	STONE FOR EROSION CONTROL, CLASS A	TON	21	
DF18314.2045481	6009000000-E	STONE FOR EROSION CONTROL, CLASS B	TON	59	
DF18314.2045481	6012000000-E	SEDIMENT CONTROL STONE	TON	28	
DF18314.2045481	6015000000-E	TEMPORARY MULCHING	ACR	0.3	
DF18314.2045481	6018000000-E	SEED FOR TEMPORARY SEEDING	LB	15	
DF18314.2045481	6021000000-E	FERTILIZER FOR TEMPORARY SEEDING	TON	0.1	
DF18314.2045481	6024000000-E	TEMPORARY SLOPE DRAINS	LF	26	
DF18314.2045481	6029000000-E	SAFETY FENCE	LF	19	
DF18314.2045481	6030000000-E	SILT EXCAVATION	CY	73	
DF18314.2045481	6036000000-E	MATTING FOR EROSION CONTROL	SY	500	
DF18314.2045481	6037000000-E	COIR FIBER MAT	SY	5	
DF18314.2045481	6042000000-E	1/4" HARDWARE CLOTH	LF	42	
DF18314.2045481	6084000000-E	SEEDING & MULCHING	ACR	0.8	
DF18314.2045481	6087000000-E	MOWING	ACR	0.6	
DF18314.2045481	6090000000-E	SEED FOR REPAIR SEEDING	LB	3	
DF18314.2045481	6093000000-E	FERTILIZER FOR REPAIR SEEDING	TON	0.1	
DF18314.2045481	6096000000-E	SEED FOR SUPPLEMENTAL SEEDING	LB	19	

DF18314.2045481	6108000000-E	FERTILIZER TOPDRESSING	TON	0.6
DF18314.2045481	6114500000-N	SPECIALIZED HAND MOWING	MHR	1
DF18314.2045481	6117000000-N	RESPONSE FOR EROSION CONTROL	EA	2
DF18314.2045481	6132000000-N	GENERIC EROSION CONTROL ITEM	EA	1 PREFABRICATED CONCRETE WASHOUT