DocuSign Envelope ID: 7E43F06D-C2FB-463B-B185-F7A7DBD0548D

CONTRACT NO.: DN00171 PROJECT: 17BP.14.R.38

PROJECT NO.	SHEET NO.
17BP.14.R.38	SIGN-1

APPROVED: DocuSigned by: George Karageorge D37A835A67FF4AD...

DATE: 8/3/2016

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 042065 ENGINEER GEORGE M. KARAGEORGE

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

SIGNING PLANS
CLAY COUNTY

LOCATION: BRIDGE NO. 78 ON SR 1318 (JULIA BUCKNER ROAD) OVER PERKINS MILL CREEK

GENERAL NOTES

- SIGNS FURNISHED BY CONTRACTOR
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING. SEE TRANSPORTATION MANAGEMENT PLANS.
- WHEN NOT STATIONED OR DIMENSIONED ON PLANS, ALL 'E' SIGNS SHALL BE FIELD LOCATED BY THE ENGINEER
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT LIMITS SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- THE BACKGROUND FOR TYPE E SIGNS SHALL BE TYPE C REFLECTIVE SHEETING.

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1264.01	OBJECT MARKERS - TYPES
1264.02	OBJECT MARKERS - INSTALLATION

SUMMARY OF QUANTITIES

ITEM NO. DESC. NO.	ITEM NO. SECT. NO.	ITEM DESCRIPTION	QUANTITY	UNIT
4155000000	907	DISPOSAL OF SIGN SYSTEM, U-CHANNEL.....	8	EA.
4915000000	1264	7' U-CHANNEL POSTS.....	4	EA.
4957000000	1264	OBJECT MARKERS (TYPE 3).....	4	EA.

401 QUANTITY REQ'D 2

12 x 36
OM-3R

ONE "U" POST PER SIGN

402 QUANTITY REQ'D 2

12 x 36
OM-3L

ONE "U" POST PER SIGN

SIGNING DETAIL



INDEX

SHEET NO.	DESCRIPTION
SIGN-1	TITLE SHEET AND SIGN DETAIL

PLAN PREPARED BY:

GEORGE M. KARAGEORGE, P.E. SENIOR TRANSPORTATION ENGINEER

ROSI R. HENNEIN TRANSPORTATION DESIGNER

Stantec

Stantec Consulting Services Inc.
801 Jones Franklin Road-Suite 300
Raleigh, NC 27606
Tel. 919.851.6866
Fax. 919.851.7024
www.stantec.com
License No. F-0672

8/3/2016
U:\Clay78\Traffic\Signing\CADD\Signing_Layout_Plans\17BP.14.R.38_sign_01.dgn
rgentry