



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

October 26, 2022

ADDENDUM # 1

To: Plan Holders

From: Wes Jamison, P.E.

DS


Division Project Development Engineer

RE: **Revised Access to ebsx files, Addition of Provisions and Associated Pay Items**

Contract ID: DN00466

County: Transylvania

Letting Date: November 8, 2022

The above contract has experienced the following revisions:

1. The ebsx file for this proposal was inadvertently uploaded to the Bid Express website. Since this proposal is to be a traditional paper bid submittal with electronic submission, the ebsx file was pulled down from Bid Express and uploaded to the NCDOT Bidding & Letting website for you to access. Be sure to carefully read and follow the "Instructions to Bidders" in the proposal, regarding your bid submission.
2. At the top of page EC-8 of the proposal, insert the provision titled Litter Removal (Mowing Areas Only). See the attached provision.
3. The following pay items have been added to the proposal:
 - a. 6114800000-N, MANUAL LITTER REMOVAL, 2 MHR
 - b. 6114900000-E, LITTER DISPOSAL, 0.1 TON(See attached revised bid items sheets T-1 thru T-3).
4. Please access ebsx addenda file on NCDOT Bidding & Letting website.

Thank you for your attention to this matter.

Litter Removal (Mowing Areas Only):

(07-19-22)

Description

This work consists of the pickup, removal, and disposal of litter from roadsides within the construction project prior to mowing operations.

Construction Methods

Provide labor, equipment and materials necessary for the pickup and removal of litter from non-construction sources and the disposal of same into state approved landfills. The Contractor shall abide by all ordinances, laws and regulations regarding disposal of litter and recycling of eligible materials. Wastes generated from construction activities shall be managed as provided elsewhere in the contract. Litter items may consist of any item not considered normal to the right-of-way, including but not limited to, varied sizes of bottles, cans, paper, tires, tire pieces, lumber, vehicle parts, building supplies, metals, household furnishings, cardboard, plastics, ladders, brush and other items not considered normal to the right of way. Litter removal shall be performed in designated areas within five days prior to any mowing operations and as directed by the Engineer. Designated areas shall include vegetated medians and shoulders within the project limits including all interchange ramps and other areas to be mown. Designated areas may be omitted for litter removal by the Engineer due to safety concerns.

The Contractor shall provide adequate personnel and materials to collect and remove litter. The Contractor shall be responsible for locating and utilizing approved local landfills and recycling facilities. Refer to Section 105-27 of the *Standard Specifications* for potential hazardous materials. All collected litter shall be containerized immediately and kept off the traveled portions of the roadway, shoulders, and rights-of-way (including paved shoulders). All collected litter that is small enough to be placed in a bag shall be bagged immediately. All collected litter that is too large for a bag shall be placed into a vehicle. Extended storage or stockpiling of collected litter and recyclables will not be permitted.

The Contractor's personnel shall dispose of any litter in a landfill approved by North Carolina Division of Waste Management. The Contractor will not be allowed to use NCDOT accounts at the landfills/recycling centers nor be allowed to dispose of the litter in NCDOT trash containers on any NCDOT property.

The Contractor shall report online the number of bags of litter and any recycling on the NCDOT Litter Management Website on the date of the pickup at the following website:

<https://apps.ncdot.gov/LM>

An access code ('Pickup Key') for the online reporting portal may be obtained via emailing the Roadside Environmental Unit Litter Management Section at ncdot.clr@ncdot.gov. The Contractor shall request access to the litter removal reporting website prior to starting initial litter collection operations.

Measurement and Payment

The quantity of litter removal to be performed will be affected by the actual conditions that occur during construction of the project. The quantity of litter removal may be increased, decreased, or eliminated entirely as directed by the Engineer. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

Manual Litter Removal will be measured and paid as the actual number of man hours each worker spends picking up litter. Such price and payment will be full compensation for all litter removal work covered by *Litter Removal*, including, but not limited to, furnishing all materials, labor, equipment, transport, reporting, and incidentals necessary to accomplish the work.

Litter Disposal will be measured and paid for by the actual number of tons of litter collected and properly disposed of at a state approved landfill. Such price and payment will be full compensation for all fees, labor, transport, and incidentals necessary to dispose of collected litter associated with *Litter Removal*.

All traffic control necessary to provide a safe work area for *Litter Removal* shall be paid for as specified elsewhere in the contract.

Payment will be made under:

Pay Item	Pay Unit
Manual Litter Removal	MHR
Litter Disposal	TON

County: TRANSYLVANIA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	3420000000-E	SP	GENERIC GUARDRAIL ITEM WEATHERING STEEL GUARDRAIL	1,325 LF		
0006	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED ADDITIONAL GUARDRAIL POSTS	10 EA		
0007	3435000000-N	SP	GENERIC GUARDRAIL ITEM PAINTED GALVANIZED GUARDRAIL ANCHOR UNITS, TYPE TL-2	1 EA		
0008	3649000000-E	876	RIP RAP, CLASS B	6 TON		
0009	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	108 SY		
0010	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	Lump Sum	L.S.	
0011	6000000000-E	1605	TEMPORARY SILT FENCE	150 LF		
0012	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	50 TON		
0013	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	50 TON		
0014	6012000000-E	1610	SEDIMENT CONTROL STONE	15 TON		
0015	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0016	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0017	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		

County: TRANSYLVANIA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0019	6029000000-E	SP	SAFETY FENCE	260 LF		
0020	6030000000-E	1630	SILT EXCAVATION	60 CY		
0021	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,000 SY		
0022	6037000000-E	SP	COIR FIBER MAT	100 SY		
0023	6042000000-E	1632	1/4" HARDWARE CLOTH	10 LF		
0024	6046000000-E	1636	TEMPORARY PIPE FOR STREAM CROSSING (15")	25 LF		
0025	6071010000-E	SP	WATTLE	250 LF		
0026	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0027	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0028	6087000000-E	1660	MOWING	3 ACR		
0029	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0030	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0031	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0032	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0033	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0034	6123000000-E	1670	REFORESTATION	1 ACR		

T-3 for ADD 1

Oct 26, 2022 1:47 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DN00466

Page 3 of 3

County: TRANSYLVANIA

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	6114800000-N	SP	MANUAL LITTER REMOVAL	2 MHR		
0036	6114900000-E	SP	LITTER DISPOSAL	0.1 TON		

1347/Oct26/Q7835.35/D179664730000/E36

Total Amount Of Bid For Entire Project :