DocuSign Envelope ID: 3999AB71-587E-4721-BE6E-7C3BE770A740

5/14/99

PROJECT REFERENCE NO.	SHEET NO.
SM-6114C	2A

ROADWAY DESIGN ENGINEER

9/1/2022

NORTH CAROLINA PROFESSIONAL SEAL 17355 ENGINEER

DocuSigned by: 8F80A4CE27EF455...

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

PAVEMENT SCHEDULE

C1	PROP. APPROX. 1.5" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C AT AN AVERAGE RATE OF 168 LBS. SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5C AT AN AVERAGE RATE OF 168 LBS. SQ. YD. IN EACH OF TWO LAYERS
D	PROP. APPROX. 4" ASPHALT CONCRETE INTERMEDIATE COURSE. TYPE I19.0C AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E	PROP. APPROX. 6" ASPHALT CONCRETE INTERMEDIATE COURSE. TYPE B25.0C AT AN AVERAGE RATE OF 684 LBS. PER SQ. YD.
R	PROPOSED 2' - 6" CURB AND GUTTER, HIGH EARLY STRENGTH CONCRETE
S	5' CONCRETE SIDEWALK
T	EARTH MATERIAL
U	EXISTING PAVEMENT
V1	1.5" MILLING



TYPICAL SECTION NO. 1

–Y– STA. 12+00.00 to –Y– STA 15+45.00



DETAIL NO. 1

–L– MEDIAN ISLAND 12+04.57 TO 13+76.26



TYPICAL SECTION NO. 2

–L– STA. 12+37.80 to –L– STA 12+88.31

8/26/2022 10:00:09 AM
Project: C:\Users\47849\rdy_2A.dgn
User: 47849