DocuSign Envelope ID: AE4F0AAE-3908-4873-B918-0496A5DF75CC

8/17/99

PROJECT REFERENCE NO.	SHEET NO.
EB-5926	1A
MAGGIE VALLEY	HAYWOOD COUNTY

ROADWAY DESIGN ENGINEER

NORTH CAROLINA PROFESSIONAL SEAL 15424 ENGINEER ALLISON C. JOHNSON

DocuSigned by: Allison C. Johnson 1/31/2022
F0B1A872C45F4D6...

Plans Prepared By:

AMERICAN Engineering
8008 CORPORATE CENTER DRIVE, SUITE 110
CHARLOTTE, NORTH CAROLINA 28226
NC Lic. No. C-3881

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

INDEX OF SHEETS

SHEET NUMBER	SHEET
1	TITLE SHEET
1A	INDEX OF SHEETS
1B	CONVENTIONAL SYMBOLS
2A-1 THRU 2A-2	PAVEMENT SCHEDULE AND ROADWAY DETAILS
4 THRU 8	PLAN SHEETS
TMP-1 THRU TMP-2	TRANSPORTATOIN MANAGEMENT PLANS
PMP-1 THRU PMP-2	PAVEMENT MARKING PLANS
EC-1 THRU EC-3	EROSION CONTROL PLANS
LS-1 THRU LS-5	LANDSCAPING PLANS
SIGN-1 THRU SIGN-4	SIGNING PLANS
SIG-1 THRU SIG-7	SIGNAL PLANS

GENERAL NOTES

GENERAL NOTES:

2018 SPECIFICATIONS
EFFECTIVE: 01-16-2018
REVISED:

DRIVEWAYS:

DRIVEWAYS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. 848.03 AT LOCATIONS SHOWN ON PLANS OR AS DIRECTED BY THE ENGINEER.

STREET TURNOUT:

STREET RETURNS SHALL BE CONSTRUCTED IN ACCORDANCE WITH STD. NO. 848.04 USING THE RADII NOTED ON PLANS.

CURB RAMPS:

CURB RAMPS ARE SHOWN ON THE PLANS AT APPROXIMATE LOCATIONS. CONSTRUCT ALL CURB RAMPS ACCORDANCE WITH STD 848.05 and/or 848.06.

STANDARD DRAWINGS

EFF. 01-16-2018

2018 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in "Roadway Standard Drawings" Highway Design Branch - N. C. Department of Transportation - Raleigh, N. C., Dated January, 2018 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 - EARTHWORK	
200.02	Method of Clearing - Method II
225.02	Guide for Grading Subgrade - Secondary and Local
DIVISION 6 - ASPHALT BASES AND PAVEMENTS	
654.01	Pavement Repairs
DIVISION 8 - INCIDENTALS	
848.01	Concrete Sidewalk
848.02	Driveway Turnout - Radius Type
848.03	Driveway Turnout - Drop Curb Type
848.04	Street Trunout
848.05	Curb Ramp - Proposed Curb & Gutter
848.06	Curb Ramp - Existing Curb & Gutter
852.01	Concrete Islands
852.10	Median Construction - with Curb and Gutter

1/31/2022
W:\AMERICAN EA\PROJECTS\NCDOT\Maggie Valley\Roadway\Plan Sheets\EB-5926_Rdy_tsh_1a.dgn
dbright