DocuSign Envelope ID: E197B1CF-38FC-4ED3-8F8A-8F73CFDDFDA7

PROJECT REFERENCE NO.	SHEET NO.
EB-5926	SIGN-1

APPROVED: DocuSigned by: Allison C. Johnson FD81A672C45F4D6...

DATE: 2/9/2022

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 15424 ENGINEER ALLISON C. JOHNSON

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

SIGNING PLANS

HAYWOOD COUNTY

LOCATION: US 19, SOCO ROAD, MAGGIE VALLEY, NC (FROM FIE TOP ROAD TO MOODY FARMS ROAD)

INDEX OF SHEETS

SHEET NO.	TITLE
SIGN-1	SIGNING PLAN TITLE SHEET
SIGN-2	TYPE 'E' AND 'F' SIGNS
SIGN-3	SIGNING PLAN
SIGN-4	SIGNING PLAN

ROADWAY STANDARD DRAWINGS

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
901.50	ARROWS AND SHIELDS
903.10	GROUND MOUNTED SIGN SUPPORTS
904.10	ORIENTATION OF GROUND MOUNTED SIGNS
904.50	MOUNTING OF TYPE 'D', 'E' AND 'F' SIGNS ON 'U' CHANNEL POSTS

GENERAL NOTES

- SIGNS FURNISHED BY STATE
- IF REMOVAL OR RELOCATION OF SIGNS ON PRIVATE STREET (NON-STATE MAINTAINED) IS REQUIRED DUE TO CONSTRUCTION, THE CONTRACTOR SHALL INFORM THE ENGINEER. THE WORK WILL BE COMPLETED BY OTHERS.
- ALL TYPE 'D' SIGNS SHALL BE MOUNTED ON TWO U-CHANNEL POSTS UNLESS OTHERWISE INDICATED ON THE PLANS.
- SIGNING PLANS DO NOT INCLUDE TEMPORARY CONSTRUCTION SIGNING OR PAVEMENT MARKINGS.
- WHEN NOT STATION OR DIMENSIONED ON PLANS, ALL 'E' AND 'F' SIGNS SHALL BE FIELD LOCATED BY THE ENINGEER.
- WHEN EXISTING SIGNS ARE REMOVED AND INSTALLED ON NEW SUPPORTS, THE RE-ERECTION SHALL IMMEDIATELY FOLLOW THE REMOVAL.
- ALL EXISTING SIGNS ON "U" CHANNEL POST WITHIN THE PROJECT SHALL BE REMOVED AND DISPOSED OF UNLESS OTHERWISE NOTED ON PLANS.
- THE BACKGROUND FOR TYPE 'E' & 'F' SIGNS SALL BE TYPE C RFLECTIVE SHEETING.

PROJECT NOTES

1. DISPOSAL OF SIGN SYSTEM, U-CHANNEL.
2. SIGN ERECTION, TYPE E AND F.

SUMMARY OF QUANTITIES

ITEM NO.		ITEM DESCRIPTION	QUANTITY	UNIT
DESC. NO.	SECT. NO.			
4072000000-E	903	SUPPORTS, 3-LB. STEEL U-CHANNEL	803	LF
4102000000-N	904	SIGN ERECTION, TYPE E	155	EA
4116100000-N	904	SIGN ERECTION, RELOCATE TYPE E (GROUND MOUNTED)	28	EA

ALLISON C. JOHNSON, P.E.
PROJECT ENGINEER

BENJAMIN C. PICKERING II, P.E.
PROJECT DESIGN ENGINEER

AMERICAN Engineering
8008 CORPORATE CENTER DRIVE, SUITE 110
CHARLOTTE, NORTH CAROLINA 28226
NC Lic. No. C-3881