DocuSign Envelope ID: 4BE41BF2-04B9-4133-B237-93AF74C900F1

(401) QUANTITY REQ'D. 94
(RELOCATE 28)

W11-2
36" X 36"

* FLUORESCENT YELLOW-GREEN BACKGROUND
ONE "U" POST PER SIGN

(402) QUANTITY REQ'D. 38
(RELOCATE 14)

W16-7pR
30" X 18"

* FLUORESCENT YELLOW-GREEN BACKGROUND
ONE "U" POST PER SIGN

(403) QUANTITY REQ'D. 28
(RELOCATE 14)

W16-7pL
30" X 18"

* FLUORESCENT YELLOW-GREEN BACKGROUND
ONE "U" POST PER SIGN

(404) QUANTITY REQ'D. 28

W16-9p
24" X 12"

* FLUORESCENT YELLOW-GREEN BACKGROUND
ONE "U" POST PER SIGN

(405) QUANTITY REQ'D. 1

R1-1
30" X 30"

ONE "U" POST PER SIGN

(406) QUANTITY REQ'D. 28

R1-5L
36" X 36"

ONE "U" POST PER SIGN

(407) QUANTITY REQ'D. 8
(RELOCATE 6)

R1-6
12"X36"

* FLUORESCENT YELLOW-GREEN BACKGROUND
ONE "U" POST PER SIGN

(408) QUANTITY REQ'D. 1

R4-7
24" X 30"

ONE "U" POST PER SIGN

(409) QUANTITY REQ'D. 38

R10-25
9"x12"

ONE "U" POST PER SIGN

PROJECT REFERENCE NO.	SHEET NO.
EB-5926	SIGN-2
MAGGIE VALLEY HAYWOOD COUNTY	

APPROVED: DocuSigned by: Allison C. Johnson FD81A672C45F4D6...

DATE: 2/11/2022

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 15424 ENGINEER ALLISON C. JOHNSON

Plans Prepared By:

AMERICAN Engineering
8008 CORPORATE CENTER DRIVE, SUITE 110
CHARLOTTE, NORTH CAROLINA 28226
NC Lic. No. C-3881

DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED

SIGNING PLAN