DocuSign Envelope ID: F628CEDE-11E1-47E7-AC47-A605CA743511

| TIP NO. | SHEET NO. |
|---|---|
| 17BP.14.R.149 | PMP-1 |

APPROVED: DocuSigned by: Lloyd D. Brown 33054DF17F5746B...

DATE: 7/15/2021

NORTH CAROLINA PROFESSIONAL SEAL 20119 ENGINEER LLOYD D. BROWN

**DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED**

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

# PAVEMENT MARKING PLAN
# JACKSON COUNTY
## LOCATION : BRIDGE NO. 490185 OVER JONES CREEK ON SR 1705 (DARK RIDGE ROAD)

### ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS SHOWN IN "ROADWAY STANDARD DRAWINGS" - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2018 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

| STD. NO. | TITLE |
|---|---|
| 1205.01 | PAVEMENT MARKINGS - LINE TYPES AND OFFSETS |
| 1205.02 | PAVEMENT MARKINGS - TWO LANE & MULTILANE ROADWAYS |
| 1205.12 | PAVEMENT MARKINGS - BRIDGES |
| 1261.01 | GUARDRAIL AND BARRIER DELINEATORS - INSTALLATION SPACING |
| 1261.02 | GUARDRAIL AND BARRIER DELINEATORS - TYPES & MOUNTING |
| 1262.01 | GUARDRAIL END DELINEATION |

### GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE

| ROAD NAME: | MARKING | MARKER |
|---|---|---|
| SR 1705 (DARK RIDGE ROAD) | PAINT | NONE |

B) PLACE TWO APPLICATIONS OF PAINT PAVEMENT MARKINGS ON THE FINAL WEARING SURFACE. PLACE THE SECOND APPLICATION OF PAINT UPON SUFFICIENT DRYING TIME OF THE FIRST.

C) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

D) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

E) PASSING ZONES WILL BE DETERMINED IN THE FIELD AND MUST BE APPROVED BY THE ENGINEER.

### INDEX


| SHEET NO. | DESCRIPTION |
|---|---|
| PMP-1 | PAVEMENT MARKING PLAN TITLE SHEET |
| PMP-2 | PAVEMENT MARKING DETAIL AND SCHEDULE |


### LEGEND

GENERAL

NORTH ARROW

PAVEMENT MARKINGS

EXISTING LINES

PERMANENT LINES


V&M Vaughn & Melton Consulting Engineers
Asheville, North Carolina 828-253-2796
Raleigh, NC 919-977-9455
Charlotte, NC 704-357-0488
Boone, NC 828-355-9933
Tri-Cities, TN 423-467-8401
Knoxville, TN 865-546-5800
Spartanburg, SC 864-574-4775
Charleston, SC 843-974-5650
Middlesboro, KY 606-248-6600
Atlanta, GA 770-627-3509

Copyright © 2006 Vaughn & Melton, Inc. All Rights Reserved

TRANSPORTATION ENGINEER LLOYD D. BROWN, P.E.

TRANSPORTATION DESIGN ENGINEER C. GONZALEZ-MARTELL

PROJECT: 17BP.14.R.149

CONTRACT: DN00468

09/08/99

7/1/2021 11:49:54 AM
V:\Asheville\Transportation\3631-06 Jackson I85 - 17BP.14.R.149\Traffic\TrafficControl\TCP\490185_PMP-1.dgn
User:amfitzpatrick